

PLAT NO. 21-11800597

SUBDIVISION PLAT
ESTABLISHING

ALTURA AT TEZEL DUPLEXES

BEING A TOTAL OF 4.633 ACRES, ESTABLISHING LOT 132, N.C.B. 15008,
BEING ALL OF A CALLED 4.622 ACRES RECORDED IN DOCUMENT NO.
20210255636, OFFICIAL PUBLIC RECORDS OF BEXAR COUNTY, TEXAS.

SCALE: 1"=60'

**UP**
ENGINEERING
+ SURVEYING111 TOWER DRIVE, SUITE 325
SAN ANTONIO, TX 78232 TEL: 210-774-5594
WWW.UPENGINEERING.COM TBPES F-17992
TBPES F-10194606STATE OF TEXAS
COUNTY OF COLLIN
THE OWNER OF LAND SHOWN ON THIS PLAT, IN PERSON OR THROUGH A DULY AUTHORIZED
AGENT, DEDICATES TO THE USE OF THE PUBLIC, EXCEPT AREAS IDENTIFIED AS PRIVATE OR
PART OF AN ENCLAVE OR PLANNED UNIT DEVELOPMENT, FOREVER ALL STREETS, ALLEYS,
PARKS, WATERCOURSES, DRAINS, EASEMENTS AND PUBLIC PLACES THEREON SHOWN FOR
THE PURPOSE AND CONSIDERATION THEREIN EXPRESSED.OWNER/DEVELOPER:
BOOLE DEVELOPERS LLC
3324 NEIMAN RD
PLANO, TX 75025
MURARI APPANSTATE OF TEXAS
COUNTY OF COLLIN
BEFORE ME, THE UNDERSIGNED AUTHORITY ON THIS DAY PERSONALLY APPEAREDMURARI APPAN KNOWN TO ME TO BE THE PERSON
WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT, AND ACKNOWLEDGED TO
ME THAT HE EXECUTED THE SAME FOR THE PURPOSES AND CONSIDERATIONS THEREIN
EXPRESSED AND IN THE CAPACITY THEREIN STATED.

GIVEN UNDER MY HAND AND SEAL OF OFFICE THIS 2nd

DAY OF July A.D. 2024

NOTARY PUBLIC COLLIN COUNTY, TEXAS

THIS PLAT OF ALTURA AT TEZEL DUPLEXES HAS BEEN SUBMITTED
TO AND CONSIDERED BY THE PLANNING COMMISSION OF THE CITY OF SAN ANTONIO, TEXAS,
AND IS HEREBY APPROVED BY SUCH COMMISSION IN ACCORDANCE WITH STATE OR LOCAL
LAWS AND REGULATIONS; AND/OR WHERE ADMINISTRATIVE EXCEPTION(S) AND/OR
VARIANCE(S) HAVE BEEN GRANTED.

DATED THIS DAY OF A.D.

BY: CHAIRMAN

BY: SECRETARY

CPS/SAWS/COSA UTILITY NOTES:

- THE CITY OF SAN ANTONIO AS A PART OF ITS ELECTRIC, GAS, WATER AND WASTEWATER SYSTEMS - CITY PUBLIC SERVICES BOARD (CPS ENERGY) AND SAN ANTONIO WATER SYSTEMS (SAWS) - IS HEREBY DEDICATED EASEMENTS AND RIGHTS-OF-WAY FOR UTILITY, TRANSMISSION AND DISTRIBUTION INFRASTRUCTURE AND SERVICE FACILITIES IN THE AREAS DESIGNATED ON THIS PLAT AS "ELECTRIC EASEMENT", "ANCHOR EASEMENT", "SERVICE EASEMENT", "OVERHANG EASEMENT", "UTILITY EASEMENT", "GAS EASEMENT", "TRANSFORMER EASEMENT", "WATER EASEMENT", "SANITARY SEWER EASEMENT" AND/OR "RECYCLED WATER EASEMENT" FOR THE PURPOSE OF INSTALLING, CONSTRUCTING, RECONSTRUCTING, MAINTAINING, REMOVING, INSPECTING, PATROLLING AND ERECTING UTILITY INFRASTRUCTURE AND SERVICE FACILITIES FOR THE REASONS DESCRIBED ABOVE. CPS ENERGY AND SAWS SHALL ALSO HAVE THE RIGHT TO RELOCATE SAID INFRASTRUCTURE AND SERVICE FACILITIES WITHIN EASEMENT AND RIGHT-OF-WAY AREAS, TOGETHER WITH THE RIGHT OF INGRESS AND EGRESS OVER GRANTOR'S ADJACENT LANDS FOR THE PURPOSE OF ACCESSING SUCH INFRASTRUCTURE AND SERVICE FACILITIES AND THE RIGHT TO REMOVE FROM SAID LANDS ALL TREES OR PARTS THEREOF, OR OTHER OBSTRUCTIONS WHICH ENDANGER OR MAY INTERFERE WITH THE EFFICIENCY OF WATER, SEWER, GAS, AND/OR ELECTRIC INFRASTRUCTURE AND SERVICE FACILITIES. NO BUILDINGS, STRUCTURES, CONCRETE SLABS, OR WALLS WILL BE PLACED WITHIN EASEMENT AREAS WITHOUT AN ENCROACHMENT AGREEMENT WITH THE RESPECTIVE UTILITY.
- ANY CPS ENERGY OR SAWS MONETARY LOSS RESULTING FROM MODIFICATIONS REQUIRED OF CPS ENERGY OR SAWS INFRASTRUCTURE AND SERVICE FACILITIES, LOCATED WITHIN SAID EASEMENTS, DUE TO GRADE CHANGES OR GROUND ELEVATION ALTERATIONS SHALL BE CHARGED TO THE PERSON OR PERSONS DEEMED RESPONSIBLE FOR SAID GRADE CHANGES OR GROUND ELEVATION ALTERATIONS.
- THIS PLAT DOES NOT AMEND, ALTER, RELEASE OR OTHERWISE AFFECT ANY EXISTING ELECTRIC, GAS, WATER, SEWER, DRAINAGE, TELEPHONE, CABLE TV EASEMENTS OR ANY OTHER EASEMENTS FOR UTILITIES UNLESS THE CHANGES TO SUCH EASEMENTS ARE DESCRIBED HEREON.

DRAINAGE NOTE:

- NO STRUCTURE, FENCES, WALLS OR OTHER OBSTRUCTIONS THAT IMPEDE DRAINAGE SHALL BE PLACED WITHIN THE LIMITS OF THE DRAINAGE EASEMENTS SHOWN ON THIS PLAT. NO LANDSCAPING OR OTHER TYPE OF MODIFICATIONS, WHICH ALTER THE CROSS-SECTIONS OF THE DRAINAGE EASEMENTS, AS APPROVED, SHALL BE ALLOWED WITHOUT THE APPROVAL OF THE DIRECTOR OF TOI OR DIRECTOR OF PUBLIC WORKS. THE CITY OF SAN ANTONIO AND BEXAR COUNTY SHALL HAVE THE RIGHT TO INGRESS AND EGRESS OVER THE GRANTOR'S ADJACENT PROPERTY TO REMOVE ANY IMPEDING OBSTRUCTIONS PLACED WITHIN THE LIMITS OF SAID DRAINAGE EASEMENT AND TO MAKE ANY MODIFICATIONS OR IMPROVEMENTS WITHIN SAID DRAINAGE EASEMENTS.

SAWS NOTES:

- WASTEWATER EDU NOTE: THE NUMBER OF WASTEWATER EQUIVALENT DWELLING UNITS (EDU'S) PAID FOR THIS SUBDIVISION PLAT ARE KEPT ON FILE UNDER THE PLAT NUMBER AT THE SAN ANTONIO WATER SYSTEM.
- THE OWNER DEDICATES THE PUBLIC PORTION OF THE SANITARY SEWER MAIN TO THE SAN ANTONIO WATER SYSTEM UPON COMPLETION BY THE DEVELOPER AND ACCEPTANCE BY THE SAN ANTONIO WATER SYSTEM. ALL ON-SITE SANITARY SEWER INFRASTRUCTURE IS TO BE PRIVATELY OWNED AND MAINTAINED.
- SAWS HIGH PRESSURE NOTE: A PORTION OF THIS TRACT IS BELOW THE GROUND ELEVATION OF 927 FEET WHERE THE STATIC PRESSURE WILL NORMALLY EXCEED 80 PSI. AT ALL SUCH LOCATIONS, THE DEVELOPER OR BUILDER SHALL INSTALL AT EACH LOT, ON THE CUSTOMER'S SIDE OF THE WATER METER, AN APPROVED TYPE PRESSURE REGULATOR IN CONFORMANCE WITH THE PLUMBING CODE OF THE CITY OF SAN ANTONIO.
- IMPACT FEE NOTE: WATER AND/OR WASTEWATER IMPACT FEES WERE NOT PAID AT THE TIME OF PLATTING FOR THIS PLAT. ALL IMPACT FEES MUST BE PAID PRIOR TO WATER METER SET AND/OR WASTEWATER SEWER SERVICE CONNECTION.
- INGRESS & EGRESS (WATER) THE SAN ANTONIO WATER SYSTEM IS HEREBY GRANTED THE RIGHT OF INGRESS AND EGRESS ACROSS GRANTOR'S ADJACENT PROPERTY TO ACCESS THE WATER EASEMENT(S) SHOWN ON THIS PLAT.
- FIRE FLOW NOTE: THE PUBLIC WATER MAIN SYSTEM HAS BEEN DESIGNED FOR A MINIMUM FIRE FLOW DEMAND OF 1000 GPM AT 25 PSI RESIDUAL PRESSURE TO MEET THE CITY OF SAN ANTONIO'S FIRE FLOW REQUIREMENTS FOR THE RESIDENTIAL DEVELOPMENT. THE FIRE FLOW REQUIREMENTS FOR INDIVIDUAL STRUCTURES WILL BE REVIEWED PRIOR TO BUILDING PERMIT APPROVAL IN ACCORDANCE WITH THE PROCEDURES SET FORTH BY THE CITY OF SAN ANTONIO DIRECTOR OF DEVELOPMENT SERVICES AND THE SAN ANTONIO FIRE DEPARTMENT FIRE MARSHAL.

SURVEY NOTE:


- BASIS OF BEARINGS IS THE TEXAS STATE PLANE COORDINATE SYSTEM, NAD 1983, SOUTH CENTRAL ZONE (4204). ALL COORDINATES AND DISTANCES SHOWN HEREON ARE GRID DISTANCES.
 - NO PORTION OF THE FEMA 1% ANNUAL CHANCE (100-YEAR) FLOODPLAIN EXISTS WITHIN THIS PLAT AS VERIFIED BY FEMA MAP PANEL 480303060, EFFECTIVE DATE OF 09/29/2019. FLOODPLAIN INFORMATION IS SUBJECT TO CHANGE AS A RESULT OF FUTURE FEMA MAP REVISIONS AND/OR AMENDMENTS.
- FINISHED FLOOR NOTE:**
- RESIDENTIAL FINISHED FLOOR ELEVATIONS MUST BE A MINIMUM OF 8 INCHES ABOVE FINAL ADJACENT GRADE.
- FIRE ACCESS NOTE:**
- INGRESS AND EGRESS SHALL BE PROVIDED BETWEEN ALL ADJACENT LOTS FOR ADEQUATE FIRE DEPARTMENT VEHICLE ACCESS PER THE CITY OF SAN ANTONIO FIRE CODE. ANY CROSS ACCESS SHALL NOT BE BLOCKED NOR MAY THIS NOTE BE REMOVED FROM THE PLAT WITHOUT WRITTEN PERMISSION FROM THE CITY OF SAN ANTONIO DIRECTOR OF DEVELOPMENT SERVICES AND THE SAN ANTONIO FIRE DEPARTMENT FIRE MARSHAL.

MAINTENANCE NOTE:

- THE MAINTENANCE OF ALL PRIVATE STREETS, OPEN SPACE, GREENBELTS, PARKS, TREE SAVE AREAS, DRAINAGE EASEMENTS AND EASEMENTS OF ANY OTHER NATURE WITHIN THIS SUBDIVISION SHALL BE THE RESPONSIBILITY OF THE PROPERTY OWNERS, OR THE PROPERTY OWNERS' ASSOCIATION, OR ITS SUCCESSORS OR ASSIGNS AND NOT THE RESPONSIBILITY OF THE CITY OF SAN ANTONIO OR BEXAR COUNTY.

TOI DETENTION & MAINTENANCE:

- STORM WATER DETENTION IS REQUIRED FOR PROPERTY WITHIN THE BOUNDARY OF THIS PLAT. BUILDING PERMITS SHALL BE ISSUED ONLY IN CONJUNCTION WITH NECESSARY STORM WATER DETENTION APPROVED BY THE CITY OF SAN ANTONIO FLOODPLAIN ADMINISTRATOR. THE PROPERTY MAY BE ELIGIBLE TO POST A FEE IN LIEU OF DETENTION (FLO) IF OFFSITE DRAINAGE CONDITIONS ALLOW BUT ONLY WHEN APPROVED BY THE CITY OF SAN ANTONIO FLOODPLAIN ADMINISTRATOR. MAINTENANCE OF ON-SITE STORM WATER DETENTION SHALL BE THE SOLE RESPONSIBILITY OF THE PROPERTY OWNERS AND/OR THE PROPERTY OWNERS' ASSOCIATION AND ITS SUCCESSORS OR ASSIGNS AND IS NOT THE RESPONSIBILITY OF THE CITY OF SAN ANTONIO OR BEXAR COUNTY.



LINE TABLE

LINE	BEARING	LENGTH
L1	N00°03'45"E	20.88'
L2	S01°33'58"E	40.54'
L3	S89°24'00"E	111.30'
L4	S89°21'52"E	50.70'
L5	S89°21'52"E	50.63'
L6	N89°21'52"W	102.69'
L7	N00°38'08"E	49.92'
L8	S00°54'42"W	49.50'
L9	N34°43'33"W	23.03'
L10	S89°24'47"E	24.51'
L11	N34°43'33"W	38.62'
L12	N00°38'08"E	48.48'
L13	N00°38'08"E	22.00'
L14	S89°21'52"E	18.94'
L15	N01°33'58"W	50.65'
L16	N00°30'20"E	50.37'
L17	S89°21'52"E	20.00'
L18	S00°30'20"W	50.33'
L19	N01°33'58"W	50.04'
L20	N01°33'58"W	4.20'
L21	N01°33'58"W	19.01'
L22	S89°29'40"E	15.00'
L23	S89°11'17"E	15.00'

CURVE TABLE

CURVE	RADIUS	LENGTH	DELTA	CHORD	CHORD BEARING
C1	657.00'	40.81'	3°33'32"	40.80'	S3°20'44"E
C2	30.00'	18.66'	35°38'15"	18.36'	N16°54'25"W
C3	10.00'	6.17'	35°21'41"	6.07'	N17°02'42"W

LEGEND

- = PROPERTY BOUNDARY
- - - = ADJOINER BOUNDARY
- - - = CENTERLINE
- = FOUND 1/2" IRON PIN (UNLESS NOTED OTHERWISE)
- = 1/2" IRON PIN SET WITH GREEN CAP STAMPED "UP ENG. & SURVEY" (UNLESS OTHERWISE NOTED)
- E.G.T.C. = ELECTRIC, GAS, TELE, & CABLE TV
- E.T.C. = ELECTRIC, TELE & CABLE TV
- O.P.R. = OFFICIAL PUBLIC RECORDS OF BEXAR COUNTY TEXAS
- D.P.R. = DEED AND PLAT RECORDS OF BEXAR COUNTY TEXAS
- N.C.B. = NEW CITY BLOCK
- R.O.W. = RIGHT OF WAY
- 1234/123 = VOLUME/PAGE
- - - 1160 - - - = EXISTING CONTOUR
- - - - - = EXISTING EASEMENT
- - - - - = PROPOSED EASEMENT

STATE OF TEXAS
COUNTY OF BEXAR

I HEREBY CERTIFY THAT PROPER ENGINEERING CONSIDERATION HAS BEEN GIVEN THIS PLAT TO THE MATTERS OF STREETS, LOTS, AND DRAINAGE LAYOUT. TO THE BEST OF MY KNOWLEDGE THIS PLAT CONFORMS TO ALL REQUIREMENTS OF THE UNIFIED DEVELOPMENT CODE, EXCEPT FOR THOSE VARIANCES GRANTED BY THE SAN ANTONIO PLANNING COMMISSION.

RYAN R. PLAGENS, P.E.
LICENSED PROFESSIONAL ENGINEER
TEXAS REGISTRATION NO. 1116407/22/24
DATESTATE OF TEXAS
COUNTY OF BEXAR

I HEREBY CERTIFY THAT THE ABOVE PLAT CONFORMS TO THE MINIMUM STANDARDS SET FORTH BY THE TEXAS BOARD OF PROFESSIONAL ENGINEERS AND LAND SURVEYORS ACCORDING TO AN ACTUAL SURVEY MADE ON THE GROUND BY: UP ENGINEERING + SURVEYING

RICHARD L. NEUBAUER III, R.P.L.S.
REGISTERED PROFESSIONAL LAND SURVEYOR
TEXAS REGISTRATION NO. 68977/22/24
DATE