

LEGEND			
●	FOUND 1/2" IRON ROD	AC.	ACRE
○	FOUND COTTON SPINDLE	NCB	NEW COUNTY BLOCK
○	FOUND PK NAIL IN ROCK	VOL.	VOLUME
○	SET 1/2" IRON ROD WITH A RED	PG.	PAGE
○	"MEALS-MYERS ENG. & SURVEY."	O.P.R.	OFFICIAL PUBLIC RECORDS OF BEXAR COUNTY, TEXAS
○	PLASTIC CAP	D.P.R.	DEED AND PLAT RECORDS OF BEXAR COUNTY, TEXAS
○	FOUND 1/2" IRON ROD WITH A RED	E.G.T.CA.	ELECTRIC, GAS, TELEPHONE, AND CABLE TV EASEMENT
○	"MEALS-MYERS ENG. & SURVEY."	(X.XXX)	NET ACREAGE
○	PLASTIC CAP		
○	CENTERLINE		
○	MIN. F.F.		
○	MINIMUM FINISHED FLOOR		

SURVEY NOTES:

- PROPERTY CORNERS ARE MONUMENTED WITH CAP OR DISK MARKED "MMES PROP CORN" UNLESS NOTED OTHERWISE.
- COORDINATES SHOWN ARE BASED ON THE NORTH AMERICAN DATUM OF 1983 FROM THE TEXAS COORDINATE SYSTEM ESTABLISHED FOR THE SOUTH CENTRAL ZONE DISPLAYED IN GRID VALUES DERIVED FROM THE TRIMBLE VRS NETWORK.
- BEARINGS ARE BASED ON THE NORTH AMERICAN DATUM OF 1983, FROM THE TEXAS COORDINATE SYSTEM ESTABLISHED FOR THE SOUTH CENTRAL ZONE.
- DISTANCES SHOWN HEREON ARE GRID. SCALE FACTOR = GRID X 1.00017 = SURFACE

CPS/SAWS/COSA UTILITY NOTES

- THE CITY OF SAN ANTONIO AS PART OF ITS ELECTRIC, GAS, WATER, AND WASTEWATER SYSTEMS - CITY PUBLIC SERVICE BOARD (CPS ENERGY) AND SAN ANTONIO WATER SYSTEM (SAWS) - IS HEREBY DEDICATED EASEMENTS AND RIGHTS-OF-WAY FOR UTILITY, TRANSMISSION AND DISTRIBUTION INFRASTRUCTURE AND SERVICE FACILITIES IN THE AREAS DESIGNATED ON THIS PLAT AS "ELECTRIC EASEMENT," "ANCHOR EASEMENT," "SERVICE EASEMENT," "OVERHANG EASEMENT," "UTILITY EASEMENT," "GAS EASEMENT," "TRANSFORMER EASEMENT," "WATER EASEMENT," "SANITARY SEWER EASEMENT," AND/OR "RECYCLED WATER EASEMENT" FOR THE PURPOSE OF INSTALLING, CONSTRUCTING, RECONSTRUCTING, MAINTAINING, REMOVING, INSPECTING, PATROLLING, AND ERECTING UTILITY INFRASTRUCTURE AND SERVICE FACILITIES FOR THE REASONS DESCRIBED ABOVE. CPS ENERGY AND SAWS SHALL ALSO HAVE THE RIGHT TO RELOCATE SAID INFRASTRUCTURE AND SERVICE FACILITIES WITHIN EASEMENT AND RIGHT-OF-WAY AREAS, TOGETHER WITH THE RIGHT OF INGRESS AND EGRESS OVER GRANTOR'S ADJACENT LANDS FOR THE PURPOSE OF ACCESSING SUCH INFRASTRUCTURE AND SERVICE FACILITIES AND THE RIGHT TO REMOVE FROM SAID LANDS ALL TREES OR PARTS THEREOF, OR OTHER OBSTRUCTIONS WHICH ENDANGER OR MAY INTERFERE WITH THE EFFICIENCY OF WATER, SEWER, GAS, AND/OR ELECTRIC INFRASTRUCTURE AND SERVICE FACILITIES. NO BUILDINGS, STRUCTURES, CONCRETE SLABS, OR WALLS WILL BE PLACED WITHIN EASEMENT AREAS WITHOUT AN ENCROACHMENT AGREEMENT WITH THE RESPECTIVE UTILITY.
- ANY CPS ENERGY OR SAWS MONETARY LOSS RESULTING FROM MODIFICATIONS REQUIRED OF CPS ENERGY OR SAWS INFRASTRUCTURE AND SERVICE FACILITIES, LOCATED WITHIN SAID EASEMENTS, DUE TO GRADE CHANGES OR GROUND ELEVATION ALTERATIONS SHALL BE CHARGED TO THE PERSON OR PERSONS DEEMED RESPONSIBLE FOR SAID GRADE CHANGES OR GROUND ELEVATION ALTERATIONS.
- THIS PLAT DOES NOT AMEND, ALTER, RELEASE OR OTHERWISE AFFECT ANY EXISTING ELECTRIC, GAS, WATER, SEWER, DRAINAGE, TELEPHONE, CABLE TV EASEMENTS OR ANY OTHER EASEMENTS FOR UTILITIES UNLESS THE CHANGES TO SUCH EASEMENTS ARE DESCRIBED HEREON.
- CONCRETE DRIVEWAY APPROACHES ARE ALLOWED WITHIN THE FIVE (5) AND TEN (10) FOOT WIDE ELECTRIC AND GAS EASEMENTS WHEN LOTS ARE SERVED ONLY BY UNDERGROUND ELECTRIC AND GAS FACILITIES.
- ROOF OVERHANGS ARE ALLOWED WITHIN THE FIVE (5) AND TEN (10) FOOT WIDE ELECTRIC AND GAS EASEMENTS WHEN ONLY UNDERGROUND ELECTRIC AND GAS FACILITIES ARE PROPOSED OR EXISTING WITHIN THOSE FIVE (5) AND TEN (10) FOOT WIDE EASEMENTS.

SAWS WASTEWATER EDU:

THE NUMBER OF WASTEWATER EQUIVALENT DWELLING UNITS (EDU'S) PAID FOR THIS SUBDIVISION PLAT ARE KEPT ON FILE UNDER THE PLAT NUMBER AT THE SAN ANTONIO WATER SYSTEM.

CLEAR VISION:

CLEAR VISION AREAS MUST BE FREE OF VISUAL OBSTRUCTIONS IN ACCORDANCE WITH THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO) POLICY ON GEOMETRIC DESIGN OF HIGHWAYS AND STREETS, OR LATEST VERSION THEREOF.

STATE OF TEXAS
COUNTY OF BEXAR

I HEREBY CERTIFY THAT THE ABOVE PLAT CONFORMS TO THE MINIMUM STANDARDS SET FORTH BY THE TEXAS BOARD OF PROFESSIONAL ENGINEERING & LAND SURVEYING ACCORDING TO AN ACTUAL SURVEY MADE ON THE GROUND BY MEALS-MYERS ENGINEERING & SURVEYING, LLC.

Paul L. Myers
PAUL L. MYERS
REGISTERED PROFESSIONAL LAND SURVEYOR
NO.6490 STATE OF TEXAS - TBPE FIRM #18576 - TBPLS FIRM #10194291

STATE OF TEXAS
COUNTY OF BEXAR

I HEREBY CERTIFY THAT PROPER ENGINEERING CONSIDERATION HAS BEEN GIVEN THIS PLAT TO THE MATTERS OF STREETS, LOTS AND DRAINAGE LAYOUT. TO THE BEST OF MY KNOWLEDGE THIS PLAT CONFORMS TO ALL REQUIREMENTS OF THE UNIFIED DEVELOPMENT CODE, EXCEPT FOR THOSE VARIANCES GRANTED BY THE SAN ANTONIO PLANNING COMMISSION.

Nathan Moreno
NATHAN MORENO
REGISTERED PROFESSIONAL ENGINEER
NO.107581 STATE OF TEXAS

FINISHED FLOOR NOTE:
RESIDENTIAL FINISHED FLOOR ELEVATION SHALL BE A MINIMUM OF EIGHT (8) INCHES ABOVE FINAL ADJACENT GRADE.

SAWS IMPACT FEE:
WATER AND/OR WASTEWATER IMPACT FEE SHALL BE PAID PRIOR TO THE TIME OF PLATTING FOR THIS PLAT. ALL IMPACT FEES MUST BE PAID PRIOR TO SERVICE CONNECTION.

SAWS DEDICATION:
THE OWNER DEDICATES THE SANITARY SEWER AND WATER MAINS TO THE SAN ANTONIO WATER SYSTEM UPON COMPLETION BY THE SAN ANTONIO WATER SYSTEM.

RESIDENTIAL FINISHED FLOOR ELEVATION:
RESIDENTIAL STRUCTURES ARE NOT ALLOWED TO BE CONSTRUCTED AT A FINISHED FLOOR ELEVATION LOWER THAN THE FINISHED FLOOR ELEVATION OF THE ADJACENT LOT. THE FINISHED FLOOR ELEVATION OF THE ADJACENT LOT SHALL BE AT OR ABOVE THE BASE FLOOD ELEVATION. PRE-CONSTRUCTION ELEVATION CERTIFICATES MAY BE REQUIRED PRIOR TO PERMIT APPROVAL, AND POST-CONSTRUCTION ELEVATION CERTIFICATES MAY BE REQUIRED PRIOR TO OCCUPANCY OF RESIDENTIAL BUILDINGS, AS DETERMINED BY THE FLOODPLAIN ADMINISTRATOR OF THE CITY OF SAN ANTONIO.

COMMON AREA MAINTENANCE:
THE MAINTENANCE OF ALL PRIVATE STREETS, OPEN SPACE, GREENBELTS, PARKS, TREE SAVE AREAS, INCLUDING LOT 5, BLOCK 1, CB OR NCB 10917, DRAINAGE EASEMENTS AND EASEMENTS OF ANY OTHER NATURE WITHIN THIS SUBDIVISION SHALL BE THE RESPONSIBILITY OF THE PROPERTY OWNERS, OR ITS SUCCESSORS OR ASSIGNS AND NOT THE RESPONSIBILITY OF THE CITY OF SAN ANTONIO OR BEXAR COUNTY.

DRAINAGE EASEMENT ENCROACHMENTS:
NO STRUCTURE, FENCES, WALLS OR OTHER ENCROACHMENTS SHALL BE PLACED WITHIN THE LIMITS OF THE DRAINAGE EASEMENT. ANY ENCROACHMENTS SHALL BE REMOVED OR MODIFIED TO COMPLY WITH THE DRAINAGE EASEMENT. ANY ENCROACHMENTS SHALL BE REMOVED OR MODIFIED TO COMPLY WITH THE DRAINAGE EASEMENT.

EASEMENTS FOR FLOODPLAINS:
THE DRAINAGE EASEMENTS WERE DELINEATED BY THE FEDERAL ENGINEERING MANAGEMENT AGENCY (FEMA) IN ACCORDANCE WITH DFRM PANEL 48029C0685H, DATED SEPTEMBER 28, 2010. OR THE 1% ANNUAL CHANCE (100-YEAR) ULTIMATE DEVELOPMENT CONDITION WATER SURFACE ELEVATION, OR THE 4% ANNUAL CHANCE (25-YEAR) ULTIMATE DEVELOPMENT CONDITION WATER SURFACE ELEVATION, OR STRUCTURES WITHIN THE DRAINAGE EASEMENTS AND FLOODPLAINS SHALL BE REMOVED OR MODIFIED TO COMPLY WITH THE DRAINAGE EASEMENT AND FLOODPLAIN REQUIREMENTS.

TO CONTAIN THE LESSER OF THE BOUNDARIES OF THE 1% ANNUAL CHANCE (100-YEAR) FLOOD ZONE ESTABLISHED BY THE FEDERAL ENGINEERING MANAGEMENT AGENCY (FEMA) IN ACCORDANCE WITH DFRM PANEL 48029C0685H, DATED SEPTEMBER 28, 2010. OR THE 1% ANNUAL CHANCE (100-YEAR) ULTIMATE DEVELOPMENT CONDITION WATER SURFACE ELEVATION, OR THE 4% ANNUAL CHANCE (25-YEAR) ULTIMATE DEVELOPMENT CONDITION WATER SURFACE ELEVATION, OR STRUCTURES WITHIN THE DRAINAGE EASEMENTS AND FLOODPLAINS SHALL BE REMOVED OR MODIFIED TO COMPLY WITH THE DRAINAGE EASEMENT AND FLOODPLAIN REQUIREMENTS.

FIRE ACCESS NOTE:
INGRESS AND EGRESS SHALL BE PROVIDED BETWEEN ALL ADJACENT LOTS FOR ADEQUATE FIRE DEPARTMENT VEHICLE ACCESS PER THE CITY OF SAN ANTONIO FIRE PREVENTION CODE. ANY CROSS ACCESS SHALL NOT BE BLOCKED NOR MAY THIS NOTE BE REMOVED FROM THE PLAT WITHOUT WRITTEN PERMISSION FROM THE CITY OF SAN ANTONIO DIRECTOR OF DEVELOPMENT SERVICES AND THE SAN ANTONIO FIRE DEPARTMENT FIRE MARSHAL.

SETBACK NOTE:
THE SETBACKS IMPOSED ON THIS PLAT ARE AT THE DISCRETION OF THE DEVELOPER OR BEXAR COUNTY AND ARE NOT SUBJECT TO ENFORCEMENT BY THE CITY OF SAN ANTONIO. BUILDING SETBACKS FOR EACH LOT SHOWN ON THIS PLAT ARE SUBJECT TO FURTHER RESTRICTIONS AS IMPOSED BY THE HOMEOWNERS ASSOCIATION.



RESIDENTIAL FIRE FLOW: RESIDENTIAL DEVELOPMENT ONLY 1817
THE PUBLIC WATER MAIN SYSTEM HAS BEEN DESIGNED FOR A MINIMUM FIRE FLOW DEMAND OF 1500 GPM AT 25 PSI RESIDUAL PRESSURE TO MEET THE CITY OF SAN ANTONIO'S FIRE FLOW REQUIREMENTS FOR THE RESIDENTIAL DEVELOPMENT. THE FIRE FLOW REQUIREMENTS FOR INDIVIDUAL STRUCTURES WILL BE REVIEWED PRIOR TO BUILDING PERMIT APPROVAL IN ACCORDANCE WITH THE PROCEDURES SET FORTH BY THE CITY OF SAN ANTONIO DIRECTOR OF DEVELOPMENT SERVICES AND THE SAN ANTONIO FIRE DEPARTMENT FIRE MARSHAL.

COMMON AREA MAINTENANCE:
THE MAINTENANCE OF ALL PRIVATE STREETS, OPEN SPACE, GREENBELTS, PARKS, TREE SAVE AREAS, INCLUDING LOT 5, BLOCK 1, CB OR NCB 10917, DRAINAGE EASEMENTS AND EASEMENTS OF ANY OTHER NATURE WITHIN THIS SUBDIVISION SHALL BE THE RESPONSIBILITY OF THE PROPERTY OWNERS, OR ITS SUCCESSORS OR ASSIGNS AND NOT THE RESPONSIBILITY OF THE CITY OF SAN ANTONIO OR BEXAR COUNTY.

OPEN SPACE NOTE:
LOT 5, BLOCK 1, NCB 10917 IS DESIGNATED AS OPEN SPACE AND AS A COMMON AREA AND A DRAINAGE EASEMENT.

SAWS HIGH PRESSURE:
A PORTION OF THE TRACT IS BELOW THE GROUND ELEVATION OF 985 FEET WHERE THE STATIC PRESSURE WILL NORMALLY EXCEED 80 PSI. AT ALL SUCH LOCATIONS, THE OWNER OR BUILDER SHALL INSTALL AT EACH LOT, ON THE CUSTOMER'S SIDE OF THE METER, AN APPROVED TYPE PRESSURE REGULATOR IN CONFORMANCE WITH THE PLUMBING CODE OF THE CITY OF SAN ANTONIO.


DATE OF PREPARATION: 6/10/2024



PLAT NO. 21-11800367

SUBDIVISION PLAT ESTABLISHING BALLESTEROS SUBDIVISION

A 4.787 ACRE TRACT OF LAND BEING ALL OF A CALLED 1.497 ACRE TRACT OF LAND AND ALL OF A CALLED 2.662 ACRE TRACT OF LAND BOTH OUT OF THE JAMES MCKAY SURVEY NO. 48, ABSTRACT NO. 522, NCB 10917 AS CONVEYED TO HILDA ENELIA BALLESTEROS, OF RECORD IN DOCUMENT NO. 20120155680 OF THE OFFICIAL PUBLIC RECORDS OF BEXAR COUNTY, TEXAS ESTABLISHING LOTS 2, 3, & 901, BLOCK 1.




8511 QUEEN HEIGHTS
SAN ANTONIO, TEXAS 78254
PHONE: 210.332.7763
TEXAS REGISTERED ENGINEERING FIRM F-14265

STATE OF TEXAS
COUNTY OF BEXAR

THE OWNER OF LAND SHOWN ON THIS PLAT, IN PERSON OR THROUGH A DULY AUTHORIZED AGENT, DEDICATES TO THE USE OF THE PUBLIC, EXCEPT AREAS IDENTIFIED AS PRIVATE OR PART OF AN ENCLAVE OR PLANNED UNIT DEVELOPMENT, FOREVER ALL STREETS, ALLEYS, PARKS, WATERCOURSES, DRAINS, EASEMENTS AND PUBLIC PLACES THEREON SHOWN FOR THE PURPOSE AND CONSIDERATION THEREIN EXPRESSED.

Hilda E. Ballesteros
OWNER
HILDA ENELIA BALLESTEROS
3114 CINDY SUE WAY
SAN ANTONIO, TX 78223
210-410-2074



STATE OF TEXAS
COUNTY OF BEXAR

BEFORE ME, THE UNDERSIGNED AUTHORITY ON THIS DAY PERSONALLY APPEARED *Hilda E. Ballesteros* KNOWN TO ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT, AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME FOR THE PURPOSES AND CONSIDERATIONS THEREIN EXPRESSED AND IN THE CAPACITY THEREIN STATED. GIVEN UNDER MY HAND AND SEAL OF OFFICE THIS 3rd DAY OF July A.D. 2024

Elvira Colmenero
NOTARY PUBLIC BEXAR COUNTY, TEXAS

THIS PLAT OF BALLESTEROS SUBDIVISION HAS BEEN SUBMITTED TO AND CONSIDERED BY THE PLANNING COMMISSION OF THE CITY OF SAN ANTONIO, TEXAS, AND IS HEREBY APPROVED BY SUCH COMMISSION IN ACCORDANCE WITH STATE OR LOCAL LAWS AND REGULATIONS; AND/OR WHERE ADMINISTRATIVE EXCEPTION(S) AND/OR VARIANCE(S) HAVE BEEN GRANTED.

DATED THIS ____ DAY OF ____ A.D. 20__

BY: _____
CHAIRMAN

BY: _____
SECRETARY