

14.59 ACRES OF LAND BEING REPLATTED WAS PREVIOUSLY PLATTED AS A PORTION OF LOT 8, BLOCK 54 IN THE SAN ANTONIO SUBURBAN IRRIGATED FARMS SUBDIVISION RECORDED IN VOLUME 980, PAGE 157-166 OF THE DEED AND PLAT RECORDS OF BEXAR COUNTY, TEXAS.

STATE OF TEXAS  
COUNTY OF BEXAR

THE AREA BEING REPLATTED WAS PREVIOUSLY PLATTED ON PLAT SAN ANTONIO SUBURBAN IRRIGATED FARMS SUBDIVISION WHICH IS RECORDED IN VOLUME 980, PAGE(S) 157-166, COUNTY PLAT AND DEED RECORDS OF BEXAR COUNTY, TEXAS.

I (WE), THE OWNER(S) OF THE PROPERTY SHOWN ON THIS REPLAT HEREBY CERTIFY THAT THIS REPLAT DOES NOT AMEND OR REMOVE ANY COVENANTS OR RESTRICTIONS.

OWNER/DEVELOPER: IT'S THE CLIMB VENTURES, LLC  
1306 GREER ST.,  
SAN ANTONIO, TX 78210  
(210)-723-6552

STATE OF TEXAS  
COUNTY OF BEXAR

SWORN AND SUBSCRIBED BEFORE ME THIS THE \_\_\_\_\_ DAY OF \_\_\_\_\_, A.D. 20\_\_\_\_

NOTARY PUBLIC IN AND FOR THE STATE OF TEXAS

MY COMMISSION EXPIRES: \_\_\_\_\_

LEGEND	
VOL PG	VOLUME PAGE(S)
B.C.O.P.R.	OFFICIAL PUBLIC RECORDS (OFFICIAL PUBLIC RECORDS OF REAL PROPERTY) OF BEXAR COUNTY, TEXAS
DR	DEED RECORDS OF BEXAR COUNTY, TEXAS
R.O.W.	RIGHT OF WAY
B.C.D.P.R.	DEED AND PLAT RECORDS OF BEXAR COUNTY, TEXAS
C.M.	CONTROLLING MONUMENT
C.A.T.V.	CABLE AND TELEVISION
①	14' ELECTRIC, GAS, TELEPHONE, AND C.A.T.V. EASEMENT
②	20' R.O.W. DEDICATION (0.42 ACRES)
③	10' BUILDING SETBACK LINE
④	VARIABLE WIDTH PUBLIC DRAINAGE EASEMENT
⑤	1% AC FLOODPLAIN PER FEMA PANEL 48029C0510F, DATED 09/29/2010
---	ADJOINER
- - - - -	EXISTING CONTOURS
- - - - -	PROPOSED EASEMENT
- - - - -	CITY OF SAN ANTONIO LIMITS
- - - - -	EFFECTIVE 1% FLOODPLAIN
- - - - -	1% ULTIMATE FLOODPLAIN
- - - - -	1% ATLAS 14 FLOODPLAIN
- - - - -	BOUNDARY LINE
- - - - -	CENTERLINE OF ROAD
●	FOUND 1/2" IRON ROD (UNLESS NOTED OTHERWISE)
○	SET 1/2" IRON ROD (UNLESS NOTED OTHERWISE)
○	FOUND WOOD FENCE POST CORNER (UNLESS NOTED OTHERWISE)
●	CALCULATED POINT

**SURVEYOR'S NOTES:**  
1. PROPERTY CORNERS ARE MONUMENTED WITH A CAP OR DISK MARKED "INTREPID" UNLESS NOTED OTHERWISE;  
2. COORDINATES SHOWN ARE BASED ON THE NORTH AMERICAN DATUM OF 1983 (NAVD 88) FROM THE TEXAS COORDINATE SYSTEM ESTABLISHED FOR THE SOUTH CENTRAL ZONE DISPLAYED IN GRID VALUES DERIVED FROM NORMAL GPS TECHNIQUES;  
3. DIMENSIONS SHOWN ARE GRID; AND BEARINGS ARE BASED ON THE NORTH AMERICAN DATUM OF 1983 (NAVD 88), FROM THE TEXAS COORDINATE SYSTEM ESTABLISHED FOR THE SOUTH CENTRAL ZONE.

**CPS/SAWS/COSA UTILITY:**  
1. THE CITY OF SAN ANTONIO AS PART OF ITS ELECTRIC, GAS, WATER, AND WASTEWATER SYSTEMS - CITY PUBLIC SERVICE BOARD (CPS ENERGY) AND SAN ANTONIO WATER SYSTEM (SAWS) - IS HEREBY DEDICATED EASEMENTS AND RIGHTS-OF-WAY FOR UTILITY, TRANSMISSION AND DISTRIBUTION INFRASTRUCTURE AND SERVICE FACILITIES IN THE AREAS DESIGNATED ON THIS PLAT AS "ELECTRIC EASEMENT," "ANCHOR EASEMENT," "SERVICE EASEMENT," "OVERHANG EASEMENT," "UTILITY EASEMENT," "GAS EASEMENT," "TRANSFORMER EASEMENT," "WATER EASEMENT," "SANITARY SEWER EASEMENT" AND/OR "RECYCLED WATER EASEMENT" FOR THE PURPOSE OF INSTALLING, CONSTRUCTING, RECONSTRUCTING, MAINTAINING, REMOVING, INSPECTING, PATROLLING, AND ERECTING UTILITY INFRASTRUCTURE AND SERVICE FACILITIES FOR THE REASONS DESCRIBED ABOVE. CPS ENERGY AND SAWS SHALL ALSO HAVE THE RIGHT TO RELOCATE SAID INFRASTRUCTURE AND SERVICE FACILITIES WITHIN EASEMENT AND RIGHT-OF-WAY AREAS, TOGETHER WITH THE RIGHT OF INGRESS AND EGRESS OVER GRANTOR'S ADJACENT LANDS FOR THE PURPOSE OF ACCESSING SUCH INFRASTRUCTURE AND SERVICE FACILITIES AND THE RIGHT TO REMOVE FROM SAID LANDS ALL TREES OR PARTS THEREOF, OR OTHER OBSTRUCTIONS WHICH ENDANGER OR MAY INTERFERE WITH THE EFFICIENCY OF WATER, SEWER, GAS, AND/OR ELECTRIC INFRASTRUCTURE AND SERVICE FACILITIES. NO BUILDINGS, STRUCTURES, CONCRETE SLABS, OR WALLS WILL BE PLACED WITHIN EASEMENT AREAS WITHOUT AN ENCROACHMENT AGREEMENT WITH THE RESPECTIVE UTILITY.  
2. ANY CPS ENERGY OR SAWS MONETARY LOSS RESULTING FROM MODIFICATIONS REQUIRED OF CPS ENERGY OR SAWS INFRASTRUCTURE AND SERVICE FACILITIES, LOCATED WITHIN SAID EASEMENTS, DUE TO GRADE CHANGES OR GROUND ELEVATION ALTERATIONS SHALL BE CHARGED TO THE PERSON OR PERSONS DEEMED RESPONSIBLE FOR SAID GRADE CHANGES OR GROUND ELEVATION ALTERATIONS.  
3. THIS PLAT DOES NOT AMEND, ALTER, RELEASE OR OTHERWISE AFFECT ANY EXISTING ELECTRIC, GAS, WATER, SEWER, DRAINAGE, TELEPHONE, CABLE TV EASEMENTS OR ANY OTHER EASEMENTS FOR UTILITIES UNLESS THE CHANGES TO SUCH EASEMENTS ARE DESCRIBED HEREON.

**CPS/SAWS/COSA UTILITY:**  
4. CONCRETE DRIVEWAY APPROACHES ARE ALLOWED WITHIN THE FIVE (5) AND TEN (10) FOOT WIDE ELECTRIC AND GAS EASEMENTS WHEN LOTS ARE SERVED ONLY BY UNDERGROUND ELECTRIC AND GAS FACILITIES.  
5. ROOF OVERHANGS ARE ALLOWED WITHIN THE FIVE (5) AND TEN (10) FOOT WIDE ELECTRIC AND GAS EASEMENTS WHEN ONLY UNDERGROUND ELECTRIC AND GAS FACILITIES ARE PROPOSED OR EXISTING WITHIN THOSE FIVE (5) AND TEN (10) FOOT WIDE EASEMENTS.

**COUNTY FINISHED FLOOR ELEVATION - RELATIVE TO FLOODPLAIN:**  
FINISHED FLOOR ELEVATIONS FOR STRUCTURES ON LOTS CONTAINING FLOODPLAIN OR ADJACENT TO THE FLOODPLAIN SHALL BE IN COMPLIANCE WITH THE FLOODPLAIN REGULATION IN EFFECT AT TIME OF CONSTRUCTION. CONTACT BEXAR COUNTY PUBLIC WORKS FOR MORE INFORMATION.

**EASEMENTS FOR FLOODPLAINS NOTE:**  
THE DRAINAGE EASEMENTS WERE DELINEATED TO CONTAIN THE LESSER OF THE BOUNDARIES OF THE 1% ANNUAL CHANCE (100-YEAR) FLOOD ZONE ESTABLISHED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) IN ACCORDANCE WITH DFIRM PANEL 48029C0510F, DATED SEPTEMBER 29, 2010; OR THE 1% ANNUAL CHANCE (100-YEAR) ULTIMATE DEVELOPMENT CONDITION WATER SURFACE ELEVATION; OR THE 4% ANNUAL CHANCE (25-YEAR) ULTIMATE DEVELOPMENT FLOODPLAIN PLUS FREEBOARD. CONSTRUCTION, IMPROVEMENTS, OR STRUCTURES WITHIN THE DRAINAGE EASEMENTS AND FLOODPLAIN ARE PROHIBITED WITHOUT PRIOR WRITTEN APPROVAL FROM THE FLOODPLAIN ADMINISTRATOR OF THE CITY OF SAN ANTONIO OR BEXAR COUNTY.

STATE OF TEXAS  
COUNTY OF BEXAR


I HEREBY CERTIFY THAT PROPER ENGINEERING CONSIDERATION HAS BEEN GIVEN THIS PLAT TO THE MATTERS OF STREETS, LOTS AND DRAINAGE LAYOUT. TO THE BEST OF MY KNOWLEDGE THIS PLAT CONFORMS TO ALL REQUIREMENTS OF THE UNIFIED DEVELOPMENT CODE, EXCEPT FOR THOSE VARIANCES GRANTED BY THE SAN ANTONIO PLANNING COMMISSION.

**CLEAR VISION NOTE:**  
CLEAR VISION AREAS MUST BE FREE OF VISUAL OBSTRUCTIONS IN ACCORDANCE WITH THE AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO) POLICY ON GEOMETRIC DESIGN OF HIGHWAYS AND STREETS, OR LATEST REVISION THEREOF.  
**COMMON AREA MAINTENANCE NOTE:**  
1. THE MAINTENANCE OF ALL PRIVATE STREETS, OPEN SPACE, GREENBELTS, PARKS, TREE SAVE AREAS, DRAINAGE EASEMENTS AND EASEMENTS OF ANY OTHER NATURE WITHIN THIS SUBDIVISION SHALL BE THE RESPONSIBILITY OF THE PROPERTY OWNERS, OR THE PROPERTY OWNER'S ASSOCIATION, OR ITS SUCCESSORS OR ASSIGNS AND NOT THE RESPONSIBILITY OF THE CITY OF SAN ANTONIO OR BEXAR COUNTY.  
**SETBACK NOTE:**  
1. THE SETBACKS ON THE PLAT ARE IMPOSED BY THE PROPERTY OWNER OR BEXAR COUNTY AND ARE NOT SUBJECT TO ENFORCEMENT BY THE CITY OF SAN ANTONIO.

**RESIDENTIAL FIRE FLOW NOTE:**  
THE PUBLIC WATER MAIN SYSTEM HAS BEEN DESIGNED FOR A MINIMUM FIRE FLOW DEMAND OF 250 GPM AT 25 PSI RESIDUAL PRESSURE TO MEET THE CITY OF SAN ANTONIO'S FIRE FLOW REQUIREMENTS FOR THE RESIDENTIAL DEVELOPMENT. THE FIRE FLOW REQUIREMENTS FOR INDIVIDUAL STRUCTURES WILL BE REVIEWED PRIOR TO BUILDING PERMIT APPROVAL IN ACCORDANCE WITH THE PROCEDURES SET FORTH BY THE CITY OF SAN ANTONIO DIRECTOR OF DEVELOPMENT SERVICES AND THE SAN ANTONIO FIRE DEPARTMENT FIRE MARSHAL.

**DRAINAGE EASEMENT ENCROACHMENTS NOTE:**  
NO STRUCTURE, FENCES, WALLS OR OTHER OBSTRUCTIONS THAT IMPEDE DRAINAGE SHALL BE PLACED WITHIN THE LIMITS OF THE DRAINAGE EASEMENTS SHOWN ON THIS PLAT. NO LANDSCAPING OR OTHER TYPE OF MODIFICATIONS, WHICH ALTER THE CROSS-SECTIONS OF THE DRAINAGE EASEMENTS, AS APPROVED, SHALL BE ALLOWED WITHOUT THE APPROVAL OF THE DIRECTOR OF PUBLIC WORKS. THE CITY OF SAN ANTONIO AND BEXAR COUNTY SHALL HAVE THE RIGHT OF INGRESS AND EGRESS OVER THE GRANTOR'S ADJACENT PROPERTY TO REMOVE ANY IMPEDING OBSTRUCTIONS PLACED WITHIN THE LIMITS OF SAID DRAINAGE EASEMENT AND TO MAKE ANY MODIFICATIONS OR IMPROVEMENTS WITHIN SAID DRAINAGE EASEMENTS.

"PLATTED" PORTION OF: LOT 4 BLOCK 54  
LIDIA FACUNDO CASTILLO (11.39 ACRES)  
DOC 20080028313 B.C.O.P.R.



CURVE TABLE				
CURVE #	RADIUS	DELTA	CHORD BEARING	CHORD LENGTH
C1	200.00'	042°03'55"	S72°39'45"W	143.56'
C2	220.00'	042°03'55"	N72°39'44"E	157.92'

STATE OF TEXAS  
COUNTY OF BEXAR


I HEREBY CERTIFY THAT THE ABOVE PLAT CONFORMS TO THE MINIMUM STANDARDS SET FORTH BY THE TEXAS BOARD OF PROFESSIONAL LAND SURVEYING ACCORDING TO AN ACTUAL SURVEY MADE ON THE GROUND BY: INTREPID SURVEYING AND ENGINEERING.

**RESIDENTIAL FINISHED FLOOR NOTE:**  
RESIDENTIAL FINISHED FLOOR ELEVATIONS MUST BE A MINIMUM OF EIGHT (8) INCHES ABOVE FINAL ADJACENT GRADE.  
**FINISHED FLOOR NOTE:**  
FINISHED FLOOR ELEVATIONS FOR NON-RESIDENTIAL STRUCTURES SHALL BE NO LESS THAN ONE FOOT ABOVE THE BASE FLOOD ELEVATION OF THE REGULATORY FLOODPLAIN (CITY OF SAN ANTONIO ULTIMATE DEVELOPMENT FLOODPLAIN). THE LOWEST ADJACENT GRADE SHALL BE AT OR ABOVE THE BASE FLOOD ELEVATION. FLOOD-PROOFING MAY BE ALLOWED IF ELEVATING THE STRUCTURE IS NOT FEASIBLE, IF APPROVED BY THE FLOODPLAIN ADMINISTRATOR OF THE CITY OF SAN ANTONIO.  
**SAWS IMPACT FEE:**  
WATER AND/OR WASTEWATER IMPACT FEES WERE NOT PAID AT THE TIME OF PLATTING FOR THIS PLAT. ALL IMPACT FEES MUST BE PAID PRIOR TO WATER METER SET AND/OR WASTEWATER SERVICE CONNECTION.

**EASEMENTS FOR FLOODPLAINS NOTE:**  
THE DRAINAGE EASEMENTS WERE DELINEATED TO CONTAIN THE LESSER OF THE BOUNDARIES OF THE 1% ANNUAL CHANCE (100-YEAR) FLOOD ZONE ESTABLISHED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) IN ACCORDANCE WITH DFIRM PANEL 48029C0510F, DATED SEPTEMBER 29, 2010; OR THE 1% ANNUAL CHANCE (100-YEAR) ULTIMATE DEVELOPMENT CONDITION WATER SURFACE ELEVATION; OR THE 4% ANNUAL CHANCE (25-YEAR) ULTIMATE DEVELOPMENT FLOODPLAIN PLUS FREEBOARD. CONSTRUCTION, IMPROVEMENTS, OR STRUCTURES WITHIN THE DRAINAGE EASEMENTS AND FLOODPLAIN ARE PROHIBITED WITHOUT PRIOR WRITTEN APPROVAL FROM THE FLOODPLAIN ADMINISTRATOR OF THE CITY OF SAN ANTONIO OR BEXAR COUNTY.

LINE TABLE		
LINE #	BEARING	LENGTH
L1	N84°32'22"E	66.07'
L2	N84°32'22"E	118.40'
L3	N70°04'26"E	100.72'
L4	S03°36'42"E	100.64'
L5	S00°01'08"W	93.39'
L6	N74°25'38"W	178.53'
L7	N74°25'38"W	58.88'
L8	S30°50'57"W	81.11'
L9	S05°32'39"E	77.82'
L10	S51°08'05"E	64.93'
L11	S86°16'55"E	75.42'
L12	S89°51'56"W	129.70'
L13	N71°13'36"W	123.46'
L14	N71°13'36"W	198.56'
L15	N86°18'18"W	29.56'
L16	N38°22'15"W	10.73'
L17	S51°24'26"W	36.99'
L18	N78°56'21"E	170.89'
L19	N84°04'24"E	154.55'
L20	N80°43'18"E	73.81'
L21	S81°00'41"E	47.74'
L22	N89°50'06"E	120.57'
L23	N86°10'57"E	106.14'
L24	N89°52'03"E	156.14'
L25	N84°38'29"E	104.87'
L26	N78°43'19"E	183.63'
L27	N86°35'42"E	154.35'
L28	N89°51'56"E	126.31'
L29	S71°13'36"E	120.13'
L30	S71°13'36"E	201.21'
L31	S86°18'18"E	33.44'
L32	S86°18'18"E	268.41'
L33	N52°36'30"E	34.91'
L34	S26°35'28"E	10.23'
L35	N00°17'54"W	20.00'

"PLATTED" PORTION OF: LOT 4, BLOCK 54  
REYNALDO TREJO (5.199 ACRES)  
DOC 20180181998 B.C.O.P.R.



CURVE TABLE				
CURVE #	RADIUS	DELTA	CHORD BEARING	CHORD LENGTH
C1	200.00'	042°03'55"	S72°39'45"W	143.56'
C2	220.00'	042°03'55"	N72°39'44"E	157.92'

STATE OF TEXAS  
COUNTY OF BEXAR

I HEREBY CERTIFY THAT THE ABOVE PLAT CONFORMS TO THE MINIMUM STANDARDS SET FORTH BY THE TEXAS BOARD OF PROFESSIONAL LAND SURVEYING ACCORDING TO AN ACTUAL SURVEY MADE ON THE GROUND BY: INTREPID SURVEYING AND ENGINEERING.

**REPLAT NO. 22-11800609**  
SUBDIVISION REPLAT & PLAT  
ESTABLISHING  
**JOYFUL SUBDIVISION**  
BEING A TOTAL OF 14.60 ACRES, ESTABLISHING LOTS 47-50, BLOCK 54, COUNTY BLOCK 5737 IN BEXAR COUNTY, TEXAS, INCLUDING A 0.42 ACRE R.O.W. DEDICATION ALONG SHERWOOD ROAD, AND BEING THAT SAME 15.56 ACRE TRACT DESCRIBED IN DOCUMENT NUMBER 20230111585 OF THE OFFICIAL PUBLIC RECORDS OF BEXAR COUNTY.

0' 60' 120' 180'  
SCALE: 1" = 60'  
PLAT DATE: 5/8/2024  
CURRENT DEED: 20230111585  
**INTREPID**  
SURVEYING & ENGINEERING  
P.O. Box 1209 • 109 DILWORTH PLAZA  
POTH, TX 78147  
O. 830.393.8833 • F. 830.393.3388  
WWW.INTREPIDTX.COM  
TBPLS #10193936 • TBPE #16550

STATE OF TEXAS  
COUNTY OF BEXAR

THE OWNER OF LAND SHOWN ON THIS PLAT, IN PERSON OR THROUGH A DULY AUTHORIZED AGENT, DEDICATES TO THE USE OF THE PUBLIC, EXCEPT AREAS IDENTIFIED AS PRIVATE OR PART OF AN ENCLAVE OR PLANNED UNIT DEVELOPMENT, FOREVER ALL STREETS, ALLEYS, PARKS, WATERCOURSES, DRAINS, EASEMENTS AND PUBLIC PLACES THEREON SHOWN FOR THE PURPOSE AND CONSIDERATION THEREIN EXPRESSED.

OWNER/DEVELOPER: IT'S THE CLIMB VENTURES LLC  
1306 GREER ST.,  
SAN ANTONIO, TX 78210,  
AUTHORIZED AGENT: TERRY PUENTE  
(210) 723-6552

STATE OF TEXAS  
COUNTY OF BEXAR

BEFORE ME, THE UNDERSIGNED AUTHORITY ON THIS DAY PERSONALLY APPEARED TERRY PUENTE, KNOWN TO ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT, AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME FOR THE PURPOSES AND CONSIDERATIONS THEREIN EXPRESSED AND IN THE CAPACITY THEREIN STATED. GIVEN UNDER MY HAND AND SEAL OF OFFICE THIS \_\_\_\_\_ DAY OF \_\_\_\_\_, A.D. 20\_\_\_\_

NOTARY PUBLIC, BEXAR COUNTY, TEXAS

**CERTIFICATE OF APPROVAL**


THIS MINOR PLAT HAS BEEN SUBMITTED TO BEXAR COUNTY, TEXAS PUBLIC WORKS DEPARTMENT AND HAVING BEEN REVIEW BY THE DIRECTOR OF PUBLIC WORKS/COUNTY ENGINEER, IS HEREBY APPROVED IN ACCORDANCE WITH THE STATE AND LOCAL LAWS AND REGULATIONS AS INDICATED BELOW ON THIS \_\_\_\_\_ DAY OF \_\_\_\_\_, A.D. 20\_\_\_\_

BY: \_\_\_\_\_  
COUNTY TEXAS

THIS PLAT OF JOYFUL SUBDIVISION HAS BEEN SUBMITTED TO AND CONSIDERED BY THE PLANNING COMMISSION OF THE CITY OF SAN ANTONIO, TEXAS, IS HEREBY APPROVED BY SUCH COMMISSION IN ACCORDANCE WITH STATE OR LOCAL LAWS AND REGULATIONS; AND/OR WHERE ADMINISTRATIVE EXCEPTION(S) AND/OR VARIANCE(S) HAVE BEEN GRANTED.  
DATED THIS \_\_\_\_\_ DAY OF \_\_\_\_\_, A.D. 20\_\_\_\_

BY: \_\_\_\_\_ CHAIRMAN

BY: \_\_\_\_\_ SECRETARY



LICENSED PROFESSIONAL ENGINEER

REGISTERED PROFESSIONAL LAND SURVEYOR

SHEET 3 OF 3