

HISTORIC AND DESIGN REVIEW COMMISSION

July 17, 2024

HDRC CASE NO: 2024-230
ADDRESS: 1210 E ELMIRA ST
LEGAL DESCRIPTION: NCB 6796 BLK 8 LOT 1 THRU 3 & S IRR 124.65 OF 4-6 & S IRR 42.09 FT OF 7
ZONING: IDZ, RIO-2
CITY COUNCIL DIST.: 1
APPLICANT: Daniel Elder/OXBOW REAL ESTATE LLC
OWNER: Daniel Elder/OXBOW REAL ESTATE LLC
TYPE OF WORK: Construction of a 6-story mixed-use structure
APPLICATION RECEIVED: June 25, 2024
60-DAY REVIEW: August 24, 2024
CASE MANAGER: Edward Hall
REQUEST:

The applicant is requesting a Certificate of Appropriateness for approval to construct a six-story, mixed-use structure on the lot addressed as 1210 E Elmira. This lot is bounded by Schiller Street to the south, E Elmira Street to the west, Myrtle Street to the north and the San Antonio River to the east. This lot is located within the River Improvement Overlay, District 2. This proposal is located on the same lot with a proposed 8-story hotel; however, that proposal is not included in this request.

APPLICABLE CITATIONS:

Sec. 35-672. Neighborhood Wide Design Standards.

STATEMENT OF PURPOSE

This section focuses on the urban design concepts that connect individual properties and help knit them together into the fabric of the community. These concepts include the basic arrangement of streets and lots, view corridors and circulation patterns. The standards apply to all development in the seven (7) river improvement overlay districts.

(a) **Pedestrian circulation.** Pedestrian access shall be provided among properties to integrate neighborhoods.

(1) Provide sidewalks that link with existing sidewalks on adjoining properties. If no sidewalk currently exists on an adjoining property, the applicant will have discretion in the placement of the sidewalk provided the following criteria are met:

A. Provide a sidewalk connection from one (1) side of the applicant's property to the other, parallel to the public right-of-way, on the street sides of the property in all river improvement overlay districts

B. Provide a connection from the street level sidewalk to the Riverwalk or creek at cross streets and bridges and other designated access points. This requirement may be waived if there is already a public connection from the street level to the Riverwalk or creek.

C. In order to preserve the rural character of "RIO-6," the HPO, in coordination with the development services department, may waive the requirement of sidewalks.

- In "RIO-3," the width of the pathway along the river shall match those widths established in the historic Hugman drawings. If there are no sidewalks in the Hugman drawings, the path will not exceed eight (8) feet in width.

D. In RIO-7, two (2) distinct public paths, a High Bank Paseo and a Low Bank Paseo exist along the San Pedro Creek. Where a High Bank Paseo condition does not exist along the creekside of a property, a shared sidewalk and/or patio space is strongly encouraged to connect one (1) side of the applicant's property to the other along the top of the bank within the creekside setback established in this section.

(2) Link the various functions and spaces on a site with sidewalks in a coordinated system.

Provide pedestrian sidewalks between buildings, parking areas and built features such as outdoor plazas and courtyards.

(3) Paving materials. Paving materials for pedestrian pathways shall use visually and texturally different materials than those used for parking spaces and automobile traffic.

A. Paving materials for pedestrian pathways shall be either:

- i. Broom-finished, scored, sandblasted or dyed concrete;
- ii. Rough or honed finished stone;
- iii. Brick or concrete pavers; or
- iv. Other materials that meet the performance standards of the above materials.

B. Asphalt is permitted for pedestrian pathways that also are designated as multi-use paths by the City of San Antonio. The Transportation and Capital Improvements department will maintain the designated multi-use path locations.

(4) Street Connections to River or Creek. Retain the interesting and unique situations where streets dead-end at the river or creek, creating both visual and physical access to the river or creek for the public.

(5) Pedestrian Access Along the Public Pathways Shall Not Be Blocked.

A. Queuing is prohibited on the public pathway.

B. Hostess stations shall be located away from the public pathway so as to not inhibit pedestrian flow on the public pathway. That is, the hostess station shall not be located in such a manner to cause a patron who has stopped at the hostess stand to be standing on the public pathway. Pedestrian flow shall be considered "inhibited" if a pedestrian walking along the pathway has to swerve, dodge, change direction or come to a complete stop to avoid a patron engaged at the hostess stand.

C. Tables and chairs shall be located a sufficient distance from the public pathway so that normal dining and service shall not inhibit the flow of pedestrian traffic. See inhibited definition in subsection B. above.

(b) Automobile Access and Parking. Automobile circulation should be efficient, and conflicts with pedestrians minimized. Entry points for automobiles should be clearly defined and connections to auto circulation on adjoining properties are encouraged to facilitate access and reduce traffic on abutting public streets.

(1) Curb Cuts.

A. Limit curb cuts to two (2) on parking areas or structures facing only one (1) street, and one (1) for each additional street face. The prohibition of additional curb cuts may be waived by the HDRC where the intent of the standards are clearly met and specific site circulation patterns require an additional curb cut, such as on long parcels or at nodes.

B. Curb cuts may be no larger than twenty-five (25) feet zero (0) inches. Continuous curb cuts are prohibited.

C. Sharing curb cuts between adjacent properties, such as providing cross property access easements, is permitted.

(2) Location of Parking Areas. Automobile parking in new developments must be balanced with the requirements of active environments. Large expanses of surface parking lots have a negative impact on street activity and the pedestrian experience. New commercial and residential structures can accommodate parking needs and contribute to a pedestrian-friendly streetscape.

A. Locate parking areas, that is any off-street, ground level surface used to park cars or any parking structure, toward the interior of the site or to the side or rear of a building.

B. The extent of parking area that may be located along the street edge or riverside shall be limited to a percentage of the lot line as per Table 672-1 as measured in a lineal direction parallel to the lot line. All parking within a thirty-foot setback from the above mentioned lot line shall comply with the requirements of the table. Where parking is located on corner sites only one (1) lot line has to meet the requirements of the table.

C. Parking lots should be avoided as a primary land use. Parking lots as a primary use are prohibited in RIO-3 and for all properties that fall within one hundred (100) feet of the river right-of-way in all RIO districts.

(3) Screen or Buffer Parking Areas From View of Public Streets, the River or Adjacent Residential Uses. (see Figure 672-2). Parking lots shall be screened with a landscape buffer as per the illustrations of bufferyards and Table 510-2 if the parking area meets one (1) of the following conditions:

A. Within a fifty-foot setback from the edge of the river ROW use, at a minimum, type E; or

B. Within a twenty-foot setback from a property line adjacent to a street use, at a minimum, type B; or

C. Within a twenty-foot setback of commercial or industrial property that abuts a residential property use, at a minimum, type C.

(4) Parking Structures Shall Be Compatible With Buildings in the Surrounding Area. Parking garages should have retail space on the ground floor of a parking structure provided the retail space has at least fifty (50) percent of its linear street frontage as display windows. Parking structures may be made visually appealing with a mural or public art component approved by the HDRC on the parking structure. A parking garage will be considered compatible if:

A. It does not vary in height by more than thirty (30) percent from another building on the same block face; and

B. It uses materials that can be found on other buildings within the block face, or in the block face across the street.

(5) Parking Structures Shall Provide Clearly Defined Pedestrian Access. Pedestrian entrances and exits shall be accentuated with directional signage, lighting or architectural features so that pedestrians can readily discern the appropriate path of travel to avoid pedestrian/auto conflicts.

(6) Parking lots, structures, and hardscape shall not drain directly into the river without installation of appropriate water quality best management practices (WQ BMPs). Acequias shall not be used for any type of drainage.

(c) Views. The river's course (both natural and manmade), and San Antonio's street pattern, creates unique views of certain properties from the public ROW. These properties often occur at prominent curves in the river or where a street changes direction and a property appears to be a terminus at the end of a street.

(1) Architectural Focal Point. When a property is situated in such a manner as to appear to be the terminus at the end of the street or at a prominent curve in the river, the building shall incorporate into its design an architectural feature that will provide a focal point at the end of the view. (see Figure 672-3) An architectural feature will be considered to be a focal point through any of the following methods, but not limited to:

A. Additional height.

B. Creation of a tower.

C. Variation in roof shape.

D. Change of color or materials.

E. Addition of a design enhancement feature such as:

i. Embellished entrance areas.

ii. Articulated corners, especially when entrance is at corner, rounded or chamfered corners ease the transitions from one street facade to the adjoining facade.

iii. Recessed or projecting balconies and entrances.

Billboards, advertising and signage are expressly prohibited as appropriate focal points.

Section 35-673. Site Design Standards

(a) Solar Access. The intent of providing and maintaining solar access to the San Antonio River is to protect the river's specific ecoclimate. The river has a special microclimate of natural and planted vegetation that requires certain levels and balanced amounts of sunlight, space and water. Development must be designed to respect and protect those natural requirements, keeping them in balance and not crowding or altering them so that vegetation does not receive more or less space and water, but particularly sunlight, than is required for normal expected growth.

(1) Building Massing to Provide Solar Access to the River. Building massing shall be so designed as to provide direct sunlight to vegetation in the river channel as defined:

A. The area to be measured for solar access shall be a thirty-foot setback from the river's edge or from the river's edge to the building face, whichever is lesser, parallel to the river for the length of the property.

B. The solar calculations shall be measured exclusive to the applicant's property; that is, shades and shadows of other buildings shall not be included in the calculations. The solar calculations shall only measure the impact of new construction and additions. The shading impact of historic buildings on the site may be excluded from the calculations.

C. The defined area shall receive a minimum of 5.5 hours of direct sunlight, measured at the winter solstice, and 7.5 hours of direct sunlight, measured at the summer solstice.

D. Those properties located on the south side of the river (whose north face is adjacent to the river) shall only be required to measure the sunlight in the 30-foot setback on the opposite bank of the river.

E. Those properties within the river improvement overlay district not directly adjacent to the river are still subject to the provisions of this section. To determine the solar access effect of these buildings on the river the applicant must measure the nearest point to the river of an area defined by a thirty-foot setback from the river's edge, parallel to the river for the length of their property that would be affected by their building. For those buildings on the south side of the river, the 30-foot setback shall be measured only on the opposite bank.

F. However, in those cases where the above conditions cannot be met due to the natural configuration of the river, existing street patterns, or existing buildings, the HDRC may approve a buildings mass and height as allowed by table 674-2.

G. If there is a conflict with this section and another section of this chapter this section shall prevail.

(b) Building Orientation. Buildings should be sited to help define active spaces for area users, provide pedestrian connections between sites, help animate the street scene and define street edges. Consideration to both the street and riverside should be given. The placement of a building on a site should therefore be considered within the context of the

block, as well as how the structure will support the broader design goals for the area.

(2) Primary and Secondary Entrances.

A. Orient a building's primary entrance toward the street with subordinate entrances located on the riverside and/or the interior of the property. On a major thoroughfare street it is acceptable to provide the primary entrance through a common courtyard and then to a street.

B. The primary entrance shall be distinguished by architectural features such as, but not limited to: an entry portal; change in material or color; change in scale of other openings; addition of columns, lintels or canopies.

C. Secondary entrances shall have architectural features that are subordinate to the primary entrance in scale and detail. For purposes of this division subordinate means that the entrance is smaller in height and width, and has fewer or simpler architectural elements.

(f) Plant Materials. A number of soil conditions converge in the San Antonio area to create unique vegetation ecosystems. Along the route of the San Antonio River, the soil conditions vary greatly from the northern boundary near Hildebrand to the city limits near Mission San Francisco de la Espada (Mission Espada) and therefore native and indigenous plants will vary accordingly. Landscaping should reflect the unique soil characteristics of the specific site.

(3) Install Trees to Provide Shade and to Separate Pedestrians From Automobile Traffic. Install street trees along the property line or in the ROW abutting all streets according to minimum requirement standards established in subsection 35-512(b), except where this conflicts with existing downtown Tri-Party improvements in "RIO-3." In "RIO-3" the owner has the option of placing trees at the property line, or along the street edge.

(g) Paving Materials. An important San Antonio landscape tradition is the use of decorative surfaces for paving and other landscape structures. Paving materials and patterns should be carefully chosen to preserve and enhance the pedestrian experience.

(1) Vary Walkway, Patio and Courtyard Paving to Add Visual Interest on the Riverside of Properties Abutting the River. Pervious paving is encouraged where feasible and appropriate to the site.

(i) Street Furnishings. Street furnishings are exterior amenities, including but not limited to, tables, chairs, umbrellas, landscape pots, wait stations, valet stations, bicycle racks, planters, benches, bus shelters, kiosks, waste receptacles and similar items that help to define pedestrian use areas. Handcrafted street furnishings are particularly important in San Antonio, and therefore this tradition of craftsmanship and of providing street furniture is encouraged.

(2) Street Furnishing Materials.

A. Street furnishings shall be made of wood, metal, stone, terra cotta, cast stone, hand-sculpted concrete, or solid surfacing material, such as Corian or Surell.

(4) Street furnishings, such as tables and chairs may not be stored (other than overnight storage) in such a way as to be visible from the river pathway.

(j) Lighting. Site lighting should be considered an integral element of the landscape design of a property. It should help define activity areas and provide interest at night. At the same time, lighting should facilitate safe and convenient circulation for pedestrians, bicyclists and motorists. Overspill of light and light pollution should be avoided.

(1) Site Lighting. Site lighting shall be shielded by permanent attachments to light fixtures so that the light sources are not visible from a public way and any offsite glare is prevented.

A. Site lighting shall include illumination of parking areas, buildings, pedestrian routes, dining areas, design features and public ways.

B. Outdoor spaces adjoining and visible from the river right-of-way shall have average ambient light levels of between one (1) and three (3) foot-candles with a minimum of 0.5-foot candles and a maximum of six (6) footcandles

at any point measured on the ground plane. Interior spaces visible from the river right-of-way on the river level and ground floor level shall use light sources with no more than the equivalent lumens of a one hundred-watt incandescent bulb. Exterior balconies, porches and canopies adjoining and visible from the river right-of-way shall use light sources with the equivalent lumens of a sixty-watt incandescent bulb with average ambient light levels no greater than the lumen output of a one hundred-watt incandescent light bulb as long as average foot candle standards are not exceeded. Accent lighting of landscape or building features including specimen plants, gates, entries, water features, art work, stairs, and ramps may exceed these standards by a multiple of 2.5. Recreational fields and activity areas that require higher light levels shall be screened from the river hike and bike pathways with a landscape buffer.

C. Exterior light fixtures that use the equivalent of more than one hundred-watt incandescent bulbs shall not emit a significant amount of the fixture's total output above a vertical cut-off angle of ninety (90) degrees. Any structural part of the fixture providing this cut-off angle must be permanently affixed.

D. Lighting spillover to the publicly owned areas of the river or across property lines shall not exceed one-half (½) of one (1) foot-candle measured at any point ten (10) feet beyond the property line.

- (2) Provide Lighting for Pedestrian Ways That is Low Scaled for Walking. The position of a lamp in a pedestrian-way light shall not exceed fifteen (15) feet in height above the ground.
- (3) Light Temperature and Color.
 - A. Light temperature and color shall be between 2500° K and 3500° K with a color rendition index (CRI) of eighty (80) or higher, respectively. This restriction is limited to all outdoor spaces adjoining and visible from the river right-of-way and from the interior spaces adjoining the river right-of-way on the river level and ground floor level. Levels shall be determined by product specifications.
- (4) Minimize the Visual Impacts of Exterior Building Lighting.
 - A. All security lighting shall be shielded so that the light sources are not visible from a public way.
 - B. Lighting (uplighting and downlighting) that is positioned to highlight a building or outdoor artwork shall be aimed at the object to be illuminated, not pointed into the sky.
 - C. Fixtures shall not distract from, or obscure important architectural features of the building. Lighting fixtures shall be a subordinate feature on the building unless they are incorporated into the over-all design scheme of the building.
- (5) Prohibited Lighting on the Riverside of Properties Abutting the River.
 - A. Flashing lights.
 - B. Rotating lights.
 - C. Chaser lights.
 - D. Exposed neon.
 - E. Seasonal decorating lights such as festoon, string or rope lights, except between November 20 and January 10.
 - F. Flood lamps.
- (6) Minimize the visual impacts of lighting in parking areas in order to enhance the perception of the nighttime sky and to prevent glare onto adjacent properties. Parking lot light poles are limited to thirty (30) feet in height, shall have a 90° cutoff angle so as to not emit light above the horizontal plane.
- (l) Access to Public Pathway Along the River. These requirements are specifically for those properties adjacent to the river to provide a connection to the publicly owned pathway along the river. The connections are to stimulate and enhance urban activity, provide path connections in an urban context, enliven street activity, and protect the ambiance and character of the river area.
 - (3) Clearly define a key pedestrian gateway into the site from the publicly owned pathway at the river with distinctive architectural or landscape elements.
 - A. The primary gateway from a development to the publicly owned pathway at the river shall be defined by an architectural or landscape element made of stone, brick, tile, metal, rough hewn cedar or hand-formed concrete or through the use of distinctive plantings or planting beds.
- (n) Service Areas and Mechanical Equipment. Service areas and mechanical equipment should be visually unobtrusive and should be integrated with the design of the site and building. Noise generated from mechanical equipment shall not exceed city noise regulations.
 - (1) Locate service entrances, waste disposal areas and other similar uses adjacent to service lanes and away from major streets and the river.
 - C. Air intake and exhaust systems, or other mechanical equipment that generates noise, smoke or odors, shall not be located at the pedestrian level.

Sec. 35-674. Building Design Principles

- (a) Architectural Character. A basic objective for architectural design in the river improvement overlay districts is to encourage the reuse of existing buildings and construction of new, innovative designs that enhance the area, and help to establish distinct identities for each of the zone districts. At the same time, these new buildings should reinforce established building traditions and respect the contexts of neighborhoods. When a new building is constructed, it shall be designed in a manner that reinforces the basic character-defining features of the area. Such features include the way in which a building is located on its site, the manner in which it faces the street and its orientation to the river. When these design variables are arranged in a new building to be similar to those seen traditionally, visual compatibility results.
- (b) Mass and Scale. A building shall appear to have a "human scale." In general, this scale can be accomplished by using familiar forms and elements interpreted in human dimensions. Exterior wall designs shall help pedestrians establish a sense of scale with relation to each building. Articulating the number of floors in a building can help to establish a building's scale, for example, and prevent larger buildings from dwarfing the pedestrian.
 - (1) Express facade components in ways that will help to establish building scale.

A. Treatment of architectural facades shall contain a discernible pattern of mass to void, or windows and doors to solid mass. Openings shall appear in a regular pattern, or be clustered to form a cohesive design. Architectural elements such as columns, lintels, sills, canopies, windows and doors should align with other architectural features on the adjacent facades.

(2) Align horizontal building elements with others in the blockface to establish building scale.

A. Align at least one (1) horizontal building element with another horizontal building element on the same block face. It will be considered to be within alignment if it is within three (3) feet, measured vertically, of the existing architectural element.

(3) Express the distinction between upper and lower floors.

A. Develop the first floor as primarily transparent. The building facade facing a major street shall have at least fifty (50) percent of the street level facade area devoted to display windows and/or windows affording some view into the interior areas. Multi-family residential buildings with no retail or office space are exempt from this requirement.

(4) Where a building facade faces the street or river and exceeds the maximum facade length allowed in Table 674-1 divide the facade of building into modules that express traditional dimensions.

A. The maximum length of an individual wall plane that faces a street or the river shall be as shown in Table 674-1.

Table 674-1

Description	RIO-1	RIO-2	RIO-3	RIO-4	RIO-5	RIO-6
Maximum Facade Length	50 ft.	50 ft.	30 ft.	75 ft.	75 ft.	50 ft.

B. If a building wall plane facing the street or river and exceeds the length allowed in Table 674-1, employ at least two (2) of the following techniques to reduce the perceived mass:

- Change materials with each building module to reduce its perceived mass; or
- Change the height with each building module of a wall plane. The change in height shall be at least ten (10) percent of the vertical height; or
- Change the roof form of each building module to help express the different modules of the building mass; or
- Change the arrangement of windows and other facade articulation features, such as, columns, pilasters or strap work, which divides large planes into smaller components.

(5) Organize the Mass of a Building to Provide Solar Access to the River.

A. One (1) method of doing so is to step the building down toward the river to meet the solar access requirements of subsection 35-673(a).

B. Another method is to set the building back from the river a distance sufficient to meet the solar access requirements of subsection 35-673(a).

(c) Height. Building heights vary along the river corridor, from one-story houses to high-rise hotels and apartments. This diversity of building heights is expected to continue. However, within each zone, a general similarity in building heights should be encouraged in order to help establish a sense of visual continuity. In addition, building heights shall be configured such that a comfortable human scale is established along the edges of properties and views to the river and other significant landmarks are provided while allowing the appropriate density for an area.

(1) The maximum building height shall be as defined in Table 674-2.

A. Solar access standards subsection 35-673(a), and massing standards subsection 35-674(b) also will affect building heights.

Table 674-2

Description	RIO-1	RIO-2	RIO-3	RIO-4	RIO-5	RIO-6
Maximum # of Stories	5	10	None	7	5	4
Maximum Height in Feet	60 ft.	120 ft.	None	84 ft.	60 ft.	50 ft.

(3) On the street-side, the building facade shall appear similar in height to those of other buildings found traditionally in the area.

If fifty (50) percent of the building facades within a block face are predominantly lower than the maximum height allowed, the new building facade on the street-side shall align with the average height of those lower buildings within the block face, or with a particular building that falls within the fifty (50) percent range. However, the remainder of the building may obtain its maximum height by stepping back fifteen (15) feet from the building face.

- (4) Designation of a development node provides for the ability to increase the building height by fifty (50) percent from the requirements set out in article VI.
- (d) Materials and Finishes. Masonry materials are well established as primary features along the river corridor and their use should be continued. Stucco that is detailed to provide a texture and pattern, which conveys a human scale, is also part of the tradition. In general, materials and finishes that provide a sense of human scale, reduce the perceived mass of a building and appear to blend with the natural setting of the river shall be used, especially on major structures.
- (1) Use indigenous materials and traditional building materials for primary wall surfaces. A minimum of seventy-five (75) percent of walls (excluding window fenestrations) shall be composed of the following:
- A. Modular masonry materials including brick, stone, and rusticated masonry block, tile, terra-cotta, structural clay tile and cast stone. Concrete masonry units (CMU) are not allowed.
 - B. Other new materials that convey the texture, scale, and finish similar to traditional building materials.
 - C. Stucco and painted concrete when detailed to express visual interest and convey a sense of scale.
 - D. Painted or stained wood in a lap or shingle pattern.
- (2) The following materials are not permitted as primary building materials and may be used as a secondary material only:
- A. Large expanses of high gloss or shiny metal panels.
 - B. Mirror glass panels. Glass curtain wall buildings are allowed in RIO-3 as long as the river and street levels comply with 35-674(d)(1) above.
- (3) Paint or Finish Colors.
- A. Use natural colors of indigenous building materials for properties that abut the River Walk area.
 - B. Use matte finishes instead of high glossy finishes on wall surfaces. Wood trim and metal trim may be painted with gloss enamel.
 - C. Bright colors may highlight entrances or architectural features.
- (e) Facade Composition. Traditionally, many commercial and multi-family buildings in the core of San Antonio have had facade designs that are organized into three (3) distinct segments: First, a "base" exists, which establishes a scale at the street level; second a "mid-section," or shaft is used, which may include several floors. Finally a "cap" finishes the composition. The cap may take the form of an ornamental roof form or decorative molding and may also include the top floors of the building. This organization helps to give a sense of scale to a building and its use should be encouraged. In order to maintain the sense of scale, buildings should have the same setback as surrounding buildings so as to maintain the street-wall pattern, if clearly established.
- In contrast, the traditional treatment of facades along the riverside has been more modest. This treatment is largely a result of the fact that the riverside was a utilitarian edge and was not oriented to the public. Today, even though orienting buildings to the river is a high priority objective, it is appropriate that these river-oriented facades be simpler in character than those facing the street.
- (1) Street Facade. Buildings that are taller than the street-wall (sixty (60) feet) shall be articulated at the stop of the street wall or stepped back in order to maintain the rhythm of the street wall. Buildings should be composed to include a base, a middle and a cap.
- A. High rise buildings, more than one hundred (100) feet tall, shall terminate with a distinctive top or cap. This can be accomplished by:
 - i. Reducing the bulk of the top twenty (20) percent of the building by ten (10) percent.
 - ii. By stepping back the top twenty (20) percent of the building.
 - iii. Changing the material of the cap.
 - B. Roof forms shall be used to conceal all mechanical equipment and to add architectural interest to the structure.
 - C. Roof surfaces should include strategies to reduce heat island effects such as use of green roofs, photo voltaic panels, and/or the use of roof materials with high solar reflectivity.
- (2) Fenestration. Windows help provide a human scale and so shall be proportioned accordingly.
- D. Curtain wall systems shall be designed with modulating features such as projecting horizontal and/or vertical mullions.
- (3) Entrances. Entrances shall be easy to find, be a special feature of the building, and be appropriately scaled.
- A. Entrances shall be the most prominent on the street side and less prominent on the river side.
 - B. Entrances shall be placed so as to be highly visible.
 - C. The scale of the entrance is determined by the prominence of the function and or the amount of use.
 - D. Entrances shall have a change in material and/or wall plane.
 - E. Entrances should not use excessive storefront systems.
- (4) Riverside facade. The riverside facade of a building shall have simpler detailing and composition than the street facade.

A. Architectural details such as cornices, sills, lintels, door surrounds, water tables and other similar details should use simple curves and handcrafted detailing.

B. Stone detailing shall be rough hewn, and chiseled faced. Smooth faced stone is not permitted as the primary building material, but can be used as accent pieces.

C. Facades on the riverside shall be asymmetrical, pedestrian scale, and give the appearance of the back of a building. That is, in traditional building along the river, the backs of building were designed with simpler details, and appear less formal than the street facades.

(g) Awnings, Canopies and Arcades. (See Figure 674-2) The tradition of sheltering sidewalks with awnings, canopies and arcades on commercial and multi-family buildings is well established in San Antonio and is a practice that should be continued. They offer shade from the hot summer sun and shelter from rainstorms, thereby facilitating pedestrian activity. They also establish a sense of scale for a building, especially at the ground level. Awnings and canopies are appropriate locations for signage. Awnings with signage shall comply with any master signage plan on file with the historic preservation officer for the property. Awnings and canopies installed at street level within the public right-of-way require licensing with the city's capital improvements management services (CIMS) department. Canopies, balconies and awnings installed at river level within the public right-of-way require licensing with the city's downtown operations department.

(1) If awnings, arcades and canopies are to be used they should accentuate the character-defining features of a building.

A. The awning, arcade or canopy shall be located in relationship to the openings of a building. That is, if there are a series of awnings or canopies, they shall be located at the window or door openings. However awnings, canopies and arcades may extend the length of building to provide shade at the first floor for the pedestrian.

B. Awnings, arcades and canopies shall be mounted to highlight architectural features such as moldings that may be found above the storefront.

C. They should match the shape of the opening.

D. Simple shed shapes are appropriate for rectangular openings.

E. Odd shapes and bubble awnings are prohibited except where the shape of an opening requires a bubble awning, or historic precedent shows they have been previously used on the building.

F. Canopies, awnings and arcades shall not conflict with the building's proportions or with the shape of the openings that the awning or canopy covers.

G. Historic canopies shall be repaired or replaced with in-kind materials.

(2) Materials and Color.

A. Awnings and canopies may be constructed of metal, wood or fabric. Certain vinyl is allowed if it has the appearance of natural fiber as approved by the HDRC.

B. Awning color shall coordinate with the building. Natural and earth tone colors are encouraged. Fluorescent colors are not allowed. When used for signage it is appropriate to choose a dark color for the canopy and use light lettering for signage.

(3) Incorporating lighting into the design of a canopy is appropriate.

A. Lights that illuminate the pedestrian way beneath the awning are appropriate.

B. Lights that illuminate the storefront are appropriate.

C. Internally illuminated awnings that glow are prohibited.

UDC Section. 35-675. Archaeology.

When an HDRC application is submitted for commercial development projects within a river improvement overlay district the city archeologist shall review the project application to determine if there is potential of containing intact archaeological deposits utilizing the following documents/methods:

(1)The Texas Sites Atlas for known/recorded sites, site data in the files of the Texas Archeological Research Laboratory and the Texas Historical Commission;

(2)USGS maps;

(3)Soil Survey maps;

(4)Distance to water;

(5)Topographical data;

(6)Predictive settlement patterns;

(7)Archival research and historic maps;

(8)Data on file at the office of historic preservation.

If after review the city archeologist determines there is potential of containing intact archaeological deposits, an

archaeological survey report shall be prepared and submitted. If, after review by the city archeologist, a determination is made that the site has little to no potential of containing intact archaeological deposits, the requirement for an archaeological survey report may be waived.

Upon completion of a survey, owners of property containing inventoried archaeological sites are encouraged to educate the public regarding archaeological components of the site and shall coordinate any efforts with the office of historic preservation.

FINDINGS:

- a. The applicant is requesting a Certificate of Appropriateness for approval to construct a six-story, mixed-use structure on the lot addressed as 1210 E Elmira. This lot is bounded by Schiller Street to the south, E Elmira Street to the west, Myrtle Street to the north and the San Antonio River to the east. This lot is located within the River Improvement Overlay, District 2. This proposal is located on the same lot with a proposed 8-story hotel; however, that proposal is not included in this request.
- b. CONCEPTUAL APPROVAL – This request received conceptual approval at the October 18, 2023, Historic and Design Review Commission hearing with the following stipulations:
 - i. That the applicant coordinate with the San Antonio River Authority in regards to regarding direct access to the San Antonio River, landscaping and maintenance boundaries and storm water control measures. ***The applicant is actively coordinating with SARA.***
 - ii. That all mechanical and service equipment be screened and comply with UDC standards. ***This stipulation has been met.***
 - iii. That final materials specifications and material colors be submitted to OHP staff for review and approval when applying for final approval. Composite siding should not feature a faux wood grain. ***This stipulation has been met.***
 - iv. That all windows be recessed at least two inches within walls, that frames feature dark colors and that windows not feature faux divided lites. ***This stipulation has been met.***
 - v. That a detailed building and landscape lighting plan be submitted to OHP staff for review and approval when applying for final approval. ***This stipulation has been met.***
 - vi. That a detailed landscape plan be submitted to OHP staff for review and approval when applying for final approval. ***This stipulation has been met.***
 - vii. ARCHAEOLOGY – An archaeological investigation is required. The project shall comply with all federal, state, and local laws, rules, and regulations regarding archaeology, as applicable.
- c. CONTEXT & DEVELOPMENT PATTERN – This lot is located in the vicinity of properties that formerly featured industrial uses. Recently, properties have been redeveloped into mixed-use and multi-family residential developments featuring varying heights and massing.
- d. SAN ANTONIO RIVER AUTHORITY COORDINATION – Per the UDC Section 35-672(c)8, consultation with the San Antonio River Authority regarding direct access to the San Antonio River, landscaping and maintenance boundaries and storm water control measures prior to the submission for a Certificate of Appropriateness. The applicant is responsible for complying with this section of the UDC.
- e. SOLAR ACCESS – The UDC Section 35-673(a)(1) provides guidelines for solar access to the San Antonio River regarding new construction. The applicant has provided a solar study noting compliance with the UDC.
- f. PEDESTRIAN CIRCULATION – Per the UDC Section 35-672(a) regarding pedestrian circulation, an applicant shall provide pedestrian access among properties to integrate neighborhoods. The applicant has proposed to integrate the site design and pedestrian access elements of this site into that over a multi-development plan. Staff finds the proposed pedestrian circulation to be appropriate and consistent with the UDC.
- g. CURB CUTS – Per the submitted site plan, the applicant has not proposed a curb cut from Schiller Street into the site. If a curb cut is proposed, the applicant is responsible for complying with all UDC standards regarding profile and width.
- h. SITE DESIGN – The applicant has proposed for the site to be incorporated into the design of a multi-development plan. According to the UDC Section 35-673, buildings should be sited to help define active spaces for area users, provide pedestrian connections between sites, help animate the street scene and define street edges. Primary entrances should be oriented toward the street and shall be distinguishable by an architectural feature. The applicant has proposed a design that features distinguishable entrance elements and pedestrian oriented elements at the street level to address pedestrians. This is consistent with the UDC.

- i. **RIVERSIDE SETBACKS** – The UDC Section 35-672(d)(1) notes that the minimum setback for buildings should be established to reinforce the defined character of the River Improvement Overlay and to help define an edge at the river pathway that is varied according to the relationship of the river and street. For RIO-2, the required setback from the top of bank is fifteen (15) feet. Staff finds that the applicant has met this standard.
- j. **LANDSCAPE DESIGN** – Per the UDC Section 35-673(e) regarding landscape design, a variety in landscape design must be provided with no more than seventy-five (75) percent of the landscape materials, including plants being the same as those on adjacent properties. Additionally, according to the UDC Section 35-674(f), indigenous, non-invasive plant species and tropical plant species are permitted. The applicant has submitted a landscape and hardscape plan noting the proposed landscape and hardscape design and proposed materials. Staff finds this to be appropriate and consistent with the UDC.
- k. **MECHANICAL EQUIPMENT** – The UDC Section 35-673(n) addresses service areas and mechanical equipment and their impact on the public. Service areas and mechanical equipment should be visually unobtrusive and should be integrated with the design of the site and building. Noise generated from mechanical equipment shall not exceed city noise regulations. The applicant is responsible for complying with the UDC Section 35-673(n) at all times. The applicant has provided a roof plan noting that mechanical equipment will be located at the roof level and will be screened by parapet walls of varying heights.
- l. **BUILDING SCALE & MASSING** – According to the UDC Section 35-674(b) a building shall appear to have a “human scale”. To comply with this, a building must (1) express façade components in ways that will help to establish building scale, (2) align horizontal building elements with others in the blockface to establish building scale, (3) express the distinction between upper and lower levels, (4) in this instance, divide the façade of the building into modules that express traditional and (5) organize the mass of a building to provide solar access to the river. The applicant has incorporated various elements that provide a human scale, including human scaled façade openings, human scaled materials, balconies and awnings at each individual level. Staff finds this to be appropriate and consistent with the Guidelines.
- m. **FAÇADE COMPOSITION** – According to the UDC Section 35-674, high rise buildings, more than one hundred (100) feet in height shall terminate with a distinctive top or cap. In addition to this, curtain wall systems shall be designed with modulating features such as projecting horizontal and/or vertical mullions, entrances shall be easy to find, be a special feature of the building and be appropriately scaled and the riverside façade of a building shall have simpler detailing and composition than the street façades. The applicant has separated the building into various sections, including a base, midsection and a building cap. Each of the proposed three distinct façade sections feature unique design elements that note a base, midsection and building cap. Staff finds this to be appropriate and consistent with the Guidelines.
- n. **FAÇADE COMPOSITION (Width)** – The UDC Section 35-674(b) notes that where a building façade faces the street or river and exceeds the maximum façade length allowed in table 674-1 (fifty feet in RIO-2), the building must be divided into modules that express traditional dimensions. The applicant has met this standard of the UDC by separating building massing both vertically and horizontally through the incorporation of balconies, brick column bays, awnings and fenestration.
- o. **BUILDING HEIGHT** – Per the UDC Section 35-674(c) notes a maximum height in RIO-2 of ten (10) stories and 120’ – 0”, in addition to the solar access standards noted in section 35-673(a). The applicant has noted an overall height of approximately 78’ to the primary parapet wall and 83’ to the mechanical penthouse parapet. Staff finds the proposed height to be appropriate and consistent with the UDC.
- p. **BUILDING HEIGHT** – Section 35-674(c)(3) states that building facades shall appear similar in height to those of other buildings found traditionally in the area. This section also states that if fifty (50) percent of the building facades within a block face are predominantly lower than the maximum height allowed, the new building façade on the street-side shall align with the average height of those lower buildings within the block face, or with a particular building that falls within the fifty (50) percent range. Predominantly, the surrounding lots feature surface parking. Existing structures in the immediate vicinity range in height from two (2) to ten (10) stories in height. Staff finds the proposed height to be appropriate and consistent with the UDC.
- q. **MATERIALS** – Regarding materials, the UDC Section 35-674(d)(1) states that indigenous and traditional building materials should be used for primary wall surfaces. A minimum of seventy-five (75) percent of walls (excluding window fenestrations) shall be composed of the following: Modular masonry materials including brick, stone, and rusticated masonry block, tile, terra-cotta, structural clay tile and cast stone. The applicant has proposed materials that include modular brick, fiber cement siding and stucco. The applicant has noted that the proposed fiber cement siding will feature a smooth finish with seven (7) inch exposures. Generally, staff finds the proposed materials to be appropriate and consistent with the UDC. Staff finds that stucco should feature a traditional or non-lumpy finish.


- r. WINDOW MATERIALS – The applicant has proposed vinyl windows with divided lites and dark gray exterior finishes. Generally, staff finds vinyl windows to be appropriate; however, staff finds that they should be recessed at least two (2) inches within each wall opening, per the UDC Section 25-674(e)(A). The applicant has noted an inset that is consistent with the UDC and has confirmed that muntins will be applied to the exterior of window panes.
- s. LIGHTING DESIGN – Lighting design for any project located in a RIO district is an important aspect of not only that particular project's design, but also the adjacent buildings as well as the River Walk. According to the UDC Section 35-673(j), site lighting should be considered an integral element of the landscape design of a property. The applicant is responsible for complying with the UDC regarding landscape and building lighting.
- t. OUTDOOR FURNITURE – The applicant has proposed outdoor seating areas on the site. Outdoor furniture should be consistent with the UDC, and should be submitted for review and approval prior to installation. At no time shall outdoor furniture impede upon or block pedestrian traffic at the public right of way. Per the submitted site plan, outdoor furniture has been proposed within the property limits.
- u. ARCHAEOLOGY – The project area is located within a River Improvement Overlay District and is adjacent to the historical alignment of the San Antonio River, an area known to contain significant historic and prehistoric archaeological deposits. In addition, the property is in close proximity to previously recorded archaeological site 41BX2402. Thus, the property may contain sites, some of which may be significant. Therefore, an archaeological investigation is required. The project shall comply with all federal, state, and local laws, rules, and regulations regarding archaeology, as applicable.

RECOMMENDATION:


Staff recommends approval based on findings a through u with the following stipulations:

- i. That the applicant completes coordination with the San Antonio River Authority in regards to regarding direct access to the San Antonio River, landscaping and maintenance boundaries and storm water control measures.
- ii. ARCHAEOLOGY – An archaeological investigation is required. The project shall comply with all federal, state, and local laws, rules, and regulations regarding archaeology, as applicable.

City of San Antonio One Stop



October 11, 2023



**Coopers Row North
HDRC Final Approval
Narrative**

Coopers Row North (Project) consists of an approximately .33-acre site built out with a six-story apartment building consisting of 5 stories of cold formed metal framing above a 1-story concrete podium with approximately 74 units and associated site work, planting, hardscape and irrigation. The ground floor will be commercial space.

The site is currently a parking lot across the River from Pearl. An aerial photo of the site is attached. The exterior of the building is planned to be brick masonry with fiber cement infill between windows, with the façade facing the planned hotel being painted stucco.

This project is phase II of the apartments (Coopers Row) currently under construction at 1118 E Elmira, and there will not be any amenities or parking within Coopers Row North. Residents will use the parking and amenities being built with Coopers Row.

**Coopers Row North
HDRC Final Approval
Planned Materials**

Exterior Building Materials


- Brick
- Complimentary brick
- Fiber cement panels
- Stucco

Landscape/Hardscape Materials



- Brick Pavers
- Concrete
- Landscaping

















Winter Solstice - 8:00 AM




Winter Solstice - 10:00 AM



Winter Solstice - 12:00 PM



Winter Solstice - 3:00 PM




Winter Solstice - 5:00 PM


- Property Boundary
- Extent of Study Area
- River

**Extent of Study Area align with extent of proposed building and offset 30' from rivers edge per UDC 35-673(a)1.A


Winter Solstice
Full Solar Access from 7:24 AM to 5:39 PM
Receives 10.25 hours of sunlight (5.5 required)




Summer Solstice - 7:00 AM




Summer Solstice - 10:00 AM



Summer Solstice - 12:00 PM



Summer Solstice - 3:00 PM



Summer Solstice - 5:00 PM

- Property Boundary
- Extent of Study Area
- River

**Extent of Study Area align with extent of proposed building and offset 30' from rivers edge per UDC 35-673(a)1.A


Summer Solstice
Full Solar Access from 6:34 AM to 3:49 PM
Receives 9.25 hours of sunlight (7.5 required)




SITE PLAN NOTES:

1. REFER TO CIVIL ENGINEER DRAWINGS FOR SITE DIMENSIONS, DRAINAGE, EASEMENTS, PROPERTY LINES AND SETBACKS.
2. REFER TO LANDSCAPE ARCHITECT DRAWINGS FOR LANDSCAPING, SIDEWALKS, SPOT ELEVATIONS AND FINAL GRADES.
3. REFER TO CIVIL AND ELECTRICAL DRAWINGS FOR ALL TRANSFORMER LOCATIONS AND REQUIRED CLEARANCES.
4. SLOPE ALL GRADING, CONCRETE WALKS & ENTRANCES AWAY FROM EXTERIOR WALLS. SIDEWALKS SHALL NOT HAVE A RUN SLOPE GREATER THAN 5% NOR A CROSS SLOPE GREATER THAN 2% CHANGES IN LEVEL BETWEEN 1/4" & 1/2" HIGH SHALL BE BEVELED WITH A SLOPE NOT STEEPER THAN 1:2
5. ALL PUBLIC ROUTES, ENTRANCES AND EXITS SHALL BE IN ACCORDANCE TO ANSI, ADA AND TAS CRITERIA.
6. ALL PUBLIC ACCOMMODATIONS SHALL BE IN ACCORDANCE WITH ANSI, ADA AND TAS CRITERIA.
7. REFER LANDSCAPE DRAWINGS FOR PLANTING, PAVING, ETC.
8. DIMENSIONS AND FINISH FLOOR ELEVATIONS ARE FOR REFERENCE ONLY. REFER TO CIVIL DRAWINGS FOR EXACT BOUNDARY, DIMENSION CONTROL AND F.F.E. CONTROL ELEVATIONS.
9. ENTRY FROM LOGGIA/EXTERIOR AREAS TO BUILDING SHALL HAVE BARRIER FREE TRANSITION.
10. WHERE SIDEWALKS INTERSECT, THE SECTION OF CONCRETE SHOULD HAVE A SLOPE NOT GREATER THAN 2% IN ANY DIRECTION.


<p>INDICATES LOCATION OF ACCESSIBLE ROUTE INTO BUILDING. ALL SLOPES SHALL MAINTAIN A MAXIMUM RUNNING SLOPE OF 5% AND A MAXIMUM CROSS SLOPE OF 2%.</p> <p>INDICATES LOCATION OF ACCESSIBLE ENTRANCE INTO BUILDING</p>	<p>-----</p> <p>-----▶</p>
----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------	----------------------------




4 LOGGIA RCP
SCALE: 1/8" = 1'-0"



3 ENLARGED PLAN - COVERED OUTDOOR PATIO
SCALE: 1/8" = 1'-0"



2 ENLARGED PLAN - LOGGIA
SCALE: 1/8" = 1'-0"



1 OVERALL PLAN - LEVEL 1
SCALE: 3/32" = 1'-0"

BUILDING PLAN LEGEND:			
	F.E. FIRE EXTINGUISHER CABINET (SEMI RECESSED)	TELE. TELECOMM CLOSET	
	F.E. FIRE EXTINGUISHER (WALL MOUNTED)	MECH. MECHANICAL CLOSET	
	WX SCHEDULED PARTITION TYPE	M.C. METER CLOSET	
	UX SCHEDULED DOOR TYPE	B. BOLLARD	
	X SCHEDULED WINDOW TYPE	S.C. STEEL COLUMN (RE-STRUCT. DWG'S FOR SIZE)	
	SX SCHEDULED STOREFRONT	E.J. EXPANSION JOINT	
	B.F.T. BARRIER FREE THRESHOLD	D.D. DECK DRAIN	
	F.O.S. FACE OF STUD (METAL)	S.P. STANDPIPE	
	F.O.M. FACE OF MASONRY	F.D. FLOOR DRAIN	
	F.O.C. FACE OF CONCRETE	B.L. BRICK LEDGE	
	A.S. AIRSPACE		RD. ROOF DRAIN
	M.O. MASONRY OPENING	---	PROPERTY LINE
	ABV. ABOVE	---	DEMISING / CORRIDOR WALL
	1 VARIES TYP. CORRIDOR BUILDOUT		9'-0" A.F.F. FURR DOWN
			8'-6" A.F.F. FURR DOWN

GENERAL NOTES:	
WALL FRAMING NOTES:	
1. EXTERIOR WALLS SHALL BE 6" MTL STUD FRAMING UNLESS NOTED OTHERWISE. EXTERIOR LOAD BEARING WALLS TO BE PARTITION TYPE W1.2b. ALL OTHER EXTERIOR WALLS TO BE PARTITION TYPE W1.2a.	
2. INTERIOR CORRIDOR WALLS SHALL BE 6" MTL STUD FRAMING, PARTITION TYPE W3.2a.	
3. INTERIOR TENANT SEPARATION WALLS SHALL BE 6" MTL STUD FRAMING, PARTITION TYPE W2.2.	
4. UNIT INTERIOR LOAD BEARING WALLS SHALL BE 6" MTL STUD FRAMING, PARTITION TYPE W4.2b.	
COMMON AREA FLOOR FINISHES:	
BUILDING CORRIDORS:	CARPET TILE (SELECTED BY OWNER)
TENANT STORAGE:	CLEAR, NON-SLIP SEALER
ELEC. ROOMS:	CLEAR, NON-SLIP SEALER
MECHANICAL CLOSETS:	CLEAR, NON-SLIP SEALER

COOPERS ROW NORTH

1118 E. LEMIRA, BLDG. 2
SAN ANTONIO, TX 78215

OXBOW

GMP PRICING - 06/13/24

NOT FOR
REGULATORY
APPROVAL,
PERMITTING, OR
CONSTRUCTION

ARCHITECT
OF RECORD:
MICHAEL GONOS

REGISTRATION
NUMBER:
24287

ISSUED:
08/25/23 - SCHEMATIC DESIGN
09/13/23 - SCHEMATIC RE-ISSUE
10/20/23 - 100% DESIGN DEVELOPMENT
02/16/24 - 100% DD RE-ISSUE
04/12/24 - 50% CD
05/29/24 - ISSUE FOR PERMIT

PROJECT NO: 23-18
SHEET CONTENTS:
OVERALL PLAN -
LEVEL 1


SCALE: As indicated
SHEET NO.

A4.1.0

Autodesk Docs/Oxbow 02/23/24-Oxbow_23-18.rvt

W PARTNERSHIP
Architects | Planners


5120 WOODWAY DR., SUITE 8000 - HOUSTON, TEXAS 77056
713.993.0439 - WWW.WPARTNERSHIP.COM




1

OVERALL PLAN - LEVEL 2

SCALE: 3/32" = 1'-0"



3/32 inch = 1 foot



BUILDING PLAN LEGEND:

	F.E. FIRE EXTINGUISHER CABINET (SEMI RECESSED)	TELE. TELECOMM CLOSET
	F.E. FIRE EXTINGUISHER (WALL MOUNTED)	MECH. MECHANICAL CLOSET
	WX SCHEDULED PARTITION TYPE	T.S. TENANT STORAGE
	UX SCHEDULED DOOR TYPE	M.C. METER CLOSET
	X SCHEDULED WINDOW TYPE	B. BOLLARD
	SX SCHEDULED STOREFRONT	S.C. STEEL COLUMN (RE-STRUCT. DWG'S FOR SIZE)
	B.F.T. BARRIER FREE THRESHOLD	E.J. EXPANSION JOINT
	F.O.S. FACE OF STUD (METAL)	D.D. DECK DRAIN
	F.O.M. FACE OF MASONRY	S.P. STANDPIPE
	F.O.C. FACE OF CONCRETE	F.D. FLOOR DRAIN
	A.S. AIRSPACE	B.L. BRICK LEDGE
	M.O. MASONRY OPENING	RD. ROOF DRAIN
	ABV. ABOVE	--- PROPERTY LINE
	1 VARIES TYP. CORRIDOR BUILDOUT	DEMISING / CORRIDOR WALL
	9' - 0" A.F.F. FURR DOWN	8' - 6" A.F.F. FURR DOWN

GENERAL NOTES:

WALL FRAMING NOTES:

- EXTERIOR WALLS SHALL BE 6" MTL STUD FRAMING UNLESS NOTED OTHERWISE. EXTERIOR LOAD BEARING WALLS TO BE PARTITION TYPE W1.2b. ALL OTHER EXTERIOR WALLS TO BE PARTITION TYPE W1.2a.
- INTERIOR CORRIDOR WALLS SHALL BE 6" MTL STUD FRAMING, PARTITION TYPE W3.2a.
- INTERIOR TENANT SEPARATION WALLS SHALL BE 6" MTL STUD FRAMING, PARTITION TYPE W2.2.
- UNIT INTERIOR LOAD BEARING WALLS SHALL BE 6" MTL STUD FRAMING, PARTITION TYPE W4.2b.

COMMON AREA FLOOR FINISHES:

BUILDING CORRIDORS:	CARPET TILE (SELECTED BY OWNER)
TENANT STORAGE:	CLEAR, NON-SLIP SEALER
ELEC. ROOMS:	CLEAR, NON-SLIP SEALER
MECHANICAL CLOSETS:	CLEAR, NON-SLIP SEALER

COOPERS ROW NORTH

1118 E. LUMINA, BLDG. 2
SAN ANTONIO, TX 78215

OXBOW

GMP PRICING - 06/13/24

NOT FOR
REGULATORY
APPROVAL,
PERMITTING, OR
CONSTRUCTION

ARCHITECT OF RECORD:	REGISTRATION NUMBER:
MICHAEL GONOS	24287

ISSUED:
08/25/23 - SCHEMATIC DESIGN
09/13/23 - SCHEMATIC RE-ISSUE
10/20/23 - 100% DESIGN DEVELOPMENT
02/16/24 - 100% DD RE-ISSUE
04/12/24 - 50% CD
05/29/24 - ISSUE FOR PERMIT

PROJECT NO: 23-18
SHEET CONTENTS:
OVERALL PLAN -
LEVEL 2

SCALE: 3/32" = 1'-0"

SHEET NO.

A4.2.0

Autodesk Docs/Oxbow 002318-A4.2.0-002318-A4.2.0

NO.

DATE:

REVISION DESCRIPTION:

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

22

23

24

25

26

27

28

29

30

31

32

33

34

35

36

37

38

39

40

41

42

43

44

45

46

47

48

49

50

51

52

53

54

55

56

57

58

59

60

61

62

63

64

65

66

67

68

69

70

71

72

73

74

75

76

77

78

79

80

81

82

83

84

85

86

87

88

89

90

91

92

93

94

95

96

97

98

99

100

101

102

103

104

105

106

107

108

109

110

111

112

113

114

115

116

117

118

119

120

121

122

123

124

125

126

127

128

129

130

131

132

133

134

135

136

137

138

139

140

141

142

143

144

145

146

147

148

149

150

151

152

153

154

155

156

157

158

159

160

161

162

163

164

165

166

167

168

169

170

171

172

173

174

175

176

177

178

179

180

181

182

183

184

185

186

187

188

189

190

191

192

193

194

195

196

197

198

199

200

201

202

203

204

205

206

207

208

209

210

211

212

213

214

215

216

217

218

219

220

221

222

223

224

225

226

227

228

229

230

231

232

233

234

235

236

237

238

239

240

241

242

243

244

245

246

247

248

249

250

251

252

253

254

255

256

257

258

259

260

261

262

263

264

265

266

267

268

269

270

271

272

273

274


275

276

277

278

279



GENERAL NOTES:

WALL FRAMING NOTES:

1. EXTERIOR WALLS SHALL BE 6" MTL STUD FRAMING UNLESS NOTED OTHERWISE. EXTERIOR LOAD BEARING WALLS TO BE PARTITION TYPE W1.2b ALL OTHER EXTERIOR WALLS TO BE PARTITION TYPE W1.2a.
2. INTERIOR CORRIDOR WALLS SHALL BE 6" MTL STUD FRAMING, PARTITION TYPE W3.2a
3. INTERIOR TENANT SEPARATION WALLS SHALL BE 6" MTL STUD FRAMING, PARTITION TYPE W2.2.
4. UNIT INTERIOR LOAD BEARING WALLS SHALL BE 6" MTL STUD FRAMING, PARTITION TYPE W4.2b.

COMMON AREA FLOOR FINISHES:

BUILDING CORRIDORS:	CARPET TILE (SELECTED BY OWNER)
TENANT STORAGE:	CLEAR, NON-SLIP SEALER
ELEC. ROOMS:	CLEAR, NON-SLIP SEALER
MECHANICAL CLOSETS:	CLEAR, NON-SLIP SEALER

inc:

NO.	
DATE:	

COOPERS ROW NORTH

1118 E ELMIRA, BLDG. 2
SAN ANTONIO, TX 78215

OXBOW

GMP PRICING - 06/13/24

NOT FOR
REGULATORY
APPROVAL,
PERMITTING, OR
CONSTRUCTION

ARCHITECT OF RECORD: MICHAEL GONOS	REGISTRATION NUMBER: 24287
-------------------------------------------------	-----------------------------------------


ISSUED:
08/25/23 - SCHEMATIC DESIGN
09/13/23 - SCHEMATIC RE-ISSUE
10/20/23 - 100% DESIGN DEVELOPMENT
02/16/24 - 100% DD RE-ISSUE
04/12/24 - 50% CD
05/29/24 - ISSUE FOR PERMIT

These plans are copyrighted and are subject to copyright protection as an "architectural work" under Section 203 of the Copyright Act of 1990, and known as Architectural Works Copyright Promotion Act of 1990. The protection includes, but is not limited to, the overall form, as well as the arrangement and composition of spaces and elements of the design. Under such protection, unauthorized use of these plans, work or forms represented can legally result in the cessation of such construction or buildings being altered and/or raised. Under such protection, unauthorized use of these plans, work or forms represented can legally result in the cessation of such construction or buildings being altered and/or raised.


PROJECT NO: 23-18
SHEET CONTENTS:
**OVERALL PLAN -
LEVEL 3**

SCALE: 3/32" = 1'-0"

A4.3.0



SCALE: 3/32" = 1'-0"



NOTE: REFER TO SHEET A4.2.0 FOR ADDITIONAL DIMENSIONS AND INFORMATION

COOPERS ROW NORTH
1118 E. ELMIRA, BLDG. 2
SAN ANTONIO, TX 78215


OXBOW

GMP PRICING - 06/13/24

SCALE: 3/32" = 1'-0"

SHEET NO.

A4.5.0



CRICKET (SLOPE, ACHIEVED W/ OVER FRAMING)

A/C CONDENSERS ON ROOF RACKS (RE: MEP DWGS)

SCUPPER/ DOWNSPOUT (5'X5' D.S., U.N.O.)

ROOF TOP UNIT (R.T.U.)

3'-0" WIDE ROOF TRAFFIC PADS

MIN. 36" X 72" ROOF ACCESS HATCH

ROOF DRAIN / OVERFLOW DRAIN


ELEVATION (T.O. PARAPET FRAMING ABV. T.O. PLATE)

ROOF PLAN LEGEND


ROOF PLAN NOTES

LOW SLOPE ROOF:

- ALL ROOF AREAS SHALL SLOPE TO DRAIN TO ROOF DRAINS & SCUPPERS OR SLOPE TO COLLECTOR BOXES W/ 5'X5' DOWNSPOUTS PER PLANS AND SHALL BE ROUTED TO STORM. (RE: M.E.P. AND CIVIL DWGS).
- ROOF SYSTEM TO BE THERMOPLASTIC POLYOLEFIN (TPO) SINGLE-PLY ROOFING MEMBRANES. INSTALL PER MANUFACTURER'S GUIDELINES.
- ALL MAIN LOW SLOPE ROOFS SHALL HAVE A MINIMUM SLOPE OF 3/8" PER FOOT U.N.O.
- ALL CRICKETS SLOPES SHALL BE 1/4" PER FOOT MINIMUM U.N.O.
- REFER TO M.E.P. DRAWINGS FOR EQUIPMENT LOCATION, CONDENSING UNIT COUNTS, RTU'S, EXHAUST FANS ETC.
- PROVIDE WALKING SURFACES AROUND EQUIPMENT IN ACCORDANCE TO ROOFING MEMBRANE MANUFACTURER'S RECOMMENDATION. REFER TO PLANS FOR LOCATIONS.
- PARAPET HEIGHT SHALL NOT EXCEED 5'-0" ABOVE ROOF DECK WITHOUT KICKER SUPPORT (RE: STRUCT. DWG.).
- ALL A/C CONDENSERS TO BE MOUNTED ON METAL ROOF RACK AND ANCHORED TO ROOF DECK, MIN. 24" ABOVE ROOF DECK.
- REFER TO PLUMBING DRAWINGS FOR ROOF DRAINS SIZE AND CONNECTION. SECONDARY ROOF DRAINS SHALL BE A MAX. OF 2" ABOVE THE PRIMARY ROOF DRAINS.
- ALL MECHANICAL EQUIPMENT AND OTHER ITEMS THAT REQUIRE SERVICE SHALL BE LOCATED 10'-0" MINIMUM FROM THE EDGE OF THE ROOF WHERE THE TOP OF PARAPET IS LESS THAN 42" ABOVE THE SURFACE OF THE ROOF. ROOF ACCESS HATCHES SHALL BE LOCATED 10 FEET MINIMUM FROM THE EDGE OF THE ROOF.
- MINIMUM CURB HEIGHT FOR ALL ROOF MOUNTED HVAC EQUIPMENT TO BE 12" HEIGHT. CRICKETS TO BE INSTALLED BEHIND ALL CURBS WITH A MINIMUM SLOPE OF 1/4" PER FOOT.
- FOR CONDENSER UNITS LOCATED DIRECTLY ABOVE BEDROOMS, PROVIDE UPGRADED VIBRATION ISOLATION PADS PER OWNER'S SELECTION.
- REFER TO FLOOR / CEILING ASSEMBLY SHEET AD11.1 FOR ANY ADDITIONAL ROOFING INFORMATION.




ARCHITECT OF RECORD:	REGISTRATION NUMBER:
MICHAEL GONOS	24287
ISSUED:	
08/25/23 - SCHEMATIC DESIGN	
09/13/23 - SCHEMATIC RE-ISSUE	
10/20/23 - 100% DESIGN DEVELOPMENT	
02/16/24 - 100% DD RE-ISSUE	
04/12/24 - 50% CD	
05/29/24 - ISSUE FOR PERMIT	




4 WALL SECTION


SCALE: 1/4" = 1'-0"



3 WALL SECTION






2 WALL SECTION



1 WALL SECTION

WALL SECTION LEGEND

SCHEDULED ROOF/ CEILING ASSEMBLY TYPE; RE: AD1.11	
SCHEDULED FLOOR/ CEILING ASSEMBLY TYPE; RE: AD1.11	
SCHEDULED WALL PARTITION TYPE; RE: AD1.21	

[illegible]

COOPERS ROW NORTH

1118 E ELMIRA, BLDG. 2
SAN ANTONIO, TX 78215





OXBOW
ISSUE FOR PERMIT - 05/29/24






ARCHITECT OF RECORD:	REGISTRATION NUMBER:
MICHAEL GONOS	24287
ISSUED:	
08/25/23 - SCHEMATIC DESIGN	
09/13/23 - SCHEMATIC RE-ISSUE	
10/20/23 - 100% DESIGN DEVELOPMENT	
02/16/24 - 100% DD RE-ISSUE	
04/12/24 - 50% CD	
05/29/24 - ISSUE FOR PERMIT	

PROJECT NO: 23-18
SHEET CONTENTS:
**EXTERIOR WALL
SECTIONS**










SCALE: 1/4" = 1'-0"
SHEET NO.
AD2.2.2
5/30/2024 1:36:12 PM
Autodesk® AutoCAD® 2023 (64-bit) (Autodesk® 2023.3.1)



WALL SECTION LEGEND

SCHEDULED ROOF/ CEILING ASSEMBLY TYPE: RE: AD1.1	
SCHEDULED FLOOR/ CEILING ASSEMBLY TYPE: RE: AD1.1	
SCHEDULED WALL PARTITION TYPE; RE: AD1.2.1	







1. THE GENERAL CONTRACTOR SHALL SCHEDULE A PRE-CONSTRUCTION CONFERENCE WITH LANDSCAPE ARCHITECT PRIOR TO MOBILIZATION TO DISCUSS AND MARK ALL TREES TO BE PROTECTED AND REMOVED.
2. THE GENERAL CONTRACTOR SHALL NOTIFY LANDSCAPE ARCHITECT OF ANY EXISTING CONDITIONS THAT PREVENT CONSTRUCTION AS DETAILED.
3. ALL DIMENSIONS MUST BE VERIFIED ON SITE. NOTIFY THE LANDSCAPE ARCHITECT IF THERE ARE ANY DISCREPANCIES BEFORE PROCEEDING WITH THE WORK.
4. CONTRACTOR SHALL IMMEDIATELY NOTIFY THE LANDSCAPE ARCHITECT OF ANY QUESTIONS THAT MAY ARISE CONCERNING THE INTENT, PLACEMENT, OR LIMITS OF DIMENSIONS NECESSARY FOR THE CONSTRUCTION OF THIS PROJECT.
5. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR ESTABLISHING SUBGRADE FOR ALL HARDSCAPE AND PLANTING AREAS. SUBGRADE FOR PLANTING AREAS SHALL BE 12" BELOW LABELED FINISH GRADE TO RECEIVE 12" SOIL MIX AND 4" MULCH BY LANDSCAPE CONTRACTOR. DO NOT EXCAVATE IN THE ROOT PROTECTION ZONE OF EXISTING TREES. THOSE AREAS ARE TO RECEIVE 2" OF COMPOST MIXED INTO THE SOIL BY HAND AT TIME OF PLANTING.
6. CONTRACTOR SHALL ALERT LANDSCAPE ARCHITECT WHEN SUBGRADE HAS BEEN ESTABLISHED FOR REVIEW PRIOR TO BACKFILLING WITH SOIL MIX.

PAVING					
KEY	DESCRIPTION / MODEL NUMBER	COLOR	FINISH	CONTRACT	REMARKS
PV1	BROOM FINISH CONCRETE PAVING	STANDARD GRAY	BROOM FINISH	N/A	CONTRACTOR TO PROVIDE MOCKUP FOR REVIEW.
PV2	ACID-ETCH CONCRETE PAVING	STANDARD GRAY	ACID-ETCH	N/A	CONTRACTOR TO PROVIDE MOCKUP FOR REVIEW.
PV3	INTEGRAL COLOR ACID-ETCH CONCRETE PAVING	INTEGRAL COLOR 'SOAPSTONE' BY BUTTERFIELD	ACID-ETCH WITH SCORED PATTERN	N/A	CONTRACTOR TO PROVIDE MOCKUP FOR REVIEW.
PV4	INTEGRAL COLOR ROCK SALT CONCRETE PAVING	INTEGRAL COLOR 'SOAPSTONE' BY BUTTERFIELD	ROCK SALT WITH SCORED PATTERN	N/A	CONTRACTOR TO PROVIDE MOCKUP FOR REVIEW.
PV5	RUNNING BOND CONC. PAVER KEYSTONE HARDSCAPES HOLLAND STONE 4" X 8" X 60MM	50/50 BLEND ANTIQUE SAVANNAH AND ANTIQUE TAN	SHOTBLAST FINISH	N/A	CONTRACTOR TO PROVIDE MOCKUP FOR REVIEW.
PV6	STACKED SOLDIER CONC. PAVER KEYSTONE HARDSCAPES VERONA 3" X 12" X 60MM	PEWTER	SHOTBLAST FINISH	N/A	CONTRACTOR TO PROVIDE MOCKUP FOR REVIEW.
PV7	HERRINGBONE CONC. PAVER KEYSTONE HARDSCAPES HOLLAND STONE 4" X 8" X 60MM	50/50 BLEND ANTIQUE SAVANNAH AND ANTIQUE TAN	SHOTBLAST FINISH	N/A	CONTRACTOR TO PROVIDE MOCKUP FOR REVIEW.
PV8	STAGGERED JOINT PORCELAIN PAVER FROM FLORIDA TILE 2MM PORCELAIN PAVER 24" X 24" AND 12" X 24"	FELDSPAR	MINERAL	N/A	CONTRACTOR TO PROVIDE MOCKUP FOR REVIEW.



DETAIL KEYS

DETAIL NUMBER

DETAIL SHEET

SECTION SYMBOL

DETAIL NUMBER

DETAIL SHEET

ELEVATION SYMBOL

DETAIL NUMBER

DETAIL SHEET

_____ LOC _____ LIMIT OF CONTRACT
 _____ - - _____ PROPERTY LINE



#1 CONTAINER - 10
#3 CONTAINER - 10
#5 CONTAINER - 5

2 SCALE: NOT TO SCALE

_____ LOC _____ LIMIT OF CONTRACT
 _____ - - - _____ PROPERTY LINE