

HISTORIC AND DESIGN REVIEW COMMISSION

August 21, 2024

HDRC CASE NO: 2024-292
ADDRESS: 901 N ALAMO ST
LEGAL DESCRIPTION: NCB 454 BLK 32 LOT 9, 10 & 11
ZONING: FBZ T6-1, H
CITY COUNCIL DIST.: 1
DISTRICT: Alamo Plaza Historic District
APPLICANT: Hue Nguyen/901 NORTH ALAMO LLC
OWNER: Hue Nguyen/901 NORTH ALAMO LLC
TYPE OF WORK: Exterior alterations
APPLICATION RECEIVED: July 30, 2024
60-DAY REVIEW: September 28, 2024
CASE MANAGER: Rachel Rettaliata

REQUEST:

The applicant is requesting a Certificate of Appropriateness for approval to:

1. Remove and reconstruct the 2-story front porch. This includes incorporating an existing portion of enclosed porch and extending beyond the porch footprint to the south.
2. Replace the existing stucco cladding with Hardie siding.
3. Construct a 1-story rear addition.

APPLICABLE CITATIONS:

Historic Design Guidelines, Chapter 2, Exterior Maintenance and Alterations

1. Materials: Woodwork

A. MAINTENANCE (PRESERVATION)

- i. *Inspections*—Conduct semi-annual inspections of all exterior wood elements to verify condition and determine maintenance needs.
- ii. *Cleaning*—Clean exterior surfaces annually with mild household cleaners and water. Avoid using high pressure power washing and any abrasive cleaning or striping methods that can damage the historic wood siding and detailing.
- iii. *Paint preparation*—Remove peeling, flaking, or failing paint surfaces from historic woodwork using the gentlest means possible to protect the integrity of the historic wood surface. Acceptable methods for paint removal include scraping and sanding, thermal removal, and when necessary, mild chemical strippers. Sand blasting and water blasting should never be used to remove paint from any surface. Sand only to the next sound level of paint, not all the way to the wood, and address any moisture and deterioration issues before repainting.
- iv. *Repainting*—Paint once the surface is clean and dry using a paint type that will adhere to the surface properly. See *General Paint Type Recommendations* in Preservation Brief #10 listed under Additional Resources for more information.

- v. *Repair*—Repair deteriorated areas or refasten loose elements with an exterior wood filler, epoxy, or glue.

B. ALTERATIONS (REHABILITATION, RESTORATION, AND RECONSTRUCTION)

- i. *Façade materials*—Avoid removing materials that are in good condition or that can be repaired in place. Consider exposing original wood siding if it is currently covered with vinyl or aluminum siding, stucco, or other materials that have not achieved historic significance.
- ii. *Materials*—Use in-kind materials when possible or materials similar in size, scale, and character when exterior woodwork is beyond repair. Ensure replacement siding is installed to match the original pattern, including exposures. Do not introduce modern materials that can accelerate and hide deterioration of historic materials. Hardiboard and other cementitious materials are not recommended.
- iii. *Replacement elements*—Replace wood elements in-kind as a replacement for existing wood siding, matching in profile, dimensions, material, and finish, when beyond repair.

2. Materials: Masonry and Stucco

A. MAINTENANCE (PRESERVATION)

- i. *Paint*—Avoid painting historically unpainted surfaces. Exceptions may be made for severely deteriorated material where other consolidation or stabilization methods are not appropriate. When painting is acceptable, utilize a water permeable paint to avoid trapping water within the masonry.
 - ii. *Clear area*—Keep the area where masonry or stucco meets the ground clear of water, moisture, and vegetation.
 - iii. *Vegetation*—Avoid allowing ivy or other vegetation to grow on masonry or stucco walls, as it may loosen mortar and stucco and increase trapped moisture.
 - iv. *Cleaning*—Use the gentlest means possible to clean masonry and stucco when needed, as improper cleaning can damage the surface. Avoid the use of any abrasive, strong chemical, sandblasting, or high-pressure cleaning method.
- B. ALTERATIONS (REHABILITATION, RESTORATION, AND RECONSTRUCTION)**
- i. *Patching*—Repair masonry or stucco by patching or replacing it with in-kind materials whenever possible. Utilize similar materials that are compatible with the original in terms of composition, texture, application technique, color, and detail, when in-kind replacement is not possible. EIFS is not an appropriate patching or replacement material for stucco.
 - ii. *Repointing*—The removal of old or deteriorated mortar should be done carefully by a professional to ensure that masonry units are not damaged in the process. Use mortar that matches the original in color, profile, and composition when repointing. Incompatible mortar can exceed the strength of historic masonry and results in deterioration. Ensure that the new joint matches the profile of the old joint when viewed in section. It is recommended that a test panel is prepared to ensure the mortar is the right strength and color.
 - iii. *Removing paint*—Take care when removing paint from masonry as the paint may be providing a protectant layer or hiding modifications to the building. Use the gentlest means possible, such as alkaline poultice cleaners and strippers, to remove paint from masonry.
 - iv. *Removing stucco*—Remove stucco from masonry surfaces where it is historically inappropriate. Prepare a test panel to ensure that underlying masonry has not been irreversibly damaged before proceeding.

3. Materials: Roofs

A. MAINTENANCE (PRESERVATION)

- i. *Regular maintenance and cleaning*—Avoid the build-up of accumulated dirt and retained moisture. This can lead to the growth of moss and other vegetation, which can lead to roof damage. Check roof surface for breaks or holes and flashing for open seams and repair as needed.

B. ALTERATIONS (REHABILITATION, RESTORATION, AND RECONSTRUCTION)

- i. *Roof replacement*—Consider roof replacement when more than 25-30 percent of the roof area is damaged or 25-30 percent of the roof tiles (slate, clay tile, or cement) or shingles are missing or damaged.
- ii. *Roof form*—Preserve the original shape, line, pitch, and overhang of historic roofs when replacement is necessary.
- iii. *Roof features*—Preserve and repair distinctive roof features such as cornices, parapets, dormers, open eaves with exposed rafters and decorative or plain rafter tails, flared eaves or decorative purlins, and brackets with shaped ends.
- iv. *Materials: sloped roofs*—Replace roofing materials in-kind whenever possible when the roof must be replaced. Retain and re-use historic materials when large-scale replacement of roof materials other than asphalt shingles is required (e.g., slate or clay tiles). Salvaged materials should be re-used on roof forms that are most visible from the public right-of-way. Match new roofing materials to the original materials in terms of their scale, color, texture, profile, and style, or select materials consistent with the building style, when in-kind replacement is not possible.
- v. *Materials: flat roofs*—Allow use of contemporary roofing materials on flat or gently sloping roofs not visible from the public right-of-way.
- vi. *Materials: metal roofs*—Use metal roofs on structures that historically had a metal roof or where a metal roof is appropriate for the style or construction period. Refer to Checklist for Metal Roofs on page 10 for desired metal roof specifications when considering a new metal roof. New metal roofs that adhere to these guidelines can be approved administratively as long as documentation can be provided that shows that the home has historically had a metal roof.
- vii. *Roof vents*—Maintain existing historic roof vents. When deteriorated beyond repair, replace roof vents in-kind or with one similar in design and material to those historically used when in-kind replacement is not possible.

4. Materials: Metal

A. MAINTENANCE (PRESERVATION)

- i. *Cleaning*—Use the gentlest means possible when cleaning metal features to avoid damaging the historic finish. Prepare a test panel to determine appropriate cleaning methods before proceeding. Use a wire brush to remove corrosion or paint build up on hard metals like wrought iron, steel, and cast iron.
- ii. *Repair*—Repair metal features using methods appropriate to the specific type of metal.
- iii. *Paint*—Avoid painting metals that were historically exposed such as copper and bronze.

B. ALTERATIONS (REHABILITATION, RESTORATION, AND RECONSTRUCTION)

- i. *Replacement*—Replace missing or significantly damaged metal features in-kind or with a substitute compatible in size, form, material, and general appearance to the historical feature when in-kind replacement is not possible.
- ii. *Rust*—Select replacement anchors of stainless steel to limit rust and associated expansion that can cause cracking of the surrounding material such as wood or masonry. Insert anchors into the mortar joints of masonry buildings.
- iii. *New metal features*—Add metal features based on accurate evidence of the original, such as photographs. Base the design on the architectural style of the building and historic patterns if no such evidence exists.

5. Architectural Features: Lighting

A. MAINTENANCE (PRESERVATION)

- i. *Lighting*—Preserve historic light fixtures in place and maintain through regular cleaning and repair as needed.

B. ALTERATIONS (REHABILITATION, RESTORATION, AND RECONSTRUCTION)

- i. *Rewiring*—Consider rewiring historic fixtures as necessary to extend their lifespan.
- ii. *Replacement lighting*—Replace missing or severely damaged historic light fixtures in-kind or with fixtures that match the original in appearance and materials when in-kind replacement is not feasible. Fit replacement fixtures to the existing mounting location.
- iii. *New light fixtures*—Avoid damage to the historic building when installing necessary new light fixtures, ensuring they may be removed in the future with little or no damage to the building. Place new light fixtures and those not historically present in locations that do not distract from the façade of the building while still directing light where needed. New light fixtures should be unobtrusive in design and should not rust or stain the building.

6. Architectural Features: Doors, Windows, and Screens

A. MAINTENANCE (PRESERVATION)

- i. *Openings*—Preserve existing window and door openings. Avoid enlarging or diminishing to fit stock sizes or air conditioning units. Avoid filling in historic door or window openings. Avoid creating new primary entrances or window openings on the primary façade or where visible from the public right-of-way.
- ii. *Doors*—Preserve historic doors including hardware, fanlights, sidelights, pilasters, and entablatures.
- iii. *Windows*—Preserve historic windows. When glass is broken, the color and clarity of replacement glass should match the original historic glass.
- iv. *Screens and shutters*—Preserve historic window screens and shutters.
- v. *Storm windows*—Install full-view storm windows on the interior of windows for improved energy efficiency. Storm window may be installed on the exterior so long as the visual impact is minimal and original architectural details are not obscured.

B. ALTERATIONS (REHABILITATION, RESTORATION, AND RECONSTRUCTION)

- i. *Doors*—Replace doors, hardware, fanlight, sidelights, pilasters, and entablatures in-kind when possible and when deteriorated beyond repair. When in-kind replacement is not feasible, ensure features match the size, material, and profile of the historic element.
- ii. *New entrances*—Ensure that new entrances, when necessary to comply with other regulations, are compatible in size, scale, shape, proportion, material, and massing with historic entrances.
- iii. *Glazed area*—Avoid installing interior floors or suspended ceilings that block the glazed area of historic windows.
- iv. *Window design*—Install new windows to match the historic or existing windows in terms of size, type, configuration, material, form, appearance, and detail when original windows are deteriorated beyond repair.
- v. *Muntins*—Use the exterior muntin pattern, profile, and size appropriate for the historic building when replacement windows are necessary. Do not use internal muntins sandwiched between layers of glass.
- vi. *Replacement glass*—Use clear glass when replacement glass is necessary. Do not use tinted glass, reflective glass, opaque glass, and other non-traditional glass types unless it was used historically. When established by the architectural style of the building, patterned, leaded, or colored glass can be used.
- vii. *Non-historic windows*—Replace non-historic incompatible windows with windows that are typical of the architectural style of the building.
- viii. *Security bars*—Install security bars only on the interior of windows and doors.
- ix. *Screens*—Utilize wood screen window frames matching in profile, size, and design of those historically found when the existing screens are deteriorated beyond repair. Ensure that the tint of replacement screens closely matches the original screens or those used historically.

x. *Shutters*—Incorporate shutters only where they existed historically and where appropriate to the architectural style of the house. Shutters should match the height and width of the opening and be mounted to be operational or appear to be operational. Do not mount shutters directly onto any historic wall material.

7. Architectural Features: Porches, Balconies, and Porte-Cocheres

A. MAINTENANCE (PRESERVATION)

i. *Existing porches, balconies, and porte-cocheres*—Preserve porches, balconies, and porte-cocheres. Do not add new porches, balconies, or porte-cocheres where not historically present.

ii. *Balusters*—Preserve existing balusters. When replacement is necessary, replace in-kind when possible or with balusters that match the originals in terms of materials, spacing, profile, dimension, finish, and height of the railing.

iii. *Floors*—Preserve original wood or concrete porch floors. Do not cover original porch floors of wood or concrete with carpet, tile, or other materials unless they were used historically.

B. ALTERATIONS (REHABILITATION, RESTORATION, AND RECONSTRUCTION)

i. *Front porches*—Refrain from enclosing front porches. Approved screen panels should be simple in design as to not change the character of the structure or the historic fabric.

ii. *Side and rear porches*—Refrain from enclosing side and rear porches, particularly when connected to the main porch or balcony. Original architectural details should not be obscured by any screening or enclosure materials. Alterations to side and rear porches should result in a space that functions, and is visually interpreted as, a porch.

iii. *Replacement*—Replace in-kind porches, balconies, porte-cocheres, and related elements, such as ceilings, floors, and columns, when such features are deteriorated beyond repair. When in-kind replacement is not feasible, the design should be compatible in scale, massing, and detail while materials should match in color, texture, dimensions, and finish.

iv. *Adding elements*—Design replacement elements, such as stairs, to be simple so as to not distract from the historic character of the building. Do not add new elements and details that create a false historic appearance.

v. *Reconstruction*—Reconstruct porches, balconies, and porte-cocheres based on accurate evidence of the original, such as photographs. If no such evidence exists, the design should be based on the architectural style of the building and historic patterns.

8. Architectural Features: Foundations

A. MAINTENANCE (PRESERVATION)

i. *Details*—Preserve the height, proportion, exposure, form, and details of a foundation such as decorative vents, grilles, and lattice work.

ii. *Ventilation*—Ensure foundations are vented to control moisture underneath the dwelling, preventing deterioration.

iii. *Drainage*—Ensure downspouts are directed away and soil is sloped away from the foundation to avoid moisture collection near the foundation.

iv. *Repair*—Inspect foundations regularly for sufficient drainage and ventilation, keeping it clear of vegetation. Also inspect for deteriorated materials such as limestone and repair accordingly. Refer to maintenance and alteration of applicable materials, for additional guidelines.

B. ALTERATIONS (REHABILITATION, RESTORATION, AND RECONSTRUCTION)

i. *Replacement features*—Ensure that features such as decorative vents and grilles and lattice panels are replaced in-kind when deteriorated beyond repair. When in-kind replacement is not possible, use features matching in size, material, and design. Replacement skirting should consist of durable, proven materials, and should either match the existing siding or be applied to have minimal visual impact.

ii. *Alternative materials*—Cedar piers may be replaced with concrete piers if they are deteriorated beyond repair.

iii. *Shoring*—Provide proper support of the structure while the foundation is rebuilt or repaired.

iv. *New utilities*—Avoid placing new utility and mechanical connections through the foundation along the primary façade or where visible from the public right-of-way.

Standard Specifications for Original Wood Window Replacement

- SCOPE OF REPAIR: When individual elements such as sills, muntins, rails, sashes, or glazing has deteriorated, every effort should be made to repair or reconstruct that individual element prior to consideration of wholesale replacement. For instance, applicant should replace individual sashes within the window system in lieu of full replacement with a new window unit.
- MISSING OR PREVIOUSLY-REPLACED WINDOWS: Where original windows are found to be missing or previously-replaced with a nonconforming window product by a previous owner, an alternative material to

wood may be considered when the proposed replacement product is more consistent with the Historic Design Guidelines in terms of overall appearance. Such determination shall be made on a case-by-case basis by OHP and/or the HDRC. Whole window systems should match the size of historic windows on property unless otherwise approved.

- MATERIAL: If full window replacement is approved, the new windows must feature primed and painted wood exterior finish. Clad, composition, or non-wood options are not allowed unless explicitly approved by the commission.
- SASH: Meeting rails must be no taller than 1.25". Stiles must be no wider than 2.25". Top and bottom sashes must be equal in size unless otherwise approved.
- DEPTH: There should be a minimum of 2" in depth between the front face of the window trim and the front face of the top window sash. This must be accomplished by recessing the window sufficiently within the opening or with the installation of additional window trim to add thickness.
- TRIM: Original trim details and sills should be retained or repaired in kind. If approved, new window trim must feature traditional dimensions and architecturally appropriate casing and sloped sill detail. Window track components such as jamb liners must be painted to match the window trim or concealed by a wood window screen set within the opening.
- GLAZING: Replacement windows should feature clear glass. Low-e or reflective coatings are not recommended for replacements. The glazing should not feature faux divided lights with an interior grille. If approved to match a historic window configuration, the window should feature real exterior muntins.
- COLOR: Replacement windows should feature a painted finish. If a clad product is approved, white or metallic manufacturer's color is not allowed, and color selection must be presented to staff.
- INSTALLATION: Replacement windows should be supplied in a block frame and exclude nailing fins. Window opening sizes should not be altered to accommodate stock sizes prior to approval.
- FINAL APPROVAL: If the proposed window does not meet the aforementioned stipulations, then the applicant must submit updated window specifications to staff for review, prior to purchase and installation. For more assistance, the applicant may request the window supplier to coordinate with staff directly for verification.

Historic Design Guidelines, Chapter 3, Guidelines for Additions

1. Massing and Form of Residential Additions

A. GENERAL

- i. *Minimize visual impact*—Site residential additions at the side or rear of the building whenever possible to minimize views of the addition from the public right-of-way. An addition to the front of a building would be inappropriate.
- ii. *Historic context*—Design new residential additions to be in keeping with the existing, historic context of the block. For example, a large, two-story addition on a block comprised of single-story homes would not be appropriate.
- iii. *Similar roof form*—Utilize a similar roof pitch, form, overhang, and orientation as the historic structure for additions.
- iv. *Transitions between old and new*—Utilize a setback or recessed area and a small change in detailing at the seam of the historic structure and new addition to provide a clear visual distinction between old and new building forms.

B. SCALE, MASSING, AND FORM

- i. *Subordinate to principal facade*—Design residential additions, including porches and balconies, to be subordinate to the principal façade of the original structure in terms of their scale and mass.
- ii. *Rooftop additions*—Limit rooftop additions to rear facades to preserve the historic scale and form of the building from the street level and minimize visibility from the public right-of-way. Full-floor second story additions that obscure the form of the original structure are not appropriate.
- iii. *Dormers*—Ensure dormers are compatible in size, scale, proportion, placement, and detail with the style of the house. Locate dormers only on non-primary facades (those not facing the public right-of-way) if not historically found within the district.
- iv. *Footprint*—The building footprint should respond to the size of the lot. An appropriate yard to building ratio should be maintained for consistency within historic districts. Residential additions should not be so large as to double the existing building footprint, regardless of lot size.
- v. *Height*—Generally, the height of new additions should be consistent with the height of the existing structure. The maximum height of new additions should be determined by examining the line-of-sight or visibility from the street. Addition height should never be so contrasting as to overwhelm or distract from the existing structure.

2. Massing and Form of Non-Residential and Mixed-Use Additions

A. GENERAL

- i. *Historic context*—Design new additions to be in keeping with the existing, historic context of the block. For example, additions should not fundamentally alter the scale and character of the block when viewed from the public right-of-way.
- ii. *Preferred location*—Place additions at the side or rear of the building whenever possible to minimize the visual impact on the original structure from the public right of way. An addition to the front of a building is inappropriate.
- iii. *Similar roof form*—Utilize a similar roof pitch, form, and orientation as the principal structure for additions, particularly for those that are visible from the public right-of-way.
- iv. *Subordinate to principal facade*—Design additions to historic buildings to be subordinate to the principal façade of the original structure in terms of their scale and mass.
- v. *Transitions between old and new*—Distinguish additions as new without distracting from the original structure. For example, rooftop additions should be appropriately set back to minimize visibility from the public right-of-way. For side or rear additions utilize setbacks, a small change in detailing, or a recessed area at the seam of the historic structure and new addition to provide a clear visual distinction between old and new building forms.

B. SCALE, MASSING, AND FORM

- i. *Height*—Limit the height of side or rear additions to the height of the original structure. Limit the height of rooftop additions to no more than 40 percent of the height of original structure.
- ii. *Total addition footprint*—New additions should never result in the doubling of the historic building footprint. Full-floor rooftop additions that obscure the form of the original structure are not appropriate.

3. Materials and Textures

A. COMPLEMENTARY MATERIALS

- i. *Complementary materials*—Use materials that match in type, color, and texture and include an offset or reveal to distinguish the addition from the historic structure whenever possible. Any new materials introduced to the site as a result of an addition must be compatible with the architectural style and materials of the original structure.
- ii. *Metal roofs*—Construct new metal roofs in a similar fashion as historic metal roofs. Refer to the Guidelines for Alternations and Maintenance section for additional specifications regarding metal roofs.
- iii. *Other roofing materials*—Match original roofs in terms of form and materials. For example, when adding on to a building with a clay tile roof, the addition should have a roof that is clay tile, synthetic clay tile, or a material that appears similar in color and dimension to the existing clay tile.

B. INAPPROPRIATE MATERIALS

- i. *Imitation or synthetic materials*—Do not use imitation or synthetic materials, such as vinyl siding, brick or simulated stone veneer, plastic, or other materials not compatible with the architectural style and materials of the original structure.

C. REUSE OF HISTORIC MATERIALS

- i. *Salvage*—Salvage and reuse historic materials, where possible, that will be covered or removed as a result of an addition.

4. Architectural Details

A. GENERAL

- i. *Historic context*—Design additions to reflect their time while respecting the historic context. Consider character-defining features and details of the original structure in the design of additions. These architectural details include roof form, porches, porticos, cornices, lintels, arches, quoins, chimneys, projecting bays, and the shapes of window and door openings.
- ii. *Architectural details*—Incorporate architectural details that are in keeping with the architectural style of the original structure. Details should be simple in design and compliment the character of the original structure. Architectural details that are more ornate or elaborate than those found on the original structure should not be used to avoid drawing undue attention to the addition.
- iii. *Contemporary interpretations*—Consider integrating contemporary interpretations of traditional designs and details for additions. Use of contemporary window moldings and door surroundings, for example, can provide visual interest while helping to convey the fact that the addition is new.

5. Mechanical Equipment and Roof Appurtenances

A. LOCATION AND SITING

- i. *Visibility*—Do not locate utility boxes, air conditioners, rooftop mechanical equipment, skylights, satellite dishes, cable lines, and other roof appurtenances on primary facades, front-facing roof slopes, in front yards, or in other locations that are clearly visible from the public right-of-way.
- ii. *Service Areas*—Locate service areas towards the rear of the site to minimize visibility from the public right-of-way. Where service areas cannot be located at the rear of the property, compatible screens or buffers will be required.

B. SCREENING

- i. *Building-mounted equipment*—Paint devices mounted on secondary facades and other exposed hardware, frames, and piping to match the color scheme of the primary structure or screen them with landscaping.
- ii. *Freestanding equipment*—Screen service areas, air conditioning units, and other mechanical equipment from public view using a fence, hedge, or other enclosure.
- iii. *Roof-mounted equipment*—Screen and set back devices mounted on the roof to avoid view from public right-of-way.

6. Designing for Energy Efficiency

A. BUILDING DESIGN

- i. *Energy efficiency*—Design additions and new construction to maximize energy efficiency.
- ii. *Materials*—Utilize green building materials, such as recycled, locally-sourced, and low maintenance materials whenever possible.
- iii. *Building elements*—Incorporate building features that allow for natural environmental control – such as operable windows for cross ventilation.
- iv. *Roof slopes*—Orient roof slopes to maximize solar access for the installation of future solar collectors where compatible with typical roof slopes and orientations found in the surrounding historic district.

B. SITE DESIGN

- i. *Building orientation*—Orient new buildings and additions with consideration for solar and wind exposure in all seasons to the extent possible within the context of the surrounding district.
- ii. *Solar access*—Avoid or minimize the impact of new construction on solar access for adjoining properties.

C. SOLAR COLLECTORS

- i. *Location*—Locate solar collectors on side or rear roof pitch of the primary historic structure to the maximum extent feasible to minimize visibility from the public right-of-way while maximizing solar access. Alternatively, locate solar collectors on a garage or outbuilding or consider a ground-mount system where solar access to the primary structure is limited.
- ii. *Mounting (sloped roof surfaces)*—Mount solar collectors flush with the surface of a sloped roof. Select collectors that are similar in color to the roof surface to reduce visibility.
- iii. *Mounting (flat roof surfaces)*—Mount solar collectors flush with the surface of a flat roof to the maximum extent feasible. Where solar access limitations preclude a flush mount, locate panels towards the rear of the roof where visibility from the public right-of-way will be minimized.

Standard Specifications for Windows in Additions and New Construction

- GENERAL: New windows on additions should relate to the windows of the primary historic structure in terms of materiality and overall appearance. Windows used in new construction should be similar in appearance to those commonly found within the district in terms of size, profile, and configuration. While no material is expressly prohibited by the Historic Design Guidelines, a high-quality wood or aluminum-clad wood window product often meets the Guidelines with the stipulations listed below. Whole window systems should match the size of historic windows on property unless otherwise approved.
- SIZE: Windows should feature traditional dimensions and proportions as found within the district.
- SASH: Meeting rails must be no taller than 1.25". Stiles must be no wider than 2.25". Top and bottom sashes must be equal in size unless otherwise approved.
- DEPTH: There should be a minimum of 2" in depth between the front face of the window trim and the front face of the top window sash.
- This must be accomplished by recessing the window sufficiently within the opening or with the installation of additional window trim to add thickness.
- TRIM: Window trim must feature traditional dimensions and architecturally appropriate casing and sloped sill detail. Window track components such as jamb liners must be painted to match the window trim or concealed by a wood window screen set within the opening.

- GLAZING: Windows should feature clear glass. Low-e or reflective coatings are not recommended for replacements. The glazing should not feature faux divided lights with an interior grille. If approved to match a historic window configuration, the window should feature real exterior muntins.
- COLOR: Wood windows should feature a painted finished. If a clad product is approved, white or metallic manufacturer's color is not allowed, and color selection must be presented to staff.
- INSTALLATION: Wood windows should be supplied in a block frame and exclude nailing fins. Window opening sizes should not be altered to accommodate stock sizes prior to approval.
- FINAL APPROVAL: If the proposed window does not meet the aforementioned stipulations, then the applicant must submit updated window specifications to staff for review, prior to purchase and installation. For more assistance, the applicant may request the window supplier to coordinate with staff directly for verification.

FINDINGS:

- a. The primary structure at 901 N Alamo is a 2-story, single-family residence constructed in 1878 in the Queen Anne style. The structure currently features a standing seam metal hip roof, a 2-story front porch with classical columns on the second story and support posts on the first story, one-over-one wood and replacement windows, and wood and stucco siding. Per the 1888 Sanborn Map, the structure originally featured a full-width front porch and a separate side porch. By 1904, the Sanborn Map shows that the porch had been converted into a wraparound porch. In the 1940s, a number of metal commercial awnings and commercial additions were installed on the property. Currently, the side porch is infilled. The property is designated as an individual landmark.
- b. FRONT PORCH MODIFICATION – The applicant has proposed to remove and reconstruct the 2-story front porch but has proposed to extend the side porch past the original porch footprint to add a side porch addition to the south of the existing side porch infill. The applicant has proposed to construct the front porch with a standing seam metal roof to match the existing roof form and 6"x6" wood columns. Per the 1888 Sanborn Map, the structure originally featured a full-width front porch and a separate side porch. By 1904, the Sanborn Map shows that the porch had been converted into a wraparound porch. In the 1940s, a number of metal commercial awnings and commercial additions were installed on the property. Currently, the side porch is infilled. Guideline 7.B.v for Exterior Maintenance and Alterations states that porches, balconies, and porte-cocheres should be reconstructed based on accurate evidence of the original, such as photographs. If no such evidence exists, the design should be based on the architectural style of the building and historic patterns. Staff finds the front porch removal and reconstruction appropriate but finds that the new front porch should match the original footprint, that materials such as porch decking, columns, and beadboard should be salvaged and reused where possible, and that the applicant should install classical columns to match the existing porch columns on the second story. The applicant should submit updated drawings and material specifications to staff for review.
- c. CLADDING REPLACEMENT – The applicant has proposed to replace the existing stucco cladding on the primary historic structure with Hardie siding. Guideline 1.B.i for Exterior Maintenance and Alterations states that applicants should consider exposing original wood siding if it is currently covered with vinyl or aluminum siding, stucco, or other materials that have not achieved historic significance. Additionally, Guideline 1.B.ii for Exterior Maintenance and Alterations states that applicants should use in-kind materials when possible or materials similar in size, scale, and character when exterior woodwork is beyond repair. Ensure replacement siding is installed to match the original pattern, including exposures. Do not introduce modern materials that can accelerate and hide deterioration of historic materials. Hardiboard and other cementitious materials are not recommended. Staff finds that exposing any original siding that is currently installed beneath the existing stucco or installing replacement fully wood siding in a traditional profile is more appropriate than the installation of Hardie siding.
- d. ADDITION: REMOVAL – The applicant has proposed to remove a number of non-original commercial installations on the property. The applicant has proposed to remove a wooden storage addition at the rear of the property that does not appear on the Sanborn Maps to accommodate a new utility addition. Staff finds the proposal appropriate.
- e. ADDITION – The applicant has proposed to construct an approximately 191-square-foot, 1-story rear addition in the location of a much larger existing rear addition to accommodate a walk-in cooler. The proposed addition will feature a flat roof with a roof deck and railing, Hardieboard cladding, one (1) door with access stairs on the south elevation, and one (1) door on the west elevation. The addition will connect to the existing rear brick and cinderblock addition and will feature a total height of 17'-1". Guideline 2.A.i for Additions states that new additions for non-residential properties should be designed to be in keeping

with the existing and historic context of the block when viewed from the public right-of-way. Additionally, non-residential additions should be placed at the side or rear of the building to minimize the visual impact on the original structure and that they should be subordinate to the principal façade. Staff finds the proposal generally appropriate but finds that the applicant should submit final material specifications to staff for review.

- f. **ADMINISTRATIVE APPROVAL** – The application materials include a number of scopes of work, including the removal of commercial awnings, removal of the corrugated metal perimeter fencing, the installation of a sport court, and additional site work, that is eligible for administrative approval and does not require review by the Historic and Design Review Commission (HDRC).

RECOMMENDATION:

Item 1, staff recommends approval of the removal and reconstruction of a wraparound front porch based on finding b with the following stipulations:

- i. That the new front porch should match the original footprint of the wraparound porch per the 1904 Sanborn Map. The applicant is required to submit updated drawings to staff for review and approval prior to the issuance of a Certificate of Appropriateness.
- ii. That salvageable materials such as porch decking, columns, and beadboard, should be salvaged and reused where possible. The applicant is required to submit a salvage and reuse plan to staff for review and approval prior to the issuance of a Certificate of Appropriateness.
- iii. That the applicant installs classical columns to match the style of the existing second-story columns. The applicant should submit updated drawings and material specifications to staff for review and approval prior to the issuance of a Certificate of Appropriateness.
- iv. That the applicant submits final material specifications for the roofing, decking, columns, skirting, steps, and handrails to staff for review and approval prior to the issuance of a Certificate of Appropriateness. The standing seam metal roof must feature panels that are 18 to 21 inches wide, seams that are 1 to 2 inches high, a crimped ridge seam, and match the current finish or a standard galvalume finish. Panels should be smooth without striation or corrugation. Ridges are to feature a double-munch or crimped ridge configuration; no vented ridge caps or end caps are allowed. All chimney, flue, and related existing roof details must be preserved. An inspection must be scheduled with OHP staff prior to the start of work to verify that the roofing material matches the approved specifications.


Item 2, staff recommends approval of the replacement of the stucco cladding based on finding c with the following stipulation:

- i. That the applicant removes the existing stucco to expose any original wood siding installed beneath the existing stucco cladding or replaces the stucco cladding with fully wood siding in a traditional profile. The applicant is required to submit evidence of any wood siding that remains in place or updated material specifications for a fully wood replacement siding material to staff for review and approval prior to the issuance of a Certificate of Appropriateness.

Item 3, staff recommends approval of the construction of a 1-story rear addition based on findings d through e with the following stipulations:


- i. That the applicant submits final material specifications for the roofing material, cladding, doors, railings, stairs, and handrailing to staff for review and approval prior to the issuance of a Certificate of Appropriateness based on finding d. The applicant is required to submit updated elevation drawings showing the profile of the proposed staircase from the front and rear elevations.

City of San Antonio One Stop




August 16, 2024

— User drawn lines



Google Maps 901 N Alamo St



Imagery ©2024 Google, Map data ©2024 Google 20 ft



Imagery ©2024 Google, Map data ©2024 Google 20 ft

Google Maps 901 N Alamo St





Imagery ©2024 Google, Data SIO, NOAA, U.S. Navy, NGA, GEBCO, Landsat / Copernicus, Map data ©2024 Google 20 ft


Google Maps 901 N Alamo St



Imagery ©2024 Google, Data SIO, NOAA, U.S. Navy, NGA, GEBCO, Landsat / Copernicus, TerraMetrics, Map data ©2024 Google 20 ft







165

169

GRAND

AV.

Mechanized

SHERMAN ST

N. WINDY ST

166

AUSTIN

BURLESON ST

10TH ST.

ST.


516

453

9TH ST.

160

Scale of Feet



MAVERICK SQUARE

150

AVENUE

148

454

GREEN HOUSES

GLASS ROOFS

AVENUE

D

C

B

A

100

90

80

70

60

50

40

30

20

10

0

10

20

30

40

50

60

70

80

90

100

110

120

130

140

150

160

170

180

190

200

210

220

230

240

250

260

270

280

290

300

310

320

330

340

350

360

370

380

390

400

410

420

430

440

450

460

470

480

490

500

510

520

530

540

550

560

570

580

590

600

610

620

630

640

650

660

670

680

690

700

710

720

730

740

750

760

770

780

790

800

810

820

830

840

850

860

870

880

890

900

910

920

930

940

950

960

970

980

990

1000

1010

1020

1030

1040

1050

1060

1070

1080

1090

1100

1110

1120

1130

1140

1150

1160

1170

1180

1190

1200

1210

1220

1230

1240

1250

1260

1270

1280

1290

1300

1310

1320

1330

1340

1350

1360

1370

1380

1390

1400

1410

1420

1430

1440

1450

1460

1470

1480

1490

1500

1510

1520

1530

1540

1550

1560

1570

1580

1590

1600

1610

1620

1630

1640

1650

1660

1670

1680

1690

1700

1710

1720

1730

1740

1750

1760

1770

1780

1790

1800

1810

1820

1830

1840

1850

1860

1870

1880

1890

1900

1910

1920

1930

1940

1950

1960

1970

1980

1990

2000

2010

2020

2030

2040

2050

2060

2070

2080

2090

2100

2110

2120

2130

2140

2150

2160

2170

2180

2190

2200

2210

2220

2230

2240

2250

2260

2270

2280

2290

2300

2310

2320

2330

2340

2350

2360

2370

2380

2390

2400

2410

2420

2430

2440

2450

2460

2470

2480

2490

2500

2510

2520

2530

2540

2550

2560

2570

2580

2590

2600

2610

2620

2630

2640

2650

2660

2670

2680

2690

2700

2710

2720

2730

2740

2750

2760

2770

2780

2790

2800

2810

2820

2830

2840

2850

2860

2870

2880

2890

2900

2910

2920

2930

2940

2950


2960

2970

2980

AVAA-24-10100971
PARCEL-1753

901 N ALAMO. BUILDINGS 1,2,3.



General Notes

- A. The dimensions on this sheet are based of of FACE OF FINISH material.
- B. GC to field verify all existing dimension prior to construction and/or installation of any equipment, accessories, etc. If discrepancy is identified, notify ARCHITECT immediately.
- C. The following items will be OSCI – Owner Supplied/Contractor Installed. all moveable equipment (any item not hard plumbed into the wall), stainless steep equipments, tables selvings.
- D. Refer o appropriate sheet and/or schedule for additional information/detail regarding items shown herein.
- E. Keynotes located on this sheet are for his sheet only.
- F. Do not scale the drawing. If a specific dimension is not given, contact ARCHITECT for clarification.
- G. Refer to Sheet A001 – General Conditions for additional information associated with, but not limited to: submittals, shop drawings, samples, cutting and patching, coordination and staging, protection of work.

No.	Revision/Issue	Date

Firm Name and Address
RYO CONSTRUCTION & DESIGN
2918 BELLAMY CIRCLE
CEDAR PARK, TEXAS 75951

Project Name and Address
DISTRICT 901 BUILDING 1
901 N ALAMO ST
SAN ANTONIO, TEXAS 78215

Sheet Title
ADDRESS MAP

Sheet
G000

Project
DISTRICT 901 BUILDING 1

Date
4/29/2024

Scale
As Noted

APPROVED
By Kevvin Ellison at 9:36 am, May 24, 2024



CITY OF SAN ANTONIO
DEVELOPMENT SERVICES DEPARTMENT
P.O. BOX 839966 | SAN ANTONIO TEXAS 78283-3966



MW Burkholder Properties, LLC
Lane Hudson
11075 IH-10 W, Suite 126
San Antonio, Texas 78230

SUBJECT: COD 19-10600218, Lot 9, 10, 11, Block 32, NCB 454

In accordance with V.T.C.A. Local Government Code Section 212.0115 and the San Antonio Unified Development Code (UDC) 35-430(C), a plat is not required for the property and this Certificate of Determination will assist customers in obtaining building permits and/or utility services. *Note: Properties located Outside City Limits, but within the ETJ will be referenced as (OCL); and properties located within the City Limits will be referenced as (ICL).*

A plat is not required for the property, subject to the following conditions §35-430(C):

17 – Within the original 36 square miles of COSA. Tract must have remained in the same configuration since June 14, 1927. Must fire rate walls if crossing lot lines.

NOTE: This Certificate of Determination (COD) documents that the identified property does not need to plat at this time; however:

1. If one or more of the following is determined to have occurred at the time of permitting for the development of this property, then this COD is voided and platting will be required:
 - a. Habitable use in the floodplain;
 - b. Public drainage improvement is required;
 - c. Extension of a utility main is required; (water, gas, and electric only or utilities as listed in 35-507(a) – which would include public (or private) drainage improvements). This would not include a Water Well or Septic Tank; and/or
 - d. Any change in the acreage or Land Use identified on the COD.
2. The proposed development may need to comply with Section 35-523 of the UDC regarding the tree ordinance. Non-compliance with the tree ordinance can result in a fine of \$2,000.00 or an additional fee equal to the fee established in Appendix C for commencing development without a tree permit.

Commercial

Acreage/Square Footage: **.463**

*Please note that the City of San Antonio's development regulations apply to all properties located inside the City of San Antonio, and the Extra Territorial Jurisdiction, which includes parts of Bexar, Comal, Guadalupe, Kendall, Medina and Wilson Counties.

Should you have any questions regarding this Certificate of Determination, please contact Dominic Silva, the Senior Planner who worked on your request at 210-207-0120, or via email at Dominic.Silva@sanantonio.gov.

Sincerely,

Zenon Solis
Principal Planner

July 30, 2024

City of San Antonio
Office of Historic Preservation
Certificate of Appropriateness Application
901 NORTH ALAMO LLC

SPECIFICATION OF MATERIALS TO BE USED:

- 1) ALL SIDING SHALL BE WOODEN CLAP BOARD TO MATCH EXISTING SIDING OF NO MORE THAN 5" IN WIDTH AND PROFILE FROM JAMES HARDIE BEADED SELECT CEDAR MILL. PAINT TO MATCH EXISTING WHITE EXTERIOR OR AS RECOMMENDED BY COSA HISTORICAL PRESERVATION.
- 2) DEMO EXISTING STUCCO AND REPLACE WITH LIKE-KIND MATERIAL SPECIFIED AS "XS-1" ON SHEET A505
- 3) WHEN RESTORING EXTERIOR, USE PINEWOOD AND PAINT USING EXTERIOR PRIMER AND TWO COATS OF EXTERIOR FINISH

Sincerely,

A handwritten signature in black ink, appearing to read "Hue Nguyen", with a long horizontal flourish extending to the right.

Hue Nguyen
901 North Alamo LLC





AUGIES
BBO IS
OPEN

NO
PARKING
ANYTIME

ACE SPRING

901 N Alamo
(210) 227-9124

Coil Springs
Leaf Springs
U-bolts
Suspension Parts
Axle Re-Build
Re-Arch
Re-Bush


ACE SPRING ALAMO



DISTRICT 901 BUILDING 1

901 NORTH ALAMO STREET - SAN ANTONIO, TEXAS 78215

SITE MAP



Limit of Construction = 2,516 SF, 2 story building

CODE ANALYSIS

2021 INTERNATIONAL BUILDING CODE, IBC
2021 INTERNATIONAL EXISTING BUILDING CODE, IEB
2021 INTERNATIONAL FIRE CODE, IFC
2021 INTERNATIONAL MECHANICAL, IMC
2021 INTERNATIONAL PLUMBING CODE, IPC
2021 INTERNATIONAL FUEL CODE, IFGC
2021 INTERNATIONAL ENERGY CONSERVATION CODE, IECC
2021 SAN ANTONIO PROPERTY MAINTENANCE CODE (BASED ON 2018 IPMC)
2020 NATIONAL ELECTRIC CODE, NEC
2012 ADA


PROJECT DESCRIPTION

FULL EXTERIOR RENOVATION OF HISTORICAL QUEEN ANNE 2 STORY HOUSE WITH AN ADDITION OF STORAGE SPACE LOCATED IN THE BACK OF THE HOUSE. ALL INTERIOR WORK SHALL INCLUDE ELECTRICAL AND PLUMBING AND RE-USE EXISTING HVAC CONDENSER FROM ROOFTOP TO GROUND FLOOR. USE SHALL BE A-2 FOR COFFEE SHOP AND YOGA STUDIO.

SITE DATA + ZONING INFORMATION

Funding PRIVATE
Address 901 N ALAMO ST, SAN ANTONIO, TEXAS 78215
BCAD ID# 104462
Legal Lot Description NCB 454 BLK 32 LOT 9, 10 & 11
FEMA Floor Plain NO
Zoning FBA T6-1
Use A2 GENERAL ASSEMBLY - COCKTAIL LOUNGE
Maximum Height 2 STORY AREA [existing]
Gross Floor Area 2,516 GSF BUILDING
Fire Sprinkler NOT REQUIRED PER NFPA 914, Occupancy Load less than 100
Fire Alarm NO

LOCATION MAP



NOT TO SCALE

PROJECT TEAM

BUILDING OWNER

HUE NGUYEN
2918 BELLAMY CIRCLE
CEDAR PARK, TX 78613
512.785.7588

DESIGNER

HUE NGUYEN
2918 BELLAMY CIRCLE
CEDAR PARK, TX 78613
512.785.7588

STRUCTURAL PE

AYODEJI AGBALE
PE# 136421, TEXAS

LANELI ENGINEERING
1708 SPRING GREEN BLVD
KATY, TEXAS 77494
Firm No# 20353

MEP ENGINEER

FRANCIS KOK
PE# 119470, TEXAS

Futuremap Engineering Design LLC
1708 SPRING GREEN BLVD
KATY, TEXAS 77494
Firm No# 20353

SHEET INDEX

G001 SITE PLAN
G001 ADA NOTES
G002 ADA NOTES CONT.
A101 EXISTING PLAN
A102 DEMO PLAN
A103 PROPOSED PLAN
A104 LIFE SAFETY PLAN
A500 WALL SCHEDULE
A501 ELEVATION PLAN
A502 ELEVATION PLAN
E001 ELECTRICAL NOTES
E101 LIGHTING PLAN
E102 POWER PLAN
E103 EMERGENCY LIGHTING
E501 ONE LINE DIAGRAM
M001 MECHANICAL NOTES
M100 MECHANICAL PLAN
MEP101 GAS PLAN & LOAD
P001 PLUMBING NOTES
P101 WATER SUPPLY PLAN
P102 WASTE & VENT PLAN
P501 RISER DIAGRAM
S001 STRUCTURAL NOTES
S100 SLAB CUT PLAN
S101 STEEL PLAN
S501 STRUCTURAL ELEVATION

General Notes

- The dimensions on this sheet are based of of FACE OF FINISH material.
- GC to field verify all existing dimension prior to construction and/or installation of any equipment, accessories, etc. If discrepancy is identified, notify ARCHITECT immediately.
- The following items will be OSCI – Owner Supplied/Contractor Installed. all moveable equipment (any item not hard plumbed into the wall), stainless steep equipments, tables selvings.
- Refer o appropriate sheet and/or schedule for additional information/detail regarding items shown herein.
- Keynotes located on this sheet are for his sheet only.
- Do not scale the drawing. If a specific dimension is not given, contact ARCHITECT for clarification.
- Refer to Sheet A001 – General Conditions for additional information associated with, but not limited to: submittals, shop drawings, samples, cutting and patching, coordination and staging, protection of work.

No.	Revision/Issue	Date

Firm Name and Address

ArcDesignContractors

Arc Design Contractors
2918 Bellamy Circle
Cedar Park, Texas 78613
arcdesigncontractors.com

Project Name and Address

DISTRICT 901 BLDN 1
901 N ALAMO ST
SAN ANTONIO, TX 78215

Sheet Title

SITE

Sheet

G001

Project DISTRICT 901 BLDN 1

Date 7/18/2024

Scale As Noted

Chapter 6: Plumbing Elements and Facilities

603 Toilet and Bathing Rooms

603.1 General
Toilet and bathing rooms shall comply with 603.

603.2 Clearances
Clearances shall comply with 603.2.

603.2.1 Turning Space
Turning space complying with 304 shall be provided within the room.

603.2.2 Overlap
Required clear floor spaces, clearance at fixtures, and turning space shall be permitted to overlap.

603.2.3 Door Swing
Doors shall not swing into the clear floor space or clearance required for any fixture. Doors shall be permitted to swing into the required turning space.

EXCEPTIONS:
1. Doors to a toilet room or bathing room for a single occupant accessed only through a private office and not for common use or public use shall be permitted to swing into the clear floor space or clearance provided the swing of the door can be reversed to comply with 603.2.3.
2. Where the toilet room or bathing room is for individual use and a clear floor space complying with 305.3 is provided within the room beyond the arc of the door swing, doors shall be permitted to swing into the clear floor space or clearance required for any fixture.

603.3 Mirrors
Mirrors located above lavatories or countertops shall be installed with the bottom edge of the reflecting surface 40 inches (1015 mm) maximum above the finish floor or ground. Mirrors not located above lavatories or countertops shall be installed with the bottom edge of the reflecting surface 35 inches (890 mm) maximum above the finish floor or ground.

603.4 Coat Hooks and Shelves
Coat hooks shall be located within one of the reach ranges specified in 308. Shelves shall be located 40 inches (1015 mm) minimum and 48 inches (1220 mm) maximum above the finish floor.

604 Water Closets and Toilet Compartments

604.1 General
Water closets and toilet compartments shall comply with 604.2 through 604.8.

EXCEPTION: Water closets and toilet compartments for children's use shall be permitted to comply with 604.9.

604.2 Location
The water closet shall be positioned with a wall or partition to the rear and to one side. The centerline of the water closet shall be 16 inches (405 mm) minimum to 18 inches (455 mm) maximum from the side wall or partition, except that the water closet shall be 17 inches (430 mm) minimum and 19 inches (485 mm) maximum from the side wall or partition in the ambulatory accessible toilet compartment specified in 604.8.2. Water closets shall be arranged for a left-hand or right-hand approach.




Figure 604.2 Water Closet Location

604.3 Clearance
Clearances around water closets and in toilet compartments shall comply with 604.3.

604.3.1 Size
Clearance around a water closet shall be 60 inches (1525 mm) minimum measured perpendicular from the side wall and 56 inches (1420 mm) minimum measured perpendicular from the rear wall.




Figure 604.3.1 Size of Clearance at Water Closets

604.3.2 Overlap
The required clearance around the water closet shall be permitted to overlap the water closet, associated grab bars, dispensers, sanitary napkin disposal units, coat hooks, shelves, accessible routes, clear floor space and clearances required at other fixtures, and the turning space. No other fixtures or obstructions shall be located within the required water closet clearance.

EXCEPTION: In residential dwelling units, a lavatory complying with 606 shall be permitted on the rear wall 18 inches (455 mm) minimum from the water closet centerline where the clearance at the water closet is 66 inches (1675 mm) minimum measured perpendicular from the rear wall.

Figure 604.3.2 (Exception) Overlap of Water Closet Clearance in Residential Dwelling Units

604.4 Seats
The seat height of a water closet above the finish floor shall be 17 inches (430 mm) minimum and 19 inches (485 mm) maximum measured to the top of the seat. Seats shall not be sprung to return to a lifted position.

EXCEPTIONS: 1. A water closet in a toilet room for a single occupant accessed only through a private office and not for common use or public use shall not be required to

comply with 604.4.

2. In residential dwelling units, the height of water closets shall be permitted to be 15 inches (380 mm) minimum and 19 inches (485 mm) maximum above the finish floor measured to the top of the seat.

604.5 Grab Bars
Grab bars for water closets shall comply with 609. Grab bars shall be provided on the side wall closest to the water closet and on the rear wall.

EXCEPTIONS: 1. Grab bars shall not be required to be installed in a toilet room for a single occupant accessed only through a private office and not for common use or public use provided that reinforcement has been installed in walls and located so as to permit the installation of grab bars complying with 604.5.

2. In residential dwelling units, grab bars shall not be required to be installed in toilet or bathrooms provided that reinforcement has been installed in walls and located so as to permit the installation of grab bars complying with 604.5.

3. In detention or correction facilities, grab bars shall not be required to be installed in housing or holding cells that are specially designed without protrusions for purposes of suicide prevention.

604.5.1 Side Wall
The side wall grab bar shall be 42 inches (1065 mm) long minimum, located 12 inches (305 mm) maximum from the rear wall and extending 54 inches (1370 mm) minimum from the rear wall.

Figure 604.5.1 Side Wall Grab Bar at Water Closets

604.5.2 Rear Wall
The rear wall grab bar shall be 36 inches (915 mm) long minimum and extend from the centerline of the water closet 12 inches (305 mm) minimum on one side and 24 inches (610 mm) minimum on the other side.

EXCEPTIONS:
1. The rear grab bar shall be permitted to be 24 inches (610 mm) long minimum, centered on the water closet, where wall space does not permit a length of 36 inches (915 mm) minimum due to the location of a recessed fixture adjacent to the water closet.

2. Where an administrative authority requires flush controls for flush valves to be located in a position that conflicts with the location of the rear grab bar, then the rear grab bar shall be permitted to be split or shifted to the open side of the toilet area.




Figure 604.5.2 Rear Wall Grab Bar at Water Closets

604.6 Flush Controls
Flush controls shall be hand operated or automatic. Hand operated flush controls shall comply with 309. Flush controls shall be located on the open side of the water closet except in ambulatory accessible compartments complying with 604.8.2.

604.7 Dispensers
Toilet paper dispensers shall comply with 309.4 and shall be 7 inches (180 mm) minimum and 9 inches (230 mm) maximum in front of the water closet measured to the centerline of the dispenser. The outlet of the dispenser shall be 15 inches (380 mm) minimum and 48 inches (1220 mm) maximum above the finish floor and shall not be located behind grab bars. Dispensers shall not be of a type that controls delivery or that does not allow continuous paper flow.

Advisory 604.7 Dispensers. If toilet paper dispensers are installed above the side wall grab bar, the outlet of the toilet paper dispenser must be 48 inches (1220 mm) maximum above the finish floor and the top of the gripping surface of the grab bar must be 33 inches (840 mm) minimum and 36 inches (915 mm) maximum above the finish floor.




Figure 604.7 Dispenser Outlet Location

604.8 Toilet Compartments
Wheelchair accessible toilet compartments shall meet the requirements of 604.8.1 and

604.8.3. Compartments containing more than one plumbing fixture shall comply with 603. Ambulatory accessible compartments shall comply with 604.8.2 and 604.8.3.

604.8.1 Wheelchair Accessible Compartments
Wheelchair accessible compartments shall comply with 604.8.1.

604.8.1.1 Size
Wheelchair accessible compartments shall be 60 inches (1525 mm) wide minimum measured perpendicular to the side wall, and 56 inches (1420 mm) deep minimum for wall hung water closets and 59 inches (1500 mm) deep minimum for floor mounted water closets measured perpendicular to the rear wall. Wheelchair accessible compartments for children's use shall be 60 inches (1525 mm) wide minimum measured perpendicular to the side wall, and 59 inches (1500 mm) deep minimum for wall hung and floor mounted water closets measured perpendicular to the rear wall.

Advisory 604.8.1.1 Size. The minimum space required in toilet compartments is provided so that a person using a wheelchair can maneuver into position at the water closet. This space cannot be obstructed by baby changing tables or other fixtures or conveniences, except as specified at 604.3.2 (Overlap). If toilet compartments are to be used to house fixtures other than those associated with the water closet, they must be designed to exceed the minimum space requirements. Convenience fixtures such as baby changing tables must also be accessible to people with disabilities as well as to other users. Toilet compartments that are designed to meet, and not exceed, the minimum space requirements may not provide adequate space for maneuvering into position at a baby changing table.




Figure 604.8.1.1 Size of Wheelchair Accessible Toilet Compartment

604.8.1.2 Doors
Toilet compartment doors, including door hardware, shall comply with 404 except that if the approach is to the latch side of the compartment door, clearance between the door side of the compartment and any obstruction shall be 42 inches (1065 mm) minimum. Doors shall be located in the front partition or in the side wall or partition farthest from the water closet. Where located in the front partition, the door opening shall be 4 inches (100 mm) maximum from the side wall or partition farthest from the water closet. Where located in the side wall or partition, the door opening shall be 4 inches (100 mm) maximum from the front partition. The door shall be self-closing. A door pull complying with 404.2.7 shall be placed on both sides of the door near the latch. Toilet compartment doors shall not swing into the minimum required compartment area.




Figure 604.8.1.2 Wheelchair Accessible Toilet Compartment Doors

604.8.1.3 Approach
Compartments shall be arranged for left-hand or right-hand approach to the water closet.

604.8.1.4 Toe Clearance
The front partition and at least one side partition shall provide a toe clearance of 9 inches (230 mm) minimum above the finish floor and 6 inches (150 mm) deep minimum beyond the compartment-side face of the partition, exclusive of partition support members. Compartments for children's use shall provide a toe clearance of 12 inches (305 mm) minimum above the finish floor.

EXCEPTION: Toe clearance at the front partition is not required in a compartment greater than 62 inches (1575 mm) deep with a wall-hung water closet or 65 inches (1650 mm) deep with a floor-mounted water closet. Toe clearance at the side partition is not required in a compartment greater than 66 inches (1675 mm) wide. Toe clearance at the front partition is not required in a compartment for children's use that is greater than 65 inches (1650 mm) deep.




Figure 604.8.1.4 Wheelchair Accessible Toilet Compartment Toe Clearance

604.8.1.5 Grab Bars
Grab bars shall comply with 609. A side-wall grab bar complying with 604.5.1 shall be provided and shall be located on the wall closest to the water closet. In addition, a rear-wall grab bar complying with 604.5.2 shall be provided.

605 Urinals

605.1 General
Urinals shall comply with 605.

605.2 Height and Depth
Urinals shall be the stall-type or the wall-hung type with the rim 17 inches (430 mm) maximum above the finish floor or ground. Urinals shall be 13½ inches (345 mm) deep minimum measured from the outer face of the urinal rim to the back of the fixture.




Figure 605.2 Height and Depth of Urinals

605.3 Clear Floor Space
A clear floor or ground space complying with 305 positioned for forward approach shall be provided.

605.4 Flush Controls
Flush controls shall be hand operated or automatic. Hand operated flush controls shall comply with 309.

606 Lavatories and Sinks
606.1 General
Lavatories and sinks shall comply with 606.

606.2 Clear Floor Space
A clear floor space complying with 305, positioned for a forward approach, and knee and toe clearance complying with 306 shall be provided.

EXCEPTIONS:
1. A parallel approach complying with 305 shall be permitted to a kitchen sink in a space where a cook top or conventional range is not provided and to wet bars.

2. A lavatory in a toilet room or bathing facility for a single occupant accessed only through a private office and not for common use or public use shall not be required to provide knee and toe clearance complying with 306.

3. In residential dwelling units, cabinetry shall be permitted under lavatories and kitchen sinks provided that all of the following conditions are met:
-the cabinetry can be removed without removal or replacement of the fixture;
-the finish floor extends under the cabinetry; and
-the walls behind and surrounding the cabinetry are finished.

4. A knee clearance of 24 inches (610 mm) minimum above the finish floor or ground shall be permitted at lavatories and sinks used primarily by children 6 through 12 years where the rim or counter surface is 31 inches (785 mm) maximum above the finish floor or ground.

5. A parallel approach complying with 305 shall be permitted to lavatories and sinks used primarily by children 5 years and younger.

6. The dip of the overflow shall not be considered in determining knee and toe clearances.
7. No more than one bowl of a multi-bowl sink shall be required to provide knee and toe clearance complying with 306.

606.3 Height
Lavatories and sinks shall be installed with the front of the higher of the rim or counter surface 34 inches (865 mm) maximum above the finish floor or ground.

EXCEPTIONS:
1. A lavatory in a toilet or bathing facility for a single occupant accessed only through a private office and not for common use or public use shall not be required to comply with 606.3.

2. In residential dwelling unit kitchens, sinks that are adjustable to variable heights, 29 inches (735 mm) minimum and 36 inches (915 mm) maximum, shall be permitted where rough-in plumbing permits connections of supply and drain pipes for sinks mounted at the height of 29 inches (735 mm).

606.4 Faucets
Controls for faucets shall comply with 309. Hand-operated metering faucets shall remain open for 10 seconds minimum.

606.5 Exposed Pipes and Surfaces
Water supply and drain pipes under lavatories and sinks shall be insulated or otherwise configured to protect against contact. There shall be no sharp or abrasive surfaces under lavatories and sinks.

902 Dining Surfaces and Work Surfaces

902.1 General
Dining surfaces and work surfaces shall comply with 902.2 and 902.3.

EXCEPTION: Dining surfaces and work surfaces for children's use shall be permitted to comply with 902.4.

Advisory 902.1 General. Dining surfaces include, but are not limited to, bars, tables, lunch counters, and booths. Examples of work surfaces include writing surfaces, study carrels, student laboratory stations, baby changing and other tables or fixtures for personal grooming, coupon counters, and where covered by the ABA scoping provisions, employee work stations.

902.2 Clear Floor or Ground Space
A clear floor space complying with 305 positioned for a forward approach shall be provided. Knee and toe clearance complying with 306 shall be provided.

902.3 Height
The tops of dining surfaces and work surfaces shall be 28 inches (710 mm) minimum and 34 inches (865 mm) maximum above the finish floor or ground.

902.4 Dining Surfaces and Work Surfaces for Children's Use
Accessible dining surfaces and work surfaces for children's use shall comply with 902.4.

EXCEPTION: Dining surfaces and work surfaces that are used primarily by children 5 years and younger shall not be required to comply with 902.4 where a clear floor or ground space complying with 305 positioned for a parallel approach is provided.

902.4.1 Clear Floor or Ground Space
A clear floor space complying with 305 positioned for forward approach shall be provided. Knee and toe clearance complying with 306 shall be provided, except that knee clearance 24 inches (610 mm) minimum above the finish floor or ground shall be permitted.

902.4.2 Height
The tops of tables and counters shall be 26 inches (660 mm) minimum and 30 inches (760 mm) maximum above the finish floor or ground.


903 Benches

903.1 General
Benches shall comply with 903.

903.2 Clear Floor or Ground Space
Clear floor or ground space complying with 305 shall be provided and shall be positioned at the end of the bench seat and parallel to the short axis of the bench.

903.3 Size
Benches shall have seats that are 42 inches (1065 mm) long minimum and 20 inches (510 mm) deep minimum and 24 inches (610 mm) deep maximum.

903.4 Back Support
The bench shall provide for back support or shall be affixed to a wall. Back support shall be 42 inches (1065 mm) long minimum and shall extend from a point 2 inches (51 mm) maximum above the seat surface to a point 18 inches (455 mm) minimum above the seat surface. Back support shall be 2½ inches (64 mm) maximum from the rear edge of the seat measured horizontally.



903.5 Height
The top of the bench seat surface shall be 17 inches (430 mm) minimum and 19 inches (485 mm) maximum above the finish floor or ground.

903.6 Structural Strength
Allowable stresses shall not be exceeded for materials used when a vertical or horizontal force of 250 pounds (1112 N) is applied at any point on the seat, fastener, mounting device, or supporting structure.

903.7 Wet Locations
Where installed in wet locations, the surface of the seat shall be slip resistant and shall not accumulate water.

General Notes

- The dimensions on this sheet are based on FACE OF FINISH material. GC to field verify all existing dimension prior to construction and/or installation of any equipment, accessories, etc. If discrepancy is identified, notify ARCHITECT immediately.
- The following items will be OSCI – Owner Supplied/Contractor Installed. all moveable equipment (any item not hard plumbed into the wall), stainless steel equipments, tables selvings.
- Refer to appropriate sheet and/or schedule for additional information/detail regarding items shown herein.
- Keynotes located on this sheet are for his sheet only.
- Do not scale the drawing. If a specific dimension is not given, contact ARCHITECT for clarification.
- Refer to Sheet A001 – General Conditions for additional information associated with, but not limited to: submittals, shop drawings, samples, cutting and patching, coordination and staging, protection of work.

No.	Revision/Issue	Date

Firm Name and Address

ArcDesignContractors

Arc Design Contractors
2918 Bellamy Circle
Cedar Park, Texas 78613
arcdesigncontractors.com

Project Name and Address

DISTRICT 901 BLDN 1
901 N ALAMO ST
SAN ANTONIO, TX 78215

Sheet Title

ADA NOTES CONT.

Sheet

G003

Project

DISTRICT 901 BLDN 1

Date


7/25/2024

Scale

As Noted



2 EXISTING PLAN - LEVEL 2
SCALE: 1/8" = 1' - 0"



1 EXISTING PLAN - LEVEL 1
SCALE: 1/8" = 1' - 0"



General Notes

- A. The dimensions on this sheet are based of of FACE OF FINISH material.
- B. GC to field verify all existing dimension prior to construction and/or installation of any equipment, accessories, etc. If discrepancy is identified, notify ARCHITECT immediately.
- C. The following items will be OSCI – Owner Supplied/Contractor Installed. all moveable equipment (any item not hard plumbed into the wall), stainless steep equipments, tables selvings.
- D. Refer o appropriate sheet and/or schedule for additional information/detail regarding items shown herein.
- E. Keynotes located on this sheet are for his sheet only.
- F. Do not scale the drawing. If a specific dimension is not given, contact ARCHITECT for clarification.
- G. Refer to Sheet A001 – General Conditions for additional information associated with, but not limited to: submittals, shop drawings, samples, cutting and patching, coordination and staging, protection of work.

No.	Revision/Issue	Date

Firm Name and Address
ArcDesignContractors
Arc Design Contractors
2918 Bellamy Circle
Cedar Park, Texas 78613
arcdesigncontractors.com

Project Name and Address DISTRICT 901 BLND 1 901 N ALAMO ST SAN ANTONIO, TX 78215	
Sheet Title	EXISTING PLAN
Sheet	A101
Project	DISTRICT 901 BLDN 1
Date	7/25/2024
Scale	As Noted



1 DEMO PLAN - LEVEL 1
SCALE: 3/16" = 1'-0"

2 DEMO PLAN - LEVEL 2
SCALE: 1/8" = 1' - 0"

General Notes

- A. The dimensions on this sheet are based of of FACE OF FINISH material.
- B. GC to field verify all existing dimension prior to construction and/or installation of any equipment, accessories, etc. If discrepancy is identified, notify ARCHITECT immediately.
- C. The following items will be OSCI – Owner Supplied/Contractor Installed. all moveable equipment (any item not hard plumbed into the wall), stainless steep equipments, tables selvings.
- D. Refer o appropriate sheet and/or schedule for additional information/detail regarding items shown herein.
- E. Keynotes located on this sheet are for his sheet only.
- F. Do not scale the drawing. If a specific dimension is not given, contact ARCHITECT for clarification.
- G. Refer to Sheet A001 – General Conditions for additional information associated with, but not limited to: submittals, shop drawings, samples, cutting and patching, coordination and staging, protection of work.



No.	Revision/Issue	Date

Firm Name and Address
ArcDesignContractors
Arc Design Contractors
2918 Bellamy Circle
Cedar Park, Texas 78613
arcdesigncontractors.com

Project Name and Address
DISTRICT 901 BLND 1
901 N ALAMO ST
SAN ANTONIO, TX 78215

Sheet Title
DEMO PLAN
A102

Project DISTRICT 901 BLDN 1
Date 7/25/2024
Scale As Noted



1 PROPOSED PLAN - LEVEL 1
SCALE: 3/16" = 1' - 0"

2 PROPOSED PLAN - LEVEL 2
SCALE: 1/8" = 1' - 0"

General Notes

- A. The dimensions on this sheet are based of of FACE OF FINISH material.
- B. GC to field verify all existing dimension prior to construction and/or installation of any equipment, accessories, etc. If discrepancy is identified, notify ARCHITECT immediately.
- C. The following items will be OSCI – Owner Supplied/Contractor Installed. all moveable equipment (any item not hard plumbed into the wall), stainless steep equipments, tables selvings.
- D. Refer o appropriate sheet and/or schedule for additional information/detail regarding items shown herein.
- E. Keynotes located on this sheet are for his sheet only.
- F. Do not scale the drawing. If a specific dimension is not given, contact ARCHITECT for clarification.
- G. Refer to Sheet A001 – General Conditions for additional information associated with, but not limited to: submittals, shop drawings, samples, cutting and patching, coordination and staging, protection of work.

No.	Revision/Issue	Date

Firm Name and Address

ArcDesignContractors

Arc Design Contractors
2918 Bellamy Circle
Cedar Park, Texas 78613
arcdesigncontractors.com

Project Name and Address

DISTRICT 901 BLDN 1
901 N ALAMO ST
SAN ANTONIO, TX 78215

Sheet Title

PROPOSED PLAN

Sheet

A103

Project

DISTRICT 901 BLDN 1

Date

7/25/2004

Scale

As Noted

General Notes

- A. The dimensions on this sheet are based of of FACE OF FINISH material.
B. GC to field verify all existing dimension prior to construction and/or installation of any equipment, accessories, etc. If discrepancy is identified, notify ARCHITECT immediately.
C. The following items will be OSCI – Owner Supplied/Contractor Installed. all moveable equipment (any item not hard plumbed into the wall), stainless steep equipments, tables selvings.
D. Refer o appropriate sheet and/or schedule for additional information/detail regarding items shown herein.
E. Keynotes located on this sheet are for his sheet only.
F. Do not scale the drawing. If a specific dimension is not given, contact ARCHITECT for clarification.
G. Refer to Sheet A001 – General Conditions for additional information associated with, but not limited to: submittals, shop drawings, samples, cutting and patching, coordination and staging, protection of work.

No.	Revision/Issue	Date

Firm Name and Address

ArcDesignContractors

Arc Design Contractors
2918 Bellamy Circle
Cedar Park, Texas 78613
arcdesigncontractors.com

Project Name and Address

DISTRICT 901 BLDN 1
901 N ALAMO ST
SAN ANTONIO, TX 78215

Sheet Title

DIMENSIONS PLAN

Sheet

A104

Project


DISTRICT 901 BLDN 1

Date

7/25/2004

Scale

As Noted



1

DIMENSIONS PLAN - LEVEL 1


SCALE: 3/16" = 1' - 0"

2


DIMENSIONS PLAN - LEVEL 2

SCALE: 1/8" = 1' - 0"





1 CEILING PLAN - LEVEL 1
SCALE: 3/16" = 1' - 0"



2 CEILING PLAN - LEVEL 2
SCALE: 1/8" = 1' - 0"

CEILING SCHEDULE				
MARK	DESCRIPTION	MANUFACTURE	SIZE	NOTE
	CEILING TILE GYPSUM, FLUSH	USG	24 " X 24"	1 HR FIRE RATED
	WOODEN SLAT 2" WIDE	ARMSTRONG	2" X 96"	
	PINE WOOD SLAT 3.5" WIDE	ARMSTRONG	3.5" X 96"	

General Notes

- A. The dimensions on this sheet are based of of FACE OF FINISH material.
- B. GC to field verify all existing dimension prior to construction and/or installation of any equipment, accessories, etc. If discrepancy is identified, notify ARCHITECT immediately.
- C. The following items will be OSCI – Owner Supplied/Contractor Installed. all moveable equipment (any item not hard plumbed into the wall), stainless steep equipments, tables selvings.
- D. Refer o appropriate sheet and/or schedule for additional information/detail regarding items shown herein.
- E. Keynotes located on this sheet are for his sheet only.
- F. Do not scale the drawing. If a specific dimension is not given, contact ARCHITECT for clarification.
- G. Refer to Sheet A001 – General Conditions for additional information associated with, but not limited to: submittals, shop drawings, samples, cutting and patching, coordination and staging, protection of work.

No.	Revision/Issue	Date

Firm Name and Address

ArcDesignContractors

Arc Design Contractors
2918 Bellamy Circle
Cedar Park, Texas 78613
arcdesigncontractors.com

Project Name and Address

DISTRICT 901 BLDN 1
901 N ALAMO ST
SAN ANTONIO, TX 78215

Sheet Title

CEILING PLAN

Sheet

A105

Project


DISTRICT 901 BLDN 1

Date


7/25/2004

Scale

As Noted



1 FLOOR PLAN - LEVEL 1
SCALE: 3/16" = 1' - 0"



2 FLOOR PLAN - LEVEL 2
SCALE: 1/8" = 1' - 0"

FLOOR FINISH SCHEDULE				
MARK	NAME	MANUFACTURE	SIZE	NOTE
	REFLEXION	DUR-A-FLEX	SAND	COLOR: SLATE
	European Oak Rustic Distressed Engineered Hardwood	WOODLAND RESERVE	5/8" X 9.5"	
	Trex composite decking	TREX	20' x 5.5"	GREY
	DUR-A-QUARTZ	DUR-A-FLEX		COLOR: SLATE

General Notes

- A. The dimensions on this sheet are based of of FACE OF FINISH material.
- B. GC to field verify all existing dimension prior to construction and/or installation of any equipment, accessories, etc. If discrepancy is identified, notify ARCHITECT immediately.
- C. The following items will be OSCI – Owner Supplied/Contractor Installed. all moveable equipment (any item not hard plumbed into the wall), stainless steep equipments, tables selvings.
- D. Refer o appropriate sheet and/or schedule for additional information/detail regarding items shown herein.
- E. Keynotes located on this sheet are for his sheet only.
- F. Do not scale the drawing. If a specific dimension is not given, contact ARCHITECT for clarification.
- G. Refer to Sheet A001 – General Conditions for additional information associated with, but not limited to: submittals, shop drawings, samples, cutting and patching, coordination and staging, protection of work.

No.	Revision/Issue	Date

Firm Name and Address

ArcDesignContractors

Arc Design Contractors
2918 Bellamy Circle
Cedar Park, Texas 78613
arcdesigncontractors.com

Project Name and Address

DISTRICT 901 BLDN 1
901 N ALAMO ST
SAN ANTONIO, TX 78215

Sheet Title

FLOOR PLAN
Sheet
A106

Project


DISTRICT 901 BLDN 1

Date

7/25/2004

Scale


As Noted



1

LIFE SAFETY PLAN - LEVEL 1

SCALE: 3/16" = 1' - 0"



OCCUPANCY CALCULATION							
AREA	FLOOR	SQFT	OCCUPANCY	OCCUPANT	OCCUPANCY CLASSIFICATION	REQUIRED EXIT	POSTED SIGN REQUIREMENT
LOUNGE 1	1	297	20	15 NET	ASSEMBLY WITHOUT FIXED SEATS: UNCONCENTRATED (TABLES & CHAIR)	2	YES
STORAGE ROOM	1	415	1	300 NET	STORAGE	1	NO
WAITING AREA	1	501	33	15 NET	WAITING	2	YES
BAR/KITCHEN	1	196	1	200 GROSS		1	NO
LOUNGE 2	2	281	19	15 NET	ASSEMBLY WITHOUT FIXED SEATS: UNCONCENTRATED (TABLES & CHAIR)	2	YES
RESTROOM	2	85	1	300 GROSS	RESTROOM	1	NO
EXERCISE TERRACE	2	677	14	50 GROSS	EXERCISE	1	NO
MERCANTILE PATIO	2	407	7	60 GROSS	MERCANTILE	1	NO
BAR/KITCHEN	2	161	1	200 GROSS		1	NO
BUILDING 1 OCCUPANCY			95				

MINIMUM EGRESS DETERMINATION					
EGRESS COMPONENT	OCCUPANT LOAD SERVE	MINIMUM COMPONENT	CALCULATED MINIMUM WIDTH	MINIMUM REQUIREMENT	ACTUAL SIZE
DOOR "A"	95	32" IBC 1010.1.1	95*0.2=19"	32"	36"
DOOR "B"	95	32" IBC 1010.1.1	95*0.2=19"	32"	36"

2

LIFE SAFETY PLAN - LEVEL 2

SCALE: 1/8" = 1' - 0"

- General Notes
- A.

The dimensions on this sheet are based of of FACE OF FINISH material.

B.

GC to field verify all existing dimension prior to construction and/or installation of any equipment, accessories, etc. If discrepancy is identified, notify ARCHITECT immediately.

C.

The following items will be OSCI – Owner Supplied/Contractor Installed. all moveable equipment (any item not hard plumbed into the wall), stainless steep equipments, tables selvings.

D.

Refer o appropriate sheet and/or schedule for additional information/detail regarding items shown herein.

E.

Keynotes located on this sheet are for his sheet only.

F.

Do not scale the drawing. If a specific dimension is not given, contact ARCHITECT for clarification.

G.

Refer to Sheet A001 – General Conditions for additional information associated with, but not limited to: submittals, shop drawings, samples, cutting and patching, coordination and staging, protection of work.

No.	Revision/Issue	Date

Firm Name and Address

ArcDesignContractors

Arc Design Contractors
2918 Bellamy Circle
Cedar Park, Texas 78613
arcdesigncontractors.com

Project Name and Address

DISTRICT 901 BLDN 1
901 N ALAMO ST
SAN ANTONIO, TX 78215

Sheet Title

LIFE SAFETY PLAN

Sheet

A107

Project

DISTRICT 901 BLDN 1


Date

7/25/2004


Scale

As Noted


WALL SCHEDULE								
WALL ID	TYPE	THICKNESS	GAUGE	INSULATION	INTERIOR SHEATING	OTHER SIDED SHEATING	USE	NOTES
W1	METAL STUD	6"	18G	N/A	5/8" MOISTURE SHEETROCK	5/8" MOISTURE SHEETROCK	Pony wall for bar	BIRKIM POST 4" OC
W2	METAL STUD	3 5/8"	20G	N/A	5/8" MOISTURE SHEETROCK	5/8" MOISTURE SHEETROCK	Interior standard wall	BIRKIM POST 4" OC
W3	METAL STUD	6"	18G	6" FIRE RETARDANT INSULATION	5/8" MOISTURE SHEETROCK	5/8" DENSGLAS	Exterior wall	BRACING PER ENGINEER NOTE



1 WALL FINISH SCHEDULE - LEVEL 2
SCALE: 1/8" = 1' - 0"




2 WALL FINISH SCHEDULE - LEVEL 2
SCALE: 1/8" = 1' - 0"




General Notes

- The dimensions on this sheet are based of of FACE OF FINISH material.
- GC to field verify all existing dimension prior to construction and/or installation of any equipment, accessories, etc. If discrepancy is identified, notify ARCHITECT immediately.
- The following items will be OSCI – Owner Supplied/Contractor Installed. all moveable equipment (any item not hard plumbed into the wall), stainless steep equipments, tables selvings.
- Refer o appropriate sheet and/or schedule for additional information/detail regarding items shown herein.
- Keynotes located on this sheet are for his sheet only.
- Do not scale the drawing. If a specific dimension is not given, contact ARCHITECT for clarification.
- Refer to Sheet A001 – General Conditions for additional information associated with, but not limited to: submittals, shop drawings, samples, cutting and patching, coordination and staging, protection of work.




A0 GENERAL FRAMING SCHEMATIC
NTS




A4 HEADER DETAILS
NTS




A5 FLOOR STUD
NTS




A6 TOP TRACK TYP.
NTS




A1 TOP TRACK TYP.
NTS




A7 HEADER TO STUD TYP.
NTS



A2 HEADER TO STUD TYP.
NTS



A8 HEADER X-SECTION TYP.
NTS



A3 HEADER X-SECTION TYP.
NTS

Wall Types General Notes

- The dimensions on this sheet are based off of FACE OF FINISH, unless otherwise noted.
- GC to field verify all existing dimensions prior to construction and/or installation of any equipment, accessories, etc. If a discrepancy is identified, notify ARCHITECT immediately.
- Refer to appropriate sheet and/or schedule for additional information/detail regarding items shown herein.
- Keynotes located on this sheet are for this sheet only.
- Do not scale the drawings. If a specific dimension is not given, contact ARCHITECT for clarification.
- Refer to Sheet A0.1-General Conditions for additional information associated with, but not limited to: submittals, shop drawings, samples, cutting and patching, coordination and staging, protection of work.
- Install all products per manufacturer's recommendations.
- Contractor to submit all drywall, mud and accessories to architect and building owner for written approval. Provide cutbooks for all products.
- All drywall products and accessories to be ASBESTOS-Free.

Sheathing Specifications:

Tile Backer Board
Manufacturer: USG or approved equal
Product: Durock or Hardie Tie BackerBoard
Thickness: 3/8"
Fire Resistance: Type-X equivalent
Moisture Resist: Yes

Painted Drywall Surfaces
Manufacturer: USG or approved equal
Product: Type-X Gypsum Board
Thickness: 5/8"
Moisture Resist: Yes
Level Finish: LEVEL 4, smooth, no texture

Sound Batt Insulation
Manufacturer: Ultraloc
Product: Denim Insulation
Product #: 10002-01924
R-Value: 3 1/2" = R-19
6" = R-21

No.	Revision/Issue	Date

Firm Name and Address

ArcDesignContractors

Arc Design Contractors
2918 Bellamy Circle
Cedar Park, Texas 78613
arcdesigncontractors.com

Project Name and Address

DISTRICT 901 BLDN 1
901 N ALAMO ST
SAN ANTONIO, TX 78215

Sheet Title

WALL SCHEDULE

Sheet

A500

Project


DISTRICT 901 BLDN 1

Date


7/25/2004

Scale


As Noted



1 NORTHWEST ELEVATION
SCALE: 3/16" = 1'-0"



2 SOUTHEAST ELEVATION
SCALE: 3/16" = 1'-0"



3 SOUTHWEST ELEVATION
SCALE: 3/16" = 1'-0"



4 NORTHEAST ELEVATION
SCALE: 3/16" = 1'-0"

General Notes

- The dimensions on this sheet are based of of FACE OF FINISH material.
- GC to field verify all existing dimension prior to construction and/or installation of any equipment, accessories, etc. If discrepancy is identified, notify ARCHITECT immediately.
- The following items will be OSCI – Owner Supplied/Contractor Installed. all moveable equipment (any item not hard plumbed into the wall), stainless steep equipments, tables selvings.
- Refer o appropriate sheet and/or schedule for additional information/detail regarding items shown herein.
- Keynotes located on this sheet are for his sheet only.
- Do not scale the drawing. If a specific dimension is not given, contact ARCHITECT for clarification.
- Refer to Sheet A001 – General Conditions for additional information associated with, but not limited to: submittals, shop drawings, samples, cutting and patching, coordination and staging, protection of work.

No.	Revision/Issue	Date

Firm Name and Address

ArcDesignContractors

Arc Design Contractors
2918 Bellamy Circle
Cedar Park, Texas 78613
arcdesigncontractors.com

Project Name and Address

DISTRICT 901 BLDN 1
901 N ALAMO ST
SAN ANTONIO, TX 78215

Sheet Title

EXTERIOR ELEVATION

Sheet

A501

Project


DISTRICT 901 BLDN 1

Date


7/25/2004

Scale


As Noted




1 INTERIOR ELEVATION - L1
SCALE: 3/16" = 1' - 0"




5 STORAGE L1
A502 NTS




6 STORAGE L1
A502 NTS




7 STORAGE L1
A502 NTS




8 STORAGE L1
A502 NTS




9 COCKTAIL LOUNGE L2
A503 NTS



10 COCKTAIL LOUNGE L2
A503 NTS



11 COCKTAIL LOUNGE L2
A503 NTS



12 COCKTAIL LOUNGE L2
A503 NTS

General Notes

- A. The dimensions on this sheet are based of of FACE OF FINISH material.
- B. GC to field verify all existing dimension prior to construction and/or installation of any equipment, accessories, etc. If discrepancy is identified, notify ARCHITECT immediately.
- C. The following items will be OSCI – Owner Supplied/Contractor Installed. all moveable equipment (any item not hard plumbed into the wall), stainless steep equipments, tables selvings.
- D. Refer o appropriate sheet and/or schedule for additional information/detail regarding items shown herein.
- E. Keynotes located on this sheet are for his sheet only.
- F. Do not scale the drawing. If a specific dimension is not given, contact ARCHITECT for clarification.
- G. Refer to Sheet A001 – General Conditions for additional information associated with, but not limited to: submittals, shop drawings, samples, cutting and patching, coordination and staging, protection of work.

No.	Revision/Issue	Date

Firm Name and Address

ArcDesignContractors

Arc Design Contractors
2918 Bellamy Circle
Cedar Park, Texas 78613
arcdesigncontractors.com

Project Name and Address

DISTRICT 901 BLDN 1
901 N ALAMO ST
SAN ANTONIO, TX 78215

Sheet Title

INTERIOR ELEVATION L1

Sheet

A502

Project


DISTRICT 901 BLDN 1

Date


7/25/2004

Scale


As Noted




1 INTERIOR ELEVATION - L2
SCALE: 3/16" = 1' - 0"




9 COCKTAIL LOUNGE L2
A503 NTS




10 COCKTAIL LOUNGE L2
A503 NTS



11 COCKTAIL LOUNGE L2
A503 NTS



12 COCKTAIL LOUNGE L2
A503 NTS



13 RESTROOM L2
A503 NTS

14 RESTROOM L2
A503 NTS

15 RESTROOM L2
A503 NTS

16 RESTROOM L2
A503 NTS

General Notes

- The dimensions on this sheet are based of of FACE OF FINISH material.
- GC to field verify all existing dimension prior to construction and/or installation of any equipment, accessories, etc. If discrepancy is identified, notify ARCHITECT immediately.
- The following items will be OSCI – Owner Supplied/Contractor Installed. all moveable equipment (any item not hard plumbed into the wall), stainless steel equipments, tables selvings.
- Refer o appropriate sheet and/or schedule for additional information/detail regarding items shown herein.
- Keynotes located on this sheet are for his sheet only.
- Do not scale the drawing. If a specific dimension is not given, contact ARCHITECT for clarification.
- Refer to Sheet A001 – General Conditions for additional information associated with, but not limited to: submittals, shop drawings, samples, cutting and patching, coordination and staging, protection of work.

No.	Revision/Issue	Date

Firm Name and Address

ArcDesignContractors

Arc Design Contractors
2918 Bellamy Circle
Cedar Park, Texas 78613
arcdesigncontractors.com

Project Name and Address

DISTRICT 901 BLDN 1
901 N ALAMO ST
SAN ANTONIO, TX 78215

Sheet Title

INTERIOR ELEVATION L2

Sheet

A503

Project


DISTRICT 901 BLDN 1

Date


7/25/2004

Scale


As Noted




1 CROSS SECTION
SCALE: 3" = 1' - 0"




2 CROSS SECTION
SCALE: 3" = 1' - 0"




3 CROSS SECTION
SCALE: 3" = 1' - 0"



4 CROSS SECTION
SCALE: 3" = 1' - 0"



5 CROSS SECTION
SCALE: 3" = 1' - 0"



6 CROSS SECTION
SCALE: 3" = 1' - 0"

General Notes

- A. The dimensions on this sheet are based of of FACE OF FINISH material.
- B. GC to field verify all existing dimension prior to construction and/or installation of any equipment, accessories, etc. If discrepancy is identified, notify ARCHITECT immediately.
- C. The following items will be OSCI – Owner Supplied/Contractor Installed. all moveable equipment (any item not hard plumbed into the wall), stainless steep equipments, tables selvings.
- D. Refer o appropriate sheet and/or schedule for additional information/detail regarding items shown herein.
- E. Keynotes located on this sheet are for his sheet only.
- F. Do not scale the drawing. If a specific dimension is not given, contact ARCHITECT for clarification.
- G. Refer to Sheet A001 – General Conditions for additional information associated with, but not limited to: submittals, shop drawings, samples, cutting and patching, coordination and staging, protection of work.

No.	Revision/Issue	Date

Firm Name and Address

ArcDesignContractors

Arc Design Contractors
2918 Bellamy Circle
Cedar Park, Texas 78613
arcdesigncontractors.com

Project Name and Address

DISTRICT 901 BLDN 1
901 N ALAMO ST
SAN ANTONIO, TX 78215

Sheet Title

DETAILS

Sheet

A504

Project

DISTRICT 901 BLDN 1

Date

7/25/2004

Scale

As Noted

PORCELAIN TILE

PT-1	Manufacturer	DAL-TILE
	Color	GREEN BEDROCK
	Style	Medella Hues(C2062)
	Product Type	PORCELAIN
	Thickness	3/8"
	Finish	GRAIN
	Installation	MOTAR
	Install Method	TILE
PT-2	Manufacturer	MOHAWK GROUP
	Style	Bolder 5.0(C2108)
	Product Type	Luxury Vinyl Tile
	Thickness	5 mm
	Finish	M-Force Ultra
	Installation	LOOSE LAY
	Install Method	MONOLITHIC, BRICK, ASHLAR, RANDOM

WOOD GRAIN PLYWOOD

WL-1	Manufacturer	GEORGIA PACIFIC
	Material	MDF(Medium Density Fiberboard)
	Finish	Laminate TFL Panel
	Name/No	8260
	Color	WHITE OAK WOOD
	Texture	17 Silken Wood
	Installation	Securely fastened with adhesive and nails
WL-2	Design Repeat	W 48.0" L 96.0"
	Manufacturer	GEORGIA PACIFI
	Material	MDF(Medium Density Fiberboard)
	Finish	Laminate TFL Panel
	Name/No	8248
	Color	BLACK HILLS OAK
	Texture	79 Ridgewood
	Installation	Securely fastened with adhesive and nails
	Design Repeat	W 62.4" L 51.4"

TOILET ACCESSORIES

TA-1	GRAB BARS	
TA-1.1	Description	36" Straight Grab Bar
	Manufacturer	Bobrick
	Thickness	B-5806-36
TA-1.2	Description	42" Straight Grab Bar
	Manufacturer	Bobrick
	Thickness	B-5806-42
TA-1	TOILET PAPER	
TA-1.1	Description	Toilet Tissue Dipenser-Surfaced Mounted
	Manufacturer	Bobrick
	Thickness	B-4288

WALL PAINT

PT-1	Manufacturer	SHERWIN WILLIAMS
	Color No.	SW 7008 Alabaster
	Sheen	SATIN
	Substrate	GYP.BD - LEVEL 4
	Remarks	ACRYLIC LATEX

FIBER REINFORCE POLYMER



FRP-1	Manufacturer	USG BUILD
	Color	White
	Style	Coarse
	Product Type	FRP
	Thickness	6 mm
	Finish	Coarse
	Installation	GLUE DOWN
	Size	8' x 4'

MARBLE LAMINATE

ML-1	Manufacturer	WILSONART
	Finish	High Gloss
	Name/No	Y0675
	Texture	Golden Nero
	Size	W 8' L 10'

QUEEN ANNE CLAPBOARD & SIDING

XS-1	Manufacturer	JAMES HARDIE
	Finish	BEADED SELECT
	Name/No	CEDAR MILL
	Texture	BEADED
	Size	W 5" L 12'



General Notes

- A. The dimensions on this sheet are based of of FACE OF FINISH material.
- B. GC to field verify all existing dimension prior to construction and/or installation of any equipment, accessories, etc. If discrepancy is identified, notify ARCHITECT immediately.
- C. The following items will be OSCI – Owner Supplied/Contractor Installed. all moveable equipment (any item not hard plumbed into the wall), stainless steep equipments, tables selvings.
- D. Refer o appropriate sheet and/or schedule for additional information/detail regarding items shown herein.
- E. Keynotes located on this sheet are for his sheet only.
- F. Do not scale the drawing. If a specific dimension is not given, contact ARCHITECT for clarification.
- G. Refer to Sheet A001 – General Conditions for additional information associated with, but not limited to: submittals, shop drawings, samples, cutting and patching, coordination and staging, protection of work.

No.	Revision/Issue	Date

Firm Name and Address		
ArcDesignContractors		
Arc Design Contractors 2918 Bellamy Circle Cedar Park, Texas 78613 arcdesigncontractors.com		

Project Name and Address		
DISTRICT 901 BLDN 1 901 N ALAMO ST SAN ANTONIO, TX 78215		
Sheet Title		
FINISH SCHEDULE		
Sheet		
A505		
Project		
DISTRICT 901 BLDN 1		
Date		
7/25/2004		
Scale		
As Noted		

**Arc Design Contractors
2918 Bellamy Circle
Cedar Park, Texas 78613**

Assigned Request Number: 2024-31619
Address: 901 N ALAMO ST, SAN ANTONIO, TEXAS 78215
WORK TYPE: EXTERIOR ALTERATIONS

ATTN: Ms. Claudia Espinosa, Claudia.Espinosa2@SanAntonio.gov, Office of Historical Preservation San Antonio

Here are the “Additional Information Required” your office requested:

- 1) Attached are limited pictures that I’m able to take of the condition of the property.
- 2) I’ve also attached 4 sides to show existing and propose plans. Due to the darkness inside the metal warehouse (which we are proposing to remove), the southeast elevation actual picture is very dark
- 3) The specific material to be used is a combination of outdoor pinewood and James Hardie Baeded Select Cedarmill. We are proposing this because ee suspect existing stucco finish were install in the 1980s and are NOT part of the original Queen Anne Victorian Style. Furthermore, we have identified the existing front porch is beyond repair and will need full replacement.

- 4) Sheet A505 has been update to specify paint and finish information

QUEEN ANNE CLAPBOARD & SIDING

XS-1	Manufacturer	JAMES HARDIE
	Finish	BEADED SELECT
	Name/No	CEDAR MILL
	Texture	BEADED

ALL EXTERIOR PAINT JOB SHALL HAVE 1 COAT OF PRIMER AND 2 COATS OF FINISH PAINT.

Manufacturer	Sherwin-Williams
Color No.	SW 2829
Primer	Extreme Primer Bond
Finish	Emerald
Sheen	Semi-gloss
Remarks	ACRYLIC LATEX

- 5) This the what the proposed finish siding will look like



Hardie® Plank

Find your style

Your home is a blank canvas. Experiment with a variety of Hardie® Plank siding styles, textures, and stunning colors featuring our ColorPlus® Technology finishes to create your masterpiece.

Select your siding texture



Select Cedar mill®



Smooth



Beaded Select Cedar mill®



Beaded Smooth



Custom Colonial Roughsawn



Custom Colonial Smooth


NORTHWEST ELEVATION

REQUEST: DEMO and REPLACE using pinewood and like-kind material. Finish shall be according to XS-1 on sheet A505 of construction set

EXISTING:



PROPOSED:



4

NORTHEAST ELEVATION

SCALE: 3/16" = 1'-0"

NORTHWEST ELEVATION

REQUEST: DEMO obstruction awning to open

EXISTING:



PROPOSED:



1 NORTHWEST ELEVATION
SCALE: 3/16" = 1'-0"


SOUTHWEST ELEVATION

REQUEST: Demo and replace wooden shed are in the southwest part of the building with enclosed additions

EXISTING:



PROPOSED:




SOUTHEAST ELEVATION

REQUEST: ADD enclosure, construction new structure.

EXISTING:



PROPOSED:





ACE SPRING

NO
PARKING
ANYTIME
FOR ANY TIME
→

VIA

BUS STOP NUMBER
60947

TEXT STOP NO TO 52020
FOR ARRIVAL TIMES

BUS ROUTES

9	

(210) 362-2020
VIAInfo.net



@dodznft
Fiesta
2022

YOUR PROTECTION
OUR LOT IS
SECURED AND MONITORED
BY VIDEO CAMERA





ACE

ACE SPRING

NATIONAL



901 N. Alamo
210-227-9121
Full Service
Auto Repair
Oil Change
Tire Rotation
Brake Service
Air Filter
Wash & Wax

DETOUR
↑
BROADWAY ST

ACE SPRING SERVICE




















middle

92'

281'

222'

drop

17'6"

ceiling
9'4"



