Z-2022-10700109

Rezoning
from "FBZD " Form Based Zoning District
to "MPCD" Master Planned Community Development



LOCATION MAP
SCALE: 1" = 2000'

SCALE : 1"=300'
0' 300' 900'
600'

NOTES:
1. BEARINGS ARE BASED ON THE STATE PLANE COORDINATE SYSTEM ESTABLISHED FOR THE TEXAS SOUTH CENTRAL ZONE 4204, NORTH AMERICAN DATUM (NAD) OF 1983
2. SIDEWALKS SHALL BE INSTALLED ACCORDING TO UDC STANDARDS SECTION 35-506(D).
3. ALL BICYCLE FACILITIES WILL BE DESIGNED AND CONSTRUCTED IN COMPLIANCE WITH THE TEXAS MUTCD AND AASHTO GUIDELINES FOR BICYCLE FACILITIES, INCLUDING CROSSWALK AND SIGNAGE REQUIREMENTS
4. MINIMUM RESIDENTIAL LOT SIZE IS 4,000 SQUARE FEET.
5. PARKS/OPEN SPACE AREAS ARE INTENDED FOR RECREATIONAL OR COMMUNITY USE AND MAY INCLUDE BUT NOT BE LIMITED TO LAWNS, PLANTING AREAS, BIKEWAYS, WALKWAYS, OR WOODED AREAS. SPACE DOES NOT INCLUDE DRIVEWAYS, PARKING LOTS OR OTHER SURFACES FOR MOTOR VEHICULAR TRAFFIC.
6. JOGGING TRAILS OR WALKING TRAILS, OPEN PLAY AREAS, ATHLETIC COURTS, PLAYGROUNDS, AND PARKS SPACES ARE SHOWN ON THE SITE PLAN AND SHALL CONFORM TO THE STANDARDS IN SECTION 35-503 OF THE UDC AND CREDITS ISSUED PER TABLE 503-4
7. ALL DEVELOPMENT WITHIN THE BOUNDARIES OF THE MPCD PLAN SHALL BE REVIEWED FOR COMPLIANCE WITH THE MASTER PLANNED COMMUNITY DISTRICT DESIGN STANDARDS (SECTION 35-345 UNIFIED DEVELOPMENT CODE)
8. BUILDINGS WITHIN THE MPCD WILL CONFORM WITH THE HEIGHT RESTRICTIONS IN SECTION 35-345(f)(1)(k).
9. ALL LOTS WITHIN THE AREAS LABELED AS SINGLE FAMILY TOWNHOME ARE RESTRICTED TO TOWNHOME USE.
10. STREETS WITHIN ANY PROPOSED SUBDIVISION WILL PROVIDE A CONNECTIVITY RATIO OF NO LESS THAN 1.20 AS OUTLINED IN THE UDC. SECTION 35-505(e)(1). THE CONNECTIVITY INDEX WILL NOT APPLY TO SUBDIVISIONS WITH LESS THAN 125 SINGLE FAMILY LOTS.
11. SIDEWALKS AND BICYCLE FACILITIES ARE REQUIRED ON ALL ARTERIALS AND COLLECTORS PER UDC TABLE 506-3, NOTE 5
12. INTERNAL STREETS WILL MEET STREET INTERSECTION REQUIREMENTS PER UDC SECTION 35-506(f)(1)
13. INTERNAL STREETS WILL MEET MAXIMUM STREET LENGTH REQUIREMENTS PER UDC SECTION 35-515(b)(3)(B)
14. BLOCK WILL MEET BLOCK LENGTH REQUIREMENTS PER UDC 35-515(b)(3)(A)

LEGEND:

— — —	= CONTOURS
——— ———	= 100 YEAR FLOODPLAIN BOUNDARY
O.P.R.	= OFFICIAL PUBLIC RECORDS OF BEXAR COUNTY, TEXAS
R.O.W.	= RIGHT-OF-WAY
℄	= CENTERLINE

70' R.O.W. STREET SECTION - COLLECTOR
NOT TO SCALE



60' R.O.W. STREET SECTION - LOCAL "B"
NOT TO SCALE

50 'R.O.W. STREET SECTION - LOCAL "A"
NOT TO SCALE



TYPICAL STREET SECTION - ZARARMORA ST (ENHANCED SECONDARY ARTERIAL)
NOT TO SCALE

From: "FBZD" Form Based Zoning District

To: "MPCD" Master Planned Community Development



VIDA - MASTER PLANNED COMMUNITY DISTRICT PLAN

ZONING DESCRIPTION FOR
4.173 94 ACRE TRACT

A 173 94 acre tract of land, situated in the Fernando Rodriguez Survey, Abstract 13, and the Samuel Wilson Survey, No. 51, Abstract 804, City of San Antonio, Bexar County, Texas, being a portion of that called 293.27 acre tract of land as conveyed to Southstar at Verano Developer, LLC in Document No. 20200290004 in the Official Public Records (O.P.R.) of Bexar County, Texas, and recorded November 30, 2020, and being a portion of University Way, a variable width right-of-way as described in Volume 9524, Pages 217-219 of the Deed and Plat Records (D.P.R.) of said county, said 173 94 acres being more particularly described by metes and bounds as follows:

BEGINNING at a ½" iron rod with cap stamped "KFW SURVEYING" (grid coordinates: N: 13680132.3315, E: 2111458.7753) found for the southeast corner of said 293.27 acres, being in the westerly right-of-way line of Union Pacific Railroad, being in the north right-of-way line of Jaycee Boulevard (variable width R.O.W.), a 174.46 acre tract of land as conveyed to Jaycee Boulevard Verano Partners,