

STATE OF TEXAS  
COUNTY OF BEXAR

THE AREA BEING REPLATTED WAS PREVIOUSLY PLATTED ON THE PLAT OF  
McCrarry Tract Subd., Unit 6 WHICH IS RECORDED IN

VOLUME 20002 , PAGES 2010-2013 , PLAT RECORDS OF BEXAR COUNTY.

THE SAN ANTONIO PLANNING COMMISSION AT ITS MEETING OF  
HELD A PUBLIC HEARING WHICH INVOLVED NOTIFICATION ON THE PROPOSED REPLAT OF THIS  
PROPERTY.

I (WE), THE OWNER(S) OF THE LAND SHOWN ON THIS REPLAT HEREBY CERTIFY THAT THIS REPLAT  
DOES NOT AMEND OR REMOVE ANY COVENANTS OR RESTRICTIONS.

OWNER/DEVELOPER  
PULTE HOMES OF TEXAS, L.P.  
A TEXAS LIMITED PARTNERSHIP  
1718 DRY CREEK WAY, SUITE 120  
SAN ANTONIO, TX 78259  
PHONE: (210) 496-1985  
FAX: (210) 496-0449  
CONTACT PERSON: SEAN MILLER  
BY: PULTE NEVADA I LLC, A DELAWARE LIMITED  
LIABILITY COMPANY, ITS GENERAL PARTNER

OWNER \_\_\_\_\_  
DULY AUTHORIZED AGENT \_\_\_\_\_

SWORN AND SUBSCRIBED BEFORE ME THIS THE \_\_\_\_\_ DAY OF \_\_\_\_\_, A.D. \_\_\_\_\_.

\_\_\_\_\_  
NOTARY PUBLIC IN AND FOR THE STATE OF TEXAS.

MY COMMISSION EXPIRES: \_\_\_\_\_

## LEGEND

Ac.	= ACRES
B.S.L.	= BUILDING SETBACK LINE
C1	= CURVE NUMBER
C.B.	= COUNTY BLOCK
DRN.	= DRAINAGE
E.G.T.CA.	= ELECTRIC, GAS, TELEPHONE AND CABLE TELEVISION
ESMT.	= EASEMENT
N.T.S.	= NOT TO SCALE
L1	= LINE NUMBER
L.S.	= LINE SETBACK
O.H.E.	= OVERHEAD ELECTRIC
O.P.R.	= OFFICIAL PUBLIC RECORDS OF BEXAR COUNTY, TEXAS
PG.	= PAGE
PGS.	= PAGES
P.R.	= PLAT RECORDS OF BEXAR COUNTY, TEXAS
R.O.W.	= RIGHT-OF-WAY
VAR.	= VARIABLE
VOL.	= VOLUME
WID.	= WIDTH
---	= STREET CENTERLINE
---	= BUILDING SETBACK LINE
---	= PROPERTY LINE
---	= EXTRATERRITORIAL JURISDICTION LIMITS
---	= UNIT BOUNDARY NODE
1000.00	= MINIMUM PAD FINISHED FLOOR ELEVATION

## KEYNOTES

- 10' E.G.T.CA. ESM'T. (VOL. 20002, PGS. 1340-1343, P.R.)
- 10' E.G.T.CA. ESM'T. (VOL. 20002, PGS. 2010-2013, P.R.)
- 20' B.S.L. (VOL. 20002, PGS. 2010-2013, P.R.)
- 10' E.G.T.CA. ESM'T. & B.S.L. (VOL. 20002, PGS. 2010-2013, P.R.)
- 28' O.H.E. ESM'T. (VOL. 20002, PGS. 2010-2013, P.R.)
- ± 145' TO INTERSECTION OF LONG RIDER & BLUE FEATHER
- ± 375' TO INTERSECTION OF SNOWY RIVER & GREY FOX

STATE OF TEXAS  
COUNTY OF BEXAR

I HEREBY CERTIFY THAT PROPER ENGINEERING CONSIDERATION HAS BEEN GIVEN THIS PLAT TO THE  
MATTERS OF STREETS, LOTS, AND DRAINAGE LAYOUT. TO THE BEST OF MY KNOWLEDGE THIS PLAT  
CONFORMS TO ALL REQUIREMENTS OF THE UNIFIED DEVELOPMENT CODE, EXCEPT FOR THOSE  
VARIANCES GRANTED BY THE SAN ANTONIO PLANNING COMMISSION.

M.W. CUDE ENGINEERS, L.L.C.  
ANDREW R. LOWRY, P.E.

\_\_\_\_\_  
LICENSED PROFESSIONAL ENGINEER

STATE OF TEXAS  
COUNTY OF BEXAR

I HEREBY CERTIFY THAT THE ABOVE PLAT CONFORMS TO THE MINIMUM STANDARDS SET FORTH BY  
THE TEXAS BOARD OF PROFESSIONAL ENGINEERS AND LAND SURVEYORS ACCORDING TO AN ACTUAL  
SURVEY MADE ON THE GROUND BY:

M.W. CUDE ENGINEERS, L.L.C.  
YURI V. BALMACEA WHEELLOCK, R.P.L.S.

\_\_\_\_\_  
REGISTERED PROFESSIONAL LAND SURVEYOR

SURVEYOR'S NOTES:

1. ALL PROPERTY CORNERS SHOWN HEREON ARE SET ½" REBAR WITH PLASTIC SURVEYOR'S CAP STAMPED "CUDE" UNLESS OTHERWISE NOTED.
2. COORDINATES SHOWN HEREON ARE TEXAS SOUTH CENTRAL ZONE (4204 TXSC) STATE PLANE GRID COORDINATES, NORTH AMERICAN DATUM OF 1983 (2011) AS DERIVED FROM THE NGS/CORS NETWORK. DISTANCES SHOWN HEREON ARE GROUND DISTANCES MEASURED IN U.S. SURVEY FEET.
3. BEARINGS SHOWN HEREON ARE BASED ON THE TEXAS SOUTH CENTRAL ZONE (4204 TXSC) STATE PLANE GRID, NORTH AMERICAN DATUM OF 1983 (2011).

SAWS NOTES:

1. THE NUMBER OF WASTEWATER EQUIVALENT DWELLING UNITS (EDU'S) PAID FOR THIS SUBDIVISION PLAT ARE KEPT ON FILE UNDER THE PLAT NUMBER AT THE SAN ANTONIO WATER SYSTEM.
2. IMPACT FEE NOTE: WATER AND/OR WASTEWATER IMPACT FEES WERE NOT PAID AT THE TIME OF PLATING FOR THIS PLAT. ALL IMPACT FEES MUST BE PAID PRIOR TO WATER METER SET AND/OR WASTEWATER SERVICE CONNECTION.
3. THE DEVELOPER DEDICATES THE SANITARY SEWER AND/OR WATER MAINS TO THE SAN ANTONIO WATER SYSTEM UPON COMPLETION BY THE DEVELOPER AND ACCEPTANCE BY THE SAN ANTONIO WATER SYSTEM.
4. IN AN EFFORT TO MEET THE CITY OF SAN ANTONIO'S FIRE FLOW REQUIREMENTS FOR THE PROPOSED RESIDENTIAL DEVELOPMENT, THE PUBLIC WATER MAIN SYSTEM HAS BEEN DESIGNED FOR A MINIMUM FIRE FLOW DEMAND OF 1,750 G.P.M. AT 25 P.S.I. RESIDUAL PRESSURE. THE FIRE FLOW REQUIREMENTS FOR INDIVIDUAL STRUCTURES WILL BE REVIEWED DURING THE BUILDING PERMIT PROCESS IN ACCORDANCE WITH THE PROCEDURES SET FORTH BY THE CITY OF SAN ANTONIO DIRECTOR OF DEVELOPMENT SERVICES AND THE SAN ANTONIO FIRE DEPARTMENT FIRE MARSHAL.
5. THE SAN ANTONIO WATER SYSTEM IS HEREBY GRANTED THE RIGHT OF INGRESS AND EGRESS ACROSS GRANTOR'S ADJACENT PROPERTY TO ACCESS THE WATER EASEMENT(S) SHOWN ON THIS PLAT.
6. THE SAN ANTONIO WATER SYSTEM IS HEREBY GRANTED THE RIGHT OF INGRESS AND EGRESS ACROSS GRANTOR'S ADJACENT PROPERTY TO ACCESS THE WASTEWATER EASEMENT(S) SHOWN ON THIS PLAT.
7. SAN ANTONIO WATER SYSTEM HIGH PRESSURE NOTE:  
A PORTION OF THIS TRACT IS BELOW THE GROUND ELEVATION OF 985 FEET, WHERE THE STATIC PRESSURE WILL NORMALLY EXCEED 80 P.S.I. AT ALL SUCH LOCATIONS, THE DEVELOPER OR BUILDER SHALL INSTALL AT EACH LOT, ON THE CUSTOMER'S SIDE OF THE METER, AN APPROVED TYPE PRESSURE REGULATOR IN CONFORMANCE WITH THE PLUMBING CODE OF THE CITY OF SAN ANTONIO.

CPS/SAWS/COSA UTILITY NOTES:

1. THE CITY OF SAN ANTONIO AS PART OF ITS ELECTRIC, GAS, WATER, AND WASTEWATER SYSTEMS - CITY PUBLIC SERVICE BOARD (CPS ENERGY) AND SAN ANTONIO WATER SYSTEM (SAWS) - IS HEREBY DEDICATED EASEMENTS AND RIGHTS-OF-WAY FOR UTILITY, TRANSMISSION AND DISTRIBUTION INFRASTRUCTURE AND SERVICE FACILITIES IN THE AREAS DESIGNATED ON THIS PLAT AS "ELECTRIC EASEMENT," "ANCHOR EASEMENT," "SERVICE EASEMENT," "OVERHANG EASEMENT," "UTILITY EASEMENT," "GAS EASEMENT," "TRANSFORMER EASEMENT," "WATER EASEMENT," "SANITARY SEWER EASEMENT" AND/OR "RECYCLED WATER EASEMENT" FOR THE PURPOSE OF INSTALLING, CONSTRUCTING, RECONSTRUCTING, MAINTAINING, REMOVING, INSPECTING, PATROLLING, AND ERECTING UTILITY INFRASTRUCTURE AND SERVICE FACILITIES FOR THE REASONS DESCRIBED ABOVE. CPS ENERGY AND SAWS SHALL ALSO HAVE THE RIGHT TO RELOCATE SAID INFRASTRUCTURE AND SERVICE FACILITIES WITHIN EASEMENT AND RIGHT-OF-WAY AREAS, TOGETHER WITH THE RIGHT OF INGRESS AND EGRESS OVER GRANTOR'S ADJACENT LANDS FOR THE PURPOSE OF ACCESSING SUCH INFRASTRUCTURE AND SERVICE FACILITIES AND THE RIGHT TO REMOVE FROM SAID LANDS ALL TREES OR PARTS THEREOF, OR OTHER OBSTRUCTIONS WHICH ENDANGER OR MAY INTERFERE WITH THE EFFICIENCY OF WATER, SEWER, GAS, AND/OR ELECTRIC INFRASTRUCTURE AND SERVICE FACILITIES. NO BUILDINGS, STRUCTURES, CONCRETE SLABS, OR WALLS WILL BE PLACED WITHIN EASEMENT AREAS WITHOUT AN ENCROACHMENT AGREEMENT WITH THE RESPECTIVE UTILITY.
2. ANY CPS ENERGY OR SAWS MONETARY LOSS RESULTING FROM MODIFICATIONS REQUIRED OF CPS ENERGY OR SAWS INFRASTRUCTURE AND SERVICE FACILITIES, LOCATED WITHIN SAID EASEMENTS, DUE TO GRADE CHANGES OR GROUND ELEVATION ALTERATIONS SHALL BE CHARGED TO THE PERSON OR PERSONS DEEMED RESPONSIBLE FOR SAID GRADE CHANGES OR GROUND ELEVATION ALTERATIONS.
3. THIS PLAT DOES NOT AMEND, ALTER, RELEASE OR OTHERWISE AFFECT ANY EXISTING ELECTRIC, GAS, WATER, SEWER, DRAINAGE, TELEPHONE, CABLE EASEMENTS OR ANY OTHER EASEMENTS FOR UTILITIES UNLESS THE CHANGES TO SUCH EASEMENTS ARE DESCRIBED HEREON.
4. CONCRETE DRIVEWAY APPROACHES ARE ALLOWED WITHIN THE FIVE (5) AND TEN (10) FOOT WIDE ELECTRIC AND GAS EASEMENTS WHEN LOTS ARE SERVED ONLY BY UNDERGROUND ELECTRIC AND GAS FACILITIES.
5. ROOF OVERHANGS ARE ALLOWED WITHIN THE FIVE (5) AND TEN (10) FOOT WIDE ELECTRIC AND GAS EASEMENTS WHEN ONLY UNDERGROUND ELECTRIC AND GAS FACILITIES ARE PROPOSED OR EXISTING WITHIN THOSE FIVE (5) AND TEN (10) FOOT WIDE EASEMENTS.

TREE NOTE:

1. THIS SUBDIVISION IS SUBJECT TO A MASTER TREE PLAN (TRE-APP-22-38801000) AND A MASTER TREE PLAN (TRE-APP-APP-21-38801076) WHICH REQUIRES COMPLIANCE BY THE OWNERS OF ALL PROPERTY WITHIN THE PLAT BOUNDARY, AND THEIR EMPLOYEES AND CONTRACTORS, AND SHALL BE BINDING ON ALL SUCCESSORS IN TITLE EXCEPT FOR OWNERS OF SINGLE-FAMILY RESIDENTIAL LOTS SUBDIVIDED HEREUNDER FOR WHICH CONSTRUCTION OF A RESIDENTIAL STRUCTURE HAS BEEN COMPLETED. THE MASTER TREE PLAN IS ON FILE AT THE CITY OF SAN ANTONIO ARBORISTS OFFICE. NO TREES OR UNDERSTORY SHALL BE REMOVED WITHOUT PRIOR APPROVAL OF THE CITY ARBORIST OFFICE PER 35-477(H).

DRAINAGE NOTE:

1. NO STRUCTURE, FENCES, WALLS OR OTHER OBSTRUCTIONS THAT IMPEDE DRAINAGE SHALL BE PLACED WITHIN THE LIMITS OF THE DRAINAGE EASEMENTS SHOWN ON THIS PLAT. NO LANDSCAPING OR OTHER TYPE OF MODIFICATIONS, WHICH ALTER THE CROSS-SECTIONS OF THE DRAINAGE EASEMENT, AS APPROVED, SHALL BE ALLOWED WITHOUT THE APPROVAL OF THE DIRECTOR OF PUBLIC WORKS. THE CITY OF SAN ANTONIO AND BEXAR COUNTY SHALL HAVE THE RIGHT TO INGRESS AND EGRESS OVER GRANTOR'S ADJACENT PROPERTY TO REMOVE ANY IMPEDING OBSTRUCTIONS PLACED WITHIN THE LIMITS OF SAID DRAINAGE EASEMENTS AND TO MAKE ANY MODIFICATIONS OR IMPROVEMENTS WITHIN SAID DRAINAGE EASEMENTS.
2. LOT 904, BLOCK 273, C.B. 4450 LIES WITHIN THE FEMA 1% ANNUAL CHANCE (100-YR) FLOODPLAIN AS VERIFIED BY FEMA MAP PANEL: 4802C02156, DATED SEPTEMBER 29, 2010. A FEMA CLOMR FLOODPLAIN STUDY HAS BEEN PREPARED BY CUDE ENGINEERS AND WAS APPROVED BY THE CITY OF SAN ANTONIO AND BEXAR COUNTY. THE FLOODPLAIN STUDY (FEMA CASE NO. 21-06-0206R) IS PENDING APPROVAL BY FEMA. FLOODPLAIN INFORMATION IS SUBJECT TO CHANGE AS A RESULT OF FUTURE FEMA MAP REVISIONS AND/OR AMENDMENTS.
3. THE DRAINAGE EASEMENTS WERE DELINEATED TO CONTAIN THE LESSER OF HTE BOUNDARIES OF THE 1% ANNUAL CHANCE (100-YEAR) FLOOD ZONE ESTABLISHED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) IN ACCORDANCE WITH THE DFIRM PANEL 4802C02156, DATED SEPTEMBER 29, 2010, OR THE 1% ANNUAL CHANCE (100-YEAR) ULTIMATE DEVELOPMENT CONDITION WATER SURFACE ELEVATION. CONSTRUCTION, IMPROVEMENTS, OR STRUCTURES WITHIN THE DRAINAGE EASEMENTS AND FLOODPLAIN ARE PROHIBITED WITHOUT PRIOR WRITTEN APPROVAL FROM THE FLOODPLAIN ADMINISTRATOR OF THE CITY OF SAN ANTONIO OR BEXAR COUNTY.

MISCELLANEOUS NOTES:

1. RESIDENTIAL FINISHED FLOOR ELEVATIONS MUST BE A MINIMUM OF EIGHT INCHES ABOVE FINISHED ADJACENT GRADE. A GRADING PLAN SHALL BE PREPARED WHICH INDICATES A DRAINAGE PLAN FOR ALL LOTS IN THE SUBDIVISION.
2. FINISHED FLOOR ELEVATIONS FOR STRUCTURES ON LOTS CONTAINING FLOODPLAIN OR ADJACENT TO THE FLOODPLAIN SHALL BE IN COMPLIANCE WITH THE FLOODPLAIN REGULATION IN EFFECT AT TIME OF CONSTRUCTION. CONTACT BEXAR COUNTY PUBLIC WORKS FOR MORE INFORMATION.
3. THE ENTIRE NATURE OF THIS SUBDIVISION SHALL BE THE RESPONSIBILITY OF THE PROPERTY OWNERS, OR THE PROPERTY OWNERS' ASSOCIATION, OR ITS SUCCESSORS OR ASSIGNS AND NOT THE RESPONSIBILITY OF THE CITY OF SAN ANTONIO OR BEXAR COUNTY.
4. LOT 904, BLOCK 273, C.B. 4450, IS DESIGNATED AS OPEN SPACE AND AS A COMMON AREA AND A PUBLIC DRAINAGE EASEMENT.

STATE OF TEXAS  
COUNTY OF BEXAR


THE OWNER OF LAND SHOWN ON THIS PLAT, IN PERSON OR THROUGH A DULY AUTHORIZED AGENT, DEDICATES TO THE USE OF THE PUBLIC, EXCEPT AREAS IDENTIFIED AS PRIVATE OR PART OF AN ENCLAVE OR PLANNED UNIT DEVELOPMENT, FOREVER ALL STREETS, ALLEYS, PARKS, WATERCOURSES, DRAINS, EASEMENTS AND PUBLIC PLACES THEREON SHOWN FOR THE PURPOSE AND CONSIDERATION THEREIN EXPRESSED.

OWNER/DEVELOPER  
DAVIS RANCH HOMEOWNERS ASSOCIATION INC BY: \_\_\_\_\_  
C/O LIFETIME HOA MANAGEMENT  
18585 SIGMA ROAD #104  
SAN ANTONIO, TX 78258 NAME: \_\_\_\_\_  
PHONE: (210) 838-6784  
CONTACT PERSON: BRYAN SIMS TITLE: \_\_\_\_\_

STATE OF TEXAS  
COUNTY OF BEXAR

BEFORE ME, THE UNDERSIGNED AUTHORITY ON THIS DAY PERSONALLY APPEARED  
BRYAN SIMS KNOWN TO ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT, AND ACKNOWLEDGED TO ME THAT THEY EXECUTED THE SAME FOR THE PURPOSES AND CONSIDERATIONS THEREIN EXPRESSED AND IN THE CAPACITY THEREIN STATED. GIVEN UNDER MY HAND AND SEAL OF OFFICE THIS \_\_\_\_\_ DAY OF \_\_\_\_\_, A.D. \_\_\_\_\_.

\_\_\_\_\_  
NOTARY PUBLIC, BEXAR COUNTY, TEXAS



## AREAS BEING REPLATTED THROUGH PUBLIC HEARING WITH WRITTEN NOTIFICATION

14.68 ACRE AREA BEING REPLATTED WAS PREVIOUSLY PLATTED AS LOTS 1-12 & LOTS 19-20 & LOT 903 OPEN SPACE, BLOCK 273, COUNTY BLOCK 4450 OF THE McCRARRY TRACT SUBD., UNIT 6 PLAT RECORDED IN VOLUME 20002, PAGES 2010-2013 OF THE PLAT RECORDS OF BEXAR COUNTY, TEXAS.

PLAT NUMBER: 23-11800030


## REPLAT ESTABLISHING

### McCrarry Tract Subd., Unit 6A

14.68 ACRES OF LAND IN THE MARY SAVAGE SURVEY NO. 263, ABSTRACT NO. 690, COUNTY BLOCK 4465 AND THE D.S. ALVEY SURVEY NO. 5, ABSTRACT NO. 1038, COUNTY BLOCK 4484, BEXAR COUNTY, TEXAS AND BEING A PORTION OF A 26.60 ACRES OF LAND IN THE McCRARRY TRACT SUBD., UNIT 6 PLAT, RECORDED IN VOLUME 20002, PAGES 2010-2013 OF THE PLAT RECORDS OF BEXAR COUNTY, TEXAS.



SCALE: 1"=150'



M.W. CUDE ENGINEERS, L.L.C.  
4122 POND HILL RD. • S-101  
SAN ANTONIO, TEXAS 78231  
T:210.681.2951 • F:210.523.7112  
WWW.CUDEENGINEERS.COM  
TPELS #10048500 • T&PE FIRM #455  
[MWC: 02142.035.0]

14-RESIDENTIAL LOTS  
1-OPEN SPACE LOT

STATE OF TEXAS  
COUNTY OF BEXAR

THE OWNER OF LAND SHOWN ON THIS PLAT, IN PERSON OR THROUGH A DULY AUTHORIZED AGENT, DEDICATES TO THE USE OF THE PUBLIC, EXCEPT AREAS IDENTIFIED AS PRIVATE OR PART OF AN ENCLAVE OR PLANNED UNIT DEVELOPMENT, FOREVER ALL STREETS, ALLEYS, PARKS, WATERCOURSES, DRAINS, EASEMENTS AND PUBLIC PLACES THEREON SHOWN FOR THE PURPOSE AND CONSIDERATION THEREIN EXPRESSED.

OWNER/DEVELOPER  
PULTE HOMES OF TEXAS, L.P.  
A TEXAS LIMITED PARTNERSHIP  
1718 DRY CREEK WAY, SUITE 120  
SAN ANTONIO, TX 78259  
PHONE: (210) 496-1985  
FAX: (210) 496-0449  
CONTACT PERSON: SEAN MILLER  
BY: PULTE NEVADA I LLC, A DELAWARE LIMITED  
LIABILITY COMPANY, ITS GENERAL PARTNER

OWNER \_\_\_\_\_  
DULY AUTHORIZED AGENT \_\_\_\_\_

STATE OF TEXAS  
COUNTY OF BEXAR

BEFORE ME, THE UNDERSIGNED AUTHORITY ON THIS DAY PERSONALLY APPEARED  
SEAN MILLER KNOWN TO ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT, AND ACKNOWLEDGED TO ME THAT THEY EXECUTED THE SAME FOR THE PURPOSES AND CONSIDERATIONS THEREIN EXPRESSED AND IN THE CAPACITY THEREIN STATED. GIVEN UNDER MY HAND AND SEAL OF OFFICE THIS \_\_\_\_\_ DAY OF \_\_\_\_\_, A.D. \_\_\_\_\_.

\_\_\_\_\_  
NOTARY PUBLIC, BEXAR COUNTY, TEXAS

CERTIFICATE OF APPROVAL

THE UNDERSIGNED, COUNTY JUDGE OF BEXAR COUNTY, TEXAS, AND PRESIDING OFFICER OF THE COMMISSIONERS COURT OF BEXAR COUNTY, DOES HEREBY CERTIFY THAT THE ATTACHED PLAT WAS DULY FILED WITH THE COMMISSIONERS COURT OF BEXAR COUNTY, TEXAS AND THAT AFTER EXAMINATION IT APPEARED THAT SAID PLAT IS IN CONFORMITY WITH THE STATUTES, RULES AND REGULATIONS GOVERNING SAME, AND THIS PLAT WAS APPROVED BY THE SAID COMMISSIONERS COURT.

DATED THIS \_\_\_\_\_ DAY OF \_\_\_\_\_, A.D. \_\_\_\_\_.

\_\_\_\_\_  
COUNTY JUDGE, BEXAR COUNTY, TEXAS


\_\_\_\_\_  
COUNTY CLERK, BEXAR COUNTY, TEXAS

THIS PLAT OF McCrarry Tract Subd., Unit 6A HAS BEEN SUBMITTED TO AND CONSIDERED BY THE PLANNING COMMISSION OF THE CITY OF SAN ANTONIO, TEXAS, AND IS HEREBY APPROVED BY SUCH COMMISSION IN ACCORDANCE WITH STATE OR LOCAL LAWS AND REGULATIONS; AND/OR WHERE ADMINISTRATIVE EXCEPTION(S) AND/OR VARIANCE(S) HAVE BEEN GRANTED.

DATED THIS \_\_\_\_\_ DAY OF \_\_\_\_\_, A.D. \_\_\_\_\_.

BY: \_\_\_\_\_ CHAIRMAN

BY: \_\_\_\_\_ SECRETARY



**LEGEND**

- Ac. = ACRES
- B.S.L. = BUILDING SETBACK LINE
- C1 = CURVE NUMBER
- C.B. = COUNTY BLOCK
- DRN. = DRAINAGE
- E.G.T.CA. = ELECTRIC, GAS, TELEPHONE AND CABLE TELEVISION
- ESMT. = EASEMENT
- N.T.S. = NOT TO SCALE
- L1 = LINE NUMBER
- L.S. = LINE SETBACK
- O.H.E. = OVERHEAD ELECTRIC
- O.P.R. = OFFICIAL PUBLIC RECORDS OF BEXAR COUNTY, TEXAS
- PGS. = PAGE
- PGS. = PAGES
- P.R. = PLAT RECORDS OF BEXAR COUNTY, TEXAS
- R.O.W. = RIGHT-OF-WAY
- VAR. = VARIABLE
- VOL. = VOLUME
- WID. = WIDTH
- +— = STREET CENTERLINE
- +— = BUILDING SETBACK LINE
- +— = PROPERTY LINE
- +— = EXTRATERRITORIAL JURISDICTION LIMITS
- +— = UNIT BOUNDARY NODE
- +— = MINIMUM PAD FINISHED FLOOR ELEVATION

**KEYNOTES**

1	10' E.G.T.CA. ESM'T. (VOL. 20002, PGS. 1340-1343, P.R.)
2	10' E.G.T.CA. ESM'T. (VOL. 20002, PGS. 2010-2013, P.R.)
3	20' B.S.L. (VOL. 20002, PGS. 2010-2013, P.R.)
4	10' E.G.T.CA. ESM'T. & B.S.L. (VOL. 20002, PGS. 2010-2013, P.R.)
5	28' O.H.E. ESM'T. (VOL. 20002, PGS. 2010-2013, P.R.)
6	± 145' TO INTERSECTION OF LONG RIDER & BLUE FEATHER
7	± 375' TO INTERSECTION OF SNOWY RIVER & GREY FOX

STATE OF TEXAS  
COUNTY OF BEXAR

THE OWNER OF LAND SHOWN ON THIS PLAT, IN PERSON OR THROUGH A DULY AUTHORIZED AGENT, DEDICATES TO THE USE OF THE PUBLIC, EXCEPT AREAS IDENTIFIED AS PRIVATE OR PART OF AN ENCLAVE OR PLANNED UNIT DEVELOPMENT, FOREVER ALL STREETS, ALLEYS, PARKS, WATERCOURSES, DRAINS, EASEMENTS AND PUBLIC PLACES THEREON SHOWN FOR THE PURPOSE AND CONSIDERATION THEREIN EXPRESSED.

OWNER/ DEVELOPER  
DAVIS RANCH HOMEOWNERS ASSOCIATION INC  
C/O LITTE HCA MANAGEMENT  
18585 SIGMA ROAD #104  
SAN ANTONIO, TX 78258  
PHONE: (210) 838 - 6784  
CONTACT PERSON: BRYAN SIMS

BY: \_\_\_\_\_  
NAME: \_\_\_\_\_  
TITLE: \_\_\_\_\_

STATE OF TEXAS  
COUNTY OF BEXAR

BEFORE ME, THE UNDERSIGNED AUTHORITY ON THIS DAY PERSONALLY APPEARED  
BRYAN SIMS KNOWN TO ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT, AND ACKNOWLEDGED TO ME THAT THEY EXECUTED THE SAME FOR THE PURPOSES AND CONSIDERATIONS THEREIN EXPRESSED AND IN THE CAPACITY THEREIN STATED. GIVEN UNDER MY HAND AND SEAL OF OFFICE THIS \_\_\_\_\_ DAY OF \_\_\_\_\_, A.D. \_\_\_\_\_

NOTARY PUBLIC, BEXAR COUNTY, TEXAS

STATE OF TEXAS  
COUNTY OF BEXAR

I HEREBY CERTIFY THAT PROPER ENGINEERING CONSIDERATION HAS BEEN GIVEN THIS PLAT TO THE MATTERS OF STREETS, LOTS, AND DRAINAGE LAYOUT. TO THE BEST OF MY KNOWLEDGE THIS PLAT CONFORMS TO ALL REQUIREMENTS OF THE UNIFIED DEVELOPMENT CODE, EXCEPT FOR THOSE VARIANCES GRANTED BY THE SAN ANTONIO PLANNING COMMISSION.

M.W. CUDE ENGINEERS, L.L.C.  
ANDREW R. LOWRY, P.E.

\_\_\_\_\_  
LICENSED PROFESSIONAL ENGINEER

STATE OF TEXAS  
COUNTY OF BEXAR

I HEREBY CERTIFY THAT THE ABOVE PLAT CONFORMS TO THE MINIMUM STANDARDS SET FORTH BY THE TEXAS BOARD OF PROFESSIONAL ENGINEERS AND LAND SURVEYORS ACCORDING TO AN ACTUAL SURVEY MADE ON THE GROUND BY:

M.W. CUDE ENGINEERS, L.L.C.  
YURI V. BALMACEA WHEELLOCK, R.P.L.S.

\_\_\_\_\_  
REGISTERED PROFESSIONAL LAND SURVEYOR

**SURVEYOR'S NOTES:**

- ALL PROPERTY CORNERS SHOWN HEREON ARE SET 1/2" REBAR WITH PLASTIC SURVEYOR'S CAP STAMPED "CUDE" UNLESS OTHERWISE NOTED.
- COORDINATES SHOWN HEREON ARE TEXAS SOUTH CENTRAL ZONE (4204 TXSC) STATE PLANE GRID COORDINATES, NORTH AMERICAN DATUM OF 1983 (2011) AS DERIVED FROM THE NGS/CORS NETWORK. DISTANCES SHOWN HEREON ARE GROUND DISTANCES MEASURED IN U.S. SURVEY FEET.
- BEARINGS SHOWN HEREON ARE BASED ON THE TEXAS SOUTH CENTRAL ZONE (4204 TXSC) STATE PLANE GRID, NORTH AMERICAN DATUM OF 1983 (2011).

**SAWS NOTES:**

- THE NUMBER OF WASTEWATER EQUIVALENT DWELLING UNITS (EDU'S) PAID FOR THIS SUBDIVISION PLAT ARE KEPT ON FILE UNDER THE PLAT NUMBER AT THE SAN ANTONIO WATER SYSTEM.
- IMPACT FEE NOTE: WATER AND/OR WASTEWATER IMPACT FEES WERE NOT PAID AT THE TIME OF PLATING FOR THIS PLAT. ALL IMPACT FEES MUST BE PAID PRIOR TO WATER METER SET AND/OR WASTEWATER SERVICE CONNECTION.
- THE DEVELOPER DEDICATES THE SANITARY SEWER AND/OR WATER MAINS TO THE SAN ANTONIO WATER SYSTEM UPON COMPLETION BY THE DEVELOPER AND ACCEPTANCE BY THE SAN ANTONIO WATER SYSTEM.
- IN AN EFFORT TO MEET THE CITY OF SAN ANTONIO'S FIRE FLOW REQUIREMENTS FOR THE PROPOSED RESIDENTIAL DEVELOPMENT, THE PUBLIC WATER MAIN SYSTEM HAS BEEN DESIGNED FOR A MINIMUM FIRE FLOW DEMAND OF 1,750 G.P.M. AT 25 P.S.I. RESIDUAL PRESSURE. THE FIRE FLOW REQUIREMENTS FOR INDIVIDUAL STRUCTURES WILL BE REVIEWED DURING THE BUILDING PERMIT PROCESS IN ACCORDANCE WITH THE PROCEDURES SET FORTH BY THE CITY OF SAN ANTONIO DIRECTOR OF DEVELOPMENT SERVICES AND THE SAN ANTONIO FIRE DEPARTMENT FIRE MARSHAL.
- THE SAN ANTONIO WATER SYSTEM IS HEREBY GRANTED THE RIGHT OF INGRESS AND EGRESS ACROSS GRANTOR'S ADJACENT PROPERTY TO ACCESS THE WATER EASEMENT(S) SHOWN ON THIS PLAT.
- THE SAN ANTONIO WATER SYSTEM IS HEREBY GRANTED THE RIGHT OF INGRESS AND EGRESS ACROSS GRANTOR'S ADJACENT PROPERTY TO ACCESS THE WASTEWATER EASEMENT(S) SHOWN ON THIS PLAT.
- SAN ANTONIO WATER SYSTEM HIGH PRESSURE NOTE:  
A PORTION OF THIS TRACT IS BELOW THE GROUND ELEVATION OF 985 FEET, WHERE THE STATIC PRESSURE WILL NORMALLY EXCEED 80 P.S.I. AT ALL SUCH LOCATIONS, THE DEVELOPER OR BUILDER SHALL INSTALL AT EACH LOT, ON THE CUSTOMER'S SIDE OF THE METER, AN APPROVED TYPE PRESSURE REGULATOR IN CONFORMANCE WITH THE PLUMBING CODE OF THE CITY OF SAN ANTONIO.

**CPS/SAWS/COSA UTILITY NOTES:**

- THE CITY OF SAN ANTONIO AS PART OF ITS ELECTRIC, GAS, WATER, AND WASTEWATER SYSTEMS - CITY PUBLIC SERVICE BOARD (CPS ENERGY) AND SAN ANTONIO WATER SYSTEM (SAWS) - IS HEREBY DEDICATED EASEMENTS AND RIGHTS-OF-WAY FOR UTILITY, TRANSMISSION AND DISTRIBUTION INFRASTRUCTURE AND SERVICE FACILITIES IN THE AREAS DESIGNATED ON THIS PLAT AS "ELECTRIC EASEMENT," "ANCHOR EASEMENT," "SERVICE EASEMENT," "OVERHANG EASEMENT," "UTILITY EASEMENT," "GAS EASEMENT," "TRANSFORMER EASEMENT," "WATER EASEMENT," "SANITARY SEWER EASEMENT" AND/OR "RECYCLED WATER EASEMENT" FOR THE PURPOSE OF INSTALLING, CONSTRUCTING, RECONSTRUCTING, MAINTAINING, REMOVING, INSPECTING, PATROLLING, AND ERECTING UTILITY INFRASTRUCTURE AND SERVICE FACILITIES FOR THE REASONS DESCRIBED ABOVE. CPS ENERGY AND SAWS SHALL ALSO HAVE THE RIGHT TO RELOCATE SAID INFRASTRUCTURE AND SERVICE FACILITIES WITHIN EASEMENT AND RIGHT-OF-WAY AREAS, TOGETHER WITH THE RIGHT OF INGRESS AND EGRESS OVER GRANTOR'S ADJACENT LANDS FOR THE PURPOSE OF ACCESSING SUCH INFRASTRUCTURE AND SERVICE FACILITIES AND THE RIGHT TO REMOVE FROM SAID LANDS ALL TREES OR PARTS THEREOF, OR OTHER OBSTRUCTIONS WHICH ENDANGER OR MAY INTERFERE WITH THE EFFICIENCY OF WATER, SEWER, GAS, AND/OR ELECTRIC INFRASTRUCTURE AND SERVICE FACILITIES. NO BUILDINGS, STRUCTURES, CONCRETE SLABS, OR WALLS WILL BE PLACED WITHIN EASEMENT AREAS WITHOUT AN ENCROACHMENT AGREEMENT WITH THE RESPECTIVE UTILITY.
- ANY CPS ENERGY OR SAWS MONETARY LOSS RESULTING FROM MODIFICATIONS REQUIRED OF CPS ENERGY OR SAWS INFRASTRUCTURE AND SERVICE FACILITIES, LOCATED WITHIN SAID EASEMENTS, DUE TO GRADE CHANGES OR GROUND ELEVATION ALTERATIONS SHALL BE CHARGED TO THE PERSON OR PERSONS DEEMED RESPONSIBLE FOR SAID GRADE CHANGES OR GROUND ELEVATION ALTERATIONS.
- THIS PLAT DOES NOT AMEND, ALTER, RELEASE OR OTHERWISE AFFECT ANY EXISTING ELECTRIC, GAS, WATER, SEWER, DRAINAGE, TELEPHONE, CABLE EASEMENTS OR ANY OTHER EASEMENTS FOR UTILITIES UNLESS THE CHANGES TO SUCH EASEMENTS ARE DESCRIBED HEREON.
- CONCRETE DRIVEWAY APPROACHES ARE ALLOWED WITHIN THE FIVE (5) AND TEN (10) FOOT WIDE ELECTRIC AND GAS EASEMENTS WHEN LOTS ARE SERVED ONLY BY UNDERGROUND ELECTRIC AND GAS FACILITIES.
- ROOF OVERHANGS ARE ALLOWED WITHIN THE FIVE (5) AND TEN (10) FOOT WIDE ELECTRIC AND GAS EASEMENTS WHEN ONLY UNDERGROUND ELECTRIC AND GAS FACILITIES ARE PROPOSED OR EXISTING WITHIN THOSE FIVE (5) AND TEN (10) FOOT WIDE EASEMENTS.

**TREE NOTE:**



- THIS SUBDIVISION IS SUBJECT TO A MASTER TREE PLAN (TRE-APP-APP22-38801000) AND A MASTER TREE PLAN (TRE-APP-APP-21-38801076) WHICH REQUIRES COMPLIANCE BY THE OWNERS OF ALL PROPERTY WITHIN THE PLAT BOUNDARY, AND THEIR EMPLOYEES AND CONTRACTORS, AND SHALL BE BINDING ON ALL SUCCESSORS IN TITLE EXCEPT FOR OWNERS OF SINGLE-FAMILY RESIDENTIAL LOTS SUBDIVIDED HEREUNDER FOR WHICH CONSTRUCTION OF A RESIDENTIAL STRUCTURE HAS BEEN COMPLETED. THE MASTER TREE PLAN IS ON FILE AT THE CITY OF SAN ANTONIO ARBORIST OFFICE. NO TREES OR UNDERSTORY SHALL BE REMOVED WITHOUT PRIOR APPROVAL OF THE CITY ARBORIST OFFICE PER 35-477(H).

**DRAINAGE NOTE:**

- NO STRUCTURE, FENCES, WALLS OR OTHER OBSTRUCTIONS THAT IMPEDE DRAINAGE SHALL BE PLACED WITHIN THE LIMITS OF THE DRAINAGE EASEMENTS SHOWN ON THIS PLAT. NO LANDSCAPING OR OTHER TYPE OF MODIFICATIONS, WHICH ALTER THE CROSS-SECTIONS OF THE DRAINAGE EASEMENT, AS APPROVED, SHALL BE ALLOWED WITHOUT THE APPROVAL OF THE DIRECTOR OF PUBLIC WORKS. THE CITY OF SAN ANTONIO AND BEXAR COUNTY SHALL HAVE THE RIGHT TO INGRESS AND EGRESS OVER GRANTOR'S ADJACENT PROPERTY TO REMOVE ANY IMPEDING OBSTRUCTIONS PLACED WITHIN THE LIMITS OF SAID DRAINAGE EASEMENTS AND TO MAKE ANY MODIFICATIONS OR IMPROVEMENTS WITHIN SAID DRAINAGE EASEMENTS.
- LOT 904, BLOCK 273, C.B. 4450 LIES WITHIN THE FEMA 1% ANNUAL CHANCE (100-YR) FLOODPLAIN AS VERIFIED BY FEMA MAP PANEL: 48029C0215G, DATED SEPTEMBER 29, 2010. A FEMA CLOMR FLOODPLAIN STUDY HAS BEEN PREPARED BY CUDE ENGINEERS AND WAS APPROVED BY THE CITY OF SAN ANTONIO AND BEXAR COUNTY. THE FLOODPLAIN STUDY (FEMA CASE NO. 21-06-0206R) IS PENDING APPROVAL BY FEMA. FLOODPLAIN INFORMATION IS SUBJECT TO CHANGE AS A RESULT OF FUTURE FEMA MAP REVISIONS AND/OR AMENDMENTS.
- THE DRAINAGE EASEMENTS WERE DELINEATED TO CONTAIN THE LESSER OF HTE BOUNDARIES OF THE 1% ANNUAL CHANCE (100-YR) FLOOD ZONE ESTABLISHED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY (FEMA) IN ACCORDANCE WITH THE DFIRM PANEL 48029C0215G, DATED SEPTEMBER 29, 2010, OR THE 1% ANNUAL CHANCE (100-YR) ULTIMATE DEVELOPMENT CONDITION WATER SURFACE ELEVATION. CONSTRUCTION, IMPROVEMENTS, OR STRUCTURES WITHIN THE DRAINAGE EASEMENTS AND FLOODPLAIN ARE PROHIBITED WITHOUT PRIOR WRITTEN APPROVAL FROM THE FLOODPLAIN ADMINISTRATOR OF THE CITY OF SAN ANTONIO OR BEXAR COUNTY.

**MISCELLANEOUS NOTES:**

- RESIDENTIAL FINISHED FLOOR ELEVATIONS MUST BE A MINIMUM OF EIGHT INCHES ABOVE FINISHED ADJACENT GRADE. A GRADING PLAN SHALL BE PREPARED WHICH INDICATES A DRAINAGE PLAN FOR ALL LOTS IN THE SUBDIVISION.
- FINISHED FLOOR ELEVATIONS FOR STRUCTURES ON LOTS CONTAINING FLOODPLAIN OR ADJACENT TO THE FLOODPLAIN SHALL BE IN COMPLIANCE WITH THE FLOODPLAIN REGULATION IN EFFECT AT TIME OF CONSTRUCTION. CONTACT BEXAR COUNTY PUBLIC WORKS FOR MORE INFORMATION.
- SETBACKS IMPOSED ON THIS PLAT ARE AT THE DISCRETION OF THE DEVELOPER OR BEXAR COUNTY AND ARE NOT SUBJECT TO ENFORCEMENT BY THE CITY OF SAN ANTONIO.
- THE MAINTENANCE OF ALL PRIVATE STREETS, OPEN SPACE, GREENBELTS, PARKS, TREE SAVE AREAS, INCLUDING LOT 904, BLOCK 273, C.B. 4450, DRAINAGE EASEMENTS AND EASEMENTS OF ANY OTHER NATURE WITHIN THIS SUBDIVISION SHALL BE THE RESPONSIBILITY OF THE PROPERTY OWNERS, OR THE PROPERTY OWNERS' ASSOCIATION, OR ITS SUCCESSORS OR ASSIGNS AND NOT THE RESPONSIBILITY OF THE CITY OF SAN ANTONIO OR BEXAR COUNTY.
- LOT 904, BLOCK 273, C.B. 4450, IS DESIGNATED AS OPEN SPACE AND AS A COMMON AREA AND A PUBLIC DRAINAGE EASEMENT.



**PLAT NUMBER: 23-11800030**

**REPLAT  
ESTABLISHING  
MCCRARY TRACT SUBD., UNIT 6A**

14.68 ACRES OF LAND IN THE MARY SAVAGE SURVEY NO. 263, ABSTRACT NO. 690, COUNTY BLOCK 4465 AND THE D.S. ALVEY SURVEY NO. 5, ABSTRACT NO. 1038, COUNTY BLOCK 4484, BEXAR COUNTY, TEXAS AND BEING A PORTION OF A 26.60 ACRES OF LAND IN THE MCCRARY TRACT SUBD., UNIT 6 PLAT, RECORDED IN VOLUME 20006, PAGES 2010-2013 OF THE PLAT RECORDS OF BEXAR COUNTY, TEXAS.

**CUDE**  
M.W. CUDE ENGINEERS, L.L.C.  
4122 POND HILL RD. • S-101  
SAN ANTONIO, TEXAS 78231  
T:210.681.2951 • F:210.523.7112  
WWW.CUDEENGINEERS.COM  
TPELS #10048500 • TSP# FIRM #455  
(MWC: 02142.035.0)

**14-RESIDENTIAL LOTS  
1-OPEN SPACE LOT**

STATE OF TEXAS  
COUNTY OF BEXAR

THE OWNER OF LAND SHOWN ON THIS PLAT, IN PERSON OR THROUGH A DULY AUTHORIZED AGENT, DEDICATES TO THE USE OF THE PUBLIC, EXCEPT AREAS IDENTIFIED AS PRIVATE OR PART OF AN ENCLAVE OR PLANNED UNIT DEVELOPMENT, FOREVER ALL STREETS, ALLEYS, PARKS, WATERCOURSES, DRAINS, EASEMENTS AND PUBLIC PLACES THEREON SHOWN FOR THE PURPOSE AND CONSIDERATION THEREIN EXPRESSED.

OWNER/ DEVELOPER  
PULTE HOMES OF TEXAS, L.P.  
A TEXAS LIMITED PARTNERSHIP  
1718 DRY CREEK WAY, SUITE 120  
SAN ANTONIO, TX 78259  
PHONE: (210) 496-1985  
FAX: (210) 496-0449  
CONTACT PERSON: SEAN MILLER  
BY: PULTE NEVADA I LLC, A DELAWARE LIMITED LIABILITY COMPANY, ITS GENERAL PARTNER

BY: \_\_\_\_\_  
NAME: \_\_\_\_\_  
TITLE: \_\_\_\_\_

STATE OF TEXAS  
COUNTY OF BEXAR

BEFORE ME, THE UNDERSIGNED AUTHORITY ON THIS DAY PERSONALLY APPEARED  
SEAN MILLER KNOWN TO ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT, AND ACKNOWLEDGED TO ME THAT THEY EXECUTED THE SAME FOR THE PURPOSES AND CONSIDERATIONS THEREIN EXPRESSED AND IN THE CAPACITY THEREIN STATED. GIVEN UNDER MY HAND AND SEAL OF OFFICE THIS \_\_\_\_\_ DAY OF \_\_\_\_\_, A.D. \_\_\_\_\_

NOTARY PUBLIC, BEXAR COUNTY, TEXAS

**CERTIFICATE OF APPROVAL**

THE UNDERSIGNED, COUNTY JUDGE OF BEXAR COUNTY, TEXAS, AND PRESIDING OFFICER OF THE COMMISSIONERS COURT OF BEXAR COUNTY, DOES HEREBY CERTIFY THAT THE ATTACHED PLAT WAS DULY FILED WITH THE COMMISSIONERS COURT OF BEXAR COUNTY, TEXAS AND THAT AFTER EXAMINATION IT APPEARED THAT SAID PLAT IS IN CONFORMITY WITH THE STATUTES, RULES AND REGULATIONS GOVERNING SAME, AND THIS PLAT WAS APPROVED BY THE SAID COMMISSIONERS COURT.

DATED THIS \_\_\_\_\_ DAY OF \_\_\_\_\_, A.D. \_\_\_\_\_

\_\_\_\_\_  
COUNTY JUDGE, BEXAR COUNTY, TEXAS


\_\_\_\_\_  
COUNTY CLERK, BEXAR COUNTY, TEXAS

THIS PLAT OF MCCRARY TRACT SUBD., UNIT 6A HAS BEEN SUBMITTED TO AND CONSIDERED BY THE PLANNING COMMISSION OF THE CITY OF SAN ANTONIO, TEXAS, AND IS HEREBY APPROVED BY SUCH COMMISSION IN ACCORDANCE WITH STATE OR LOCAL LAWS AND REGULATIONS; AND/OR WHERE ADMINISTRATIVE EXCEPTION(S) AND/OR VARIANCE(S) HAVE BEEN GRANTED.

DATED THIS \_\_\_\_\_ DAY OF \_\_\_\_\_, A.D. \_\_\_\_\_

BY: \_\_\_\_\_ CHAIRMAN

BY: \_\_\_\_\_ SECRETARY



CPS/SAWS/COSA UTILITY NOTES:

1. THE CITY OF SAN ANTONIO AS PART OF ITS ELECTRIC, GAS, WATER, AND WASTEWATER SYSTEMS - CITY PUBLIC SERVICE BOARD (CPS ENERGY AND SAN ANTONIO WATER SYSTEM (SAWS)) - IS HEREBY DEDICATING AND EASEMENTING THE FOLLOWING DESCRIBED PROPERTY TO THE CITY OF SAN ANTONIO FOR DISTRIBUTION INFRASTRUCTURE AND SERVICE FACILITIES IN THE AREAS DESIGNATED ON THIS PLAN AS "ELECTRIC EASEMENT," "ANCHOR EASEMENT," "SERVICE EASEMENT," "OVERHEAD GAS EASEMENT," "UTILITY EASEMENT," "GAS EASEMENT," "TRANSFORMER EASEMENT," "WATER EASEMENT," "SANITARY SEWER EASEMENT" AND "RECYCLED WATER EASEMENT" FOR THE PURPOSE OF INSTALLING, CONSTRUCTING, RECONSTRUCTING, MAINTAINING, REMOVING, INSPECTING, PATROLLING, AND ERECTING UTILITY INFRASTRUCTURE AND SERVICE FACILITIES AND FOR ANY REASONS DEEMED REASONABLE BY THE CITY OF SAN ANTONIO. THE CITY OF SAN ANTONIO WILL RELOCATE SAID INFRASTRUCTURE AND SERVICE FACILITIES WITHIN EASEMENT AND RIGHT-OF-WAY AREAS, TOGETHER WITH THE RIGHT OF INGRESS AND EGRESS OVER GRANTOR'S ADJACENT LANDS FOR THE PURPOSE OF ACCESSING SUCH INFRASTRUCTURE AND SERVICE FACILITIES. THE RIGHT OF THE CITY OF SAN ANTONIO TO ACCESS SUCH INFRASTRUCTURE OR OTHER OBSTRUCTIONS WHICH ENDANGER OR MAY INTERFERE WITH THE EFFICIENCY OF WATER, SEWER, GAS, AND/OR ELECTRIC INFRASTRUCTURE AND SERVICE FACILITIES. NO BUILDINGS, STRUCTURES, CONCRETE SLABS, OR WALLS WILL BE PLACED WITHIN EASEMENT AREAS WITHOUT AN ENCROACHMENT AGREEMENT WITH THE RESPECTIVE UTILITY.

2. ANY CPS ENERGY OR SAWS MONETARY LOSS RESULTING FROM MODIFICATIONS REQUIRED OF CPS ENERGY OR SAWS INFRASTRUCTURE AND SERVICE FACILITIES, LOCATED WITHIN SAID EASEMENTS, DUE TO THE RELOCATION OF SUCH INFRASTRUCTURE AND SERVICE FACILITIES, OR CHARGED TO THE PERSON OR PERSONS DEEMED RESPONSIBLE FOR SAID GRADE CHANGES OR GROUND ELEVATION ALTERATIONS.

3. THIS PLAN DOES NOT AMEND, ALTER, RELEASE OR OTHERWISE AFFECT ANY EXISTING ELECTRIC, GAS, WATER, SEWER, OR WASTEWATER EASEMENTS OR ANY OTHER EASEMENTS FOR UTILITIES UNLESS THE CHANGES TO SUCH EASEMENTS ARE DESCRIBED HEREIN.


4. CONCRETE DRIVEWAY APPROACHES ARE ALLOWED WITHIN THE FIVE (5) AND TEN (10) FOOT WIDE ELECTRIC AND GAS EASEMENTS WHEN LOTS ARE SERVED ONLY BY UNDERGROUND ELECTRIC AND GAS UTILITIES.

5. ROOF OVERHANGS ARE ALLOWED WITHIN THE FIVE (5) AND TEN (10) FOOT WIDE ELECTRIC AND GAS EASEMENTS WHEN ONLY UNDERGROUND ELECTRIC AND GAS FACILITIES ARE PROPOSED OR EXISTING WITHIN THE FIVE (5) AND TEN (10) FOOT WIDE EASEMENTS.

TRUE NOTE:

1. THIS SUBDIVISION IS SUBJECT TO A MASTER TRAP-TIE (TRAP-APP-APP-38801000) AND A MASTER TRAP-TIE PLAN (TRAP-TIE-APP-21-3880100) WHICH REQUIRES PLACEMENT OF THE CHIMNEYS OF ALL PLUMBING WITHIN THE PROPERTY BOUNDARY AND THE TRAP-TIE AND TRAP-TIE-38801000 MUST BE BINDING ON ALL SUCCESSORS IN TITLE EXCEPT FOR OWNERS OF SINGLE-FAMILY RESIDENTIAL LOTS SUBDIVIDED HEREUNDER FOR WHICH CONSTRUCTION OF A RESIDENTIAL STRUCTURE HAS NOT YET BEEN INITIATED. THERE WILL BE NO TRAP-TIE PLANS FILED WITH THE SAN ANTONIO ARCHITECTURAL BOARD. NO TREES OR UNDERSTORY SHALL BE REMOVED WITHOUT PRIOR APPROVAL OF THE CITY ARCHITECT OFFICE PER 35-477(H).

CURVE TABLE					
CURVE	RADIUS	DELTA	LENGTH	CHORD BEARING	CHORD
C1	920.00'	40°55'58"	657.26'	S19°04'21"W	643.37'
C2	10.00'	90°00'00"	15.71'	N68°55'18"E	14.14'
C3	125.00'	50°13'13"	109.56'	N01°11'19"W	106.09'



STATE OF TEXAS  
COUNTY OF BEXAR

THE OWNER OF LAND SHOWN ON THIS PLAT, IN PERSON OR THROUGH A DULY AUTHORIZED AGENT, DESIGNATES TO THE USE OF THE PUBLIC, EXCEPT AREAS IDENTIFIED AS PRIVATE OR PART OF AN ENCLAVE OR PLANNED UNIT DEVELOPMENT, FOREVER ALL STREETS, ALLEYS, PARKS, WATERCOURSES, DRAINS, EASEMENTS AND PUBLIC PLACES THEREON SHOWN FOR THE PURPOSE AND CONSIDERATION THEREIN EXPRESSED.

OWNER/ DEVELOPER  
PULTE HOMES OF TEXAS, L.P.  
A TEXAS LIMITED PARTNERSHIP  
1718 DRY CREEK WAY, SUITE 120  
SAN ANTONIO, TX 78259  
PHONE: (210) 496-1985  
FAX: (210) 496-0449  
CONTACT PERSON: SEAN MILLER  
BY: PULTE NEVADA I LLC, A DELAWARE LIMITED  
LIABILITY COMPANY, ITS GENERAL PARTNER

BY: \_\_\_\_\_  
NAME: \_\_\_\_\_  
TITLE: \_\_\_\_\_

STATE OF TEXAS  
COUNTY OF BEXAR

BEFORE ME, THE UNDERSIGNED AUTHORITY ON THIS DAY PERSONALLY APPEARED SEAN MILLER, KNOWN TO ME TO BE THE PERSON WHOSE NAME IS SUBSCRIBED TO THE FOREGOING INSTRUMENT, AND ACKNOWLEDGED TO ME THAT THEY EXECUTED THE SAME FOR THE PURPOSES AND CONSIDERATIONS THEREIN EXPRESSED AND IN THE CAPACITY THEREIN STATED. GIVEN UNDER MY HAND AND SEAL OF OFFICE THIS \_\_\_\_\_ DAY OF \_\_\_\_\_ A.D. \_\_\_\_\_

2.

\_\_\_\_\_  
NOTARY PUBLIC, BEXAR COUNTY, TEXAS

COUNTY CLERK, BEXAR COUNTY, TEXAS

BY: \_\_\_\_\_  
SECRETARY